

## CONCEPTUAL DESIGN REPORT NO. 2

(DRAFT)

PROJECT NO.: 0257-027-02 DATE: NOVEMBER 2004 DISTRIBUTION LIST: DELOITTE AND TOUCHE BGC CALGARY

1 E-COPY 1 COPY



Re: Faro Pit Plug Dam- Conceptual Design Report No. 2

#### Dear Doug:

The above referenced draft report has been uploaded to the Deloitte & Touche Inc. e-room. This report presents our revised conceptual design for the Faro Pit Plug Dam. The conceptual design has been revised on the basis of new site specific information that has been gathered in 2004. The new information includes the results of a preliminary field investigation for borrow material and drilling at the Plug Dam site and the Faro Creek site. This draft report has been issued for your comment and review as part of the next phase of Faro Mine closure planning. Once your, and the regulatory reviewers, comments are received the report will be issued in final form.

We trust that this information meets with your requirements at this time. Should you have any questions or comments, please do not hesitate to contact me at the number listed above.

Yours truly,

**BGC** Engineering Inc.

per:

Gerry Ferris, M.Sc., P.Eng. Geotechnical Engineer

GWF/slf

Attached: Draft Report

## **TABLE OF CONTENTS**

1.0	Intro	duction	4					
	1.1							
	1.2	Scope of Work and Authorization to Proceed	4					
	1.3	Site Survey Datum	4					
2.0	Background Information 2.1 Location 2.2 Geology							
	2.1	Location	4					
	2.2	Geology	4					
3.0	Eiold	Unvestigation	1					
3.0	Field Investigation							
	3.2		Reconnaissance4					
	3.3	Drilling						
	5.5	3.3.1 ODEX Drilling						
		3.3.2 Diamond Drilling						
	3.4	Hydraulic Conductivity Testing						
	0.1	3.4.1 Rising/Falling Head tests						
		3.4.2 Packer Tests						
	3.5	Test pit Investigation						
	0.0	3.5.1 Test pit Excavation						
		3.5.2 Surface Sampling						
	3.6	Geophysics						
	3.7	. ,						
		3.7.1 Maximum Reservoir Elevation						
		3.7.2 Hydraulic Conductivity – Plug Dam Area						
		3.7.3 Hydraulic Conductivity – Faro Creek Area						
4.0	Revi	sed Conceptual Design	4					
	4.1	General						
	4.2	Embankment Section and Construction	4					
		4.2.1 Zone 1 Impervious Earth Fill	4					
		4.2.2 Zone 2 Filter						
		4.2.3 Zone 3 Rockfill	4					
	4.3	Seepage Assessment						
5.0	Quar	Quantities and Cost Estimate						
		5.1.1 Excavation	4					
		5.1.1.1 Bulk Overburden Excavation and Stripping	4					
		5.1.1.2 Core Trench Rock Excavation						
		5.1.2 Foundation Preparation	4					
		5.1.3 Foundation Grouting	4					

	E 4 0 4 O annually letting Operation	,			
	5.1.3.1 Consolidation Grouting				
	5.1.3.2 Curtain Grouting				
	5.1.4 Embankment Materials	4			
6.0 Cor	nclusions and Recommendations	4			
7.0 Clo	sure	4			
Bibliograp	ohy	4			
	PHOTOGRAPHS Figures				
	riguics				
Figure 1	Site Location Plan				
Figure 2	Aerial Photograph Showing Current Site Conditions				
Figure 3	General Site Plan				
Figure 4	Dam Site Geology Plan				
Figure 5	Faro Creek Geology Plan				
Figure 6	Detailed Site Plan – Plug Dam				
Figure 7	Detailed Site Plan – Faro Creek				
Figure 8	Surface sampling				
Figure 9	Representative Cross Sections				
Figure 10	Faro Storage Capacity Curve				
Figure 12	Conceptual Plug Dam Section				
	TABLES				
Table 1 Liv	draulic Conductivity Data	4			
-	draulic Conductivity Dataro Pit Plug Dam Construction Cost Estimate				
i able z Fal	TO FIL Flug Dam Construction Cost Estimate	4			
	APPENDICES				

Appendix I – Borehole Logs

Appendix II - Hydraulic Conductivity Testing

Appendix III - Laboratory Testing Results

Appendix IV – Geophysics

#### LIMITATIONS OF REPORT

This report was prepared by BGC Engineering Inc. (BGC) for the account of Deloitte and Touche Inc., Interim Receiver for Anvil Range Mining Corporation. The material in it reflects the judgement of BGC staff in light of the information available to BGC at the time of report preparation. Any use which a Third Party makes of this report, or any reliance on decisions to be based on it are the responsibility of such Third Parties. BGC Engineering Inc. accepts no responsibility for damages, if any, suffered by any Third Party as a result of decisions made or actions based on this report.

As a mutual protection to our client, the public, and ourselves, all reports and drawings are submitted for the confidential information of our client for a specific project and authorization for use and / or publication of data, statements, conclusions or abstracts from or regarding our reports and drawings is reserved pending our written approval.

#### 1.0 INTRODUCTION

#### 1.1 Background and Study Objective

Previously a conceptual design report for the in-pit plug dam (the "Plug Dam") was prepared by BGC Engineering Inc. (BGC 2004). That report was prepared on the basis of existing information combined with a visual inspection of the Plug Dam abutment areas. This "Conceptual Design Report No. 2" describes data collection in the area of the Plug Dam and the former Faro Creek channel. The results of this investigation have been used to update the conceptual design of the Plug Dam

The Plug Dam may be necessary as part of mine closure, however a final decision has not yet been made. The purpose of the Plug Dam would be to retain pit water (and possibly tailings solids and/or waste rock) within the main open pit and prevent overflow and/or seepage from entering the adjacent Zone II Pit, located to the south. Currently no definition of the required additional storage volume in the Faro Pit has been provided. Therefore the conceptual design of the Plug Dam has been prepared on the basis of maximizing the water level in the Faro pit, and maintaining "reasonable" costs for construction. Once storage requirements for the pit are better defined the Plug Dam concept should be reassessed. Closure planning meetings are planned for the beginning of 2005 where decisions related to storage requirements and overall closure concepts will be made.

When the water elevation in the Zone II Pit rises above about 1094 m amsl it flows through the waste rock towards the north fork of Rose Creek. At lower water elevations seepage through the rock occurs. The water level within the Zone II Pit is controlled by pumping the water that collects in its base back to the main pit. The Zone II pump is operated in the range of 1074 to 1079 m amsl so the water level is maintained below these elevations.

During the closure-planning workshop of February, 2004 in Vancouver, it was recognized that the conceptual design prepared for the Plug Dam was not based on site specific information and preliminary investigations should be performed to test the conceptual design. As a result, Deloitte and Touche Inc. (Deloitte) and the Type II Mine Management team requested that BGC Engineering Inc. (BGC) undertake a preliminary investigation and prepare an updated conceptual design and cost estimate.

This report presents the updated conceptual design for the Plug Dam. Since the first conceptual design report (BGC 2004) presented a detailed summary of the key information available at that time the reader will be referred to the previous report as appropriate.

## 1.2 Scope of Work and Authorization to Proceed

The agreed upon scope of work developed by BGC was presented in a proposal dated August 4, 2004 to Deloitte. Authorization to proceed was provided by Mr. Doug Sedgwick of Deloitte on August 10, 2004.

The program of work undertaken by BGC included the following major tasks, at the Plug Dam location:

- Bedrock core drilling and water pressure testing to assess rock mass quality and hydraulic conductivity in the abutments and middle of the dam foundation. This was performed to confirm the depth and extent of the grout curtain.
- Geophysical surveys to delineate the bedrock surface under the cover of surficial materials in the pillar area between the Faro Pit and the Zone II Pit.
- Test pitting to assess the quality of overburden materials on top of the left abutment for potential use as core material.

Other investigation activities were performed outside of the direct Plug Dam construction area, these included:

- ODEX drilling to assess the overburden stratigraphy within the former Faro Creek valley
  on the west side of the Faro pit, including falling head water tests to estimate the
  hydraulic conductivity within the potential outlet from the Faro Pit.
- Survey of the exposed bedrock elevations on the rim of the Faro Pit between the Faro creek channel and the Plug Dam location.
- Surface sampling and test pitting to assess the quality of the overburden materials exposed on the Northeast Waste Dump.

In addition to the above investigation activities, a review of relevant information that has become available since preparation of the 2004 conceptual design report was undertaken.

This draft report presents the updated conceptual design for the Plug Dam based on the information that is now available. Following receipt of review comments a final report will be prepared.

#### 1.3 Site Survey Datum

Within the mine site area, topographic elevations may be referenced to various datum levels. Unless noted otherwise, all drawings in this report are based on the 1927 North American Grid system (NAD27) and geodetic datum, with elevations given in metres above mean sea level (m amsl). Older mine drawings may be based on "Mine Datum" or "Down Valley Project Datum" and may be in feet. The approximate conversion factors for these data are as follows (Robertson 1997):

- To convert Mine Datum to m amsl, subtract 33.3 m or 109.2 feet.
- To convert Down Valley Project Datum to m amsl, subtract 32.3 m or 106 feet.

#### 2.0 BACKGROUND INFORMATION

#### 2.1 Location

The Faro Mine is located about 20 km north-northwest of Faro, Yukon, in the Anvil Range Mountains, about 190 km northeast of Whitehorse. Access to the mine is via a 23 km long mine access road from the Town of Faro, as shown in Figure 1.

Figure 2 shows an overview of the current site conditions, indicating the locations of interest. The Faro open pit straddles the Faro Creek valley. Figure 3 shows the topographic features of the Faro Pit area in more detail. The drainage of Faro Creek was diverted around the northeast side of the pit to allow mining of the open pit. The pit was mined in three zones. Zones I and III are located within the main pit boundary. The Zone II Pit was located south of the Main Pit, as shown in Figure 3 and was subsequently completely filled in with waste rock.

Waste rock piles from the open pit mine are draped over the valley slopes of Rose Creek, along the southeast sides of the pit. The original Faro Creek drainage course forms a notch into the pit wall crests on the west and north sides. The pit is currently filled with water to about elevation 1142 m. The notch along the former Faro Creek channel has been partially filled in with waste rock, with the lowest topographical point now being at elevation 1181.59 m (on waste rock) at the top of the access road to the pump barge, as shown in Figure 2. A bedrock low, at elevation 1158.2 m occurs in this area (SRK 1991). The location of this topographic and bedrock low is indicated on Figure 2. The drilling performed at borehole BGC04-01 indicated that the bedrock elevation was 1055.3 m, and the elevation of the exposed bedrock in the area is at an elevation of about 1160 m.

On the southeast corner of the pit, a haul road ramp forms a narrow slot through the Faro Pit crest. This road was previously used to connect the main Pit to the Zone II Pit and was abandoned during mining of the Zone III ore body. The maximum bedrock elevation in the base of the haul road is about elevation 1158.9 m amsl (SRK, 1991). This elevation tentatively represents another bedrock low on the rim of the Faro Pit. The bedrock around the Zone II Pit has been covered by waste rock dumps, which have a maximum elevation of about 1254 m amsl on the southeast side, between Faro Pit and Rose Creek. The minimum saddle elevation on the haul road out of the main pit, located on rockfill cover over the former Zone II pit area, is 1174.57 m, as shown in Figures 2 and 3.

## 2.2 Geology

The conceptual design report presented a detailed summary of the geology of the Faro Pit, concentrating on the Plug Dam and Zone II Pit. The geology was compiled from various archival reports and references, augmented by limited site reconnaissance observations. The reader is referred to that previous report for a detailed discussion. As the conceptual design report was being completed, additional archival geotechnical data concerning the Plug Dam area was found by SRK. This section provides a brief outline of the previous detailed review and updates to the available information and the current investigation.

The Anvil Range ore bodies occur at the contact between the Mt. Mye Formation and the Vangorda Formation. Both of these formations have been encountered in the vicinity of the Plug Dam site area, with the Vangorda Formation on the right abutment and the Mt. Mye Formation on the left abutment. Figure 4 presents an updated geological plan of the Plug Dam area.

Figure 5 shows a geological plan of the Faro Creek area. This geological plan was created on the basis of airphoto interpretation and previous geological mapping. Site reconnaissance will be required in this area to provide additional details. Based on the mapping of the Faro Pit, no known faults dissect the Faro Creek area.

During the 1994 investigation of the Zone II pit seepage (SRK 1994) a borehole, BH94-16 was drilled within about 500 m downstream of the plug dam site. At this location, shown on Figures 3 and 6, an upper sequence of Carbonaceous Phyllite, Quartz Sericite Schist, Biotite Schist about 20 m thick was encountered. Within this upper sequence, drill core recoveries ranged between 50% and 95%, with RQD less than 20%. Below about 20 m depth the rock consisted of a Chloritic Biotite Schist with better total core recovery and RQD values.

Three packer tests were performed during drilling of borehole BH94-16, using a single packer. The hydraulic conductivities measured for the following zones; 4.6 to 15.2m, 15.5 to 24.4m and 58.6 to 68.3m were respectively 2.1x10<sup>-8</sup> m/s, 8.9x10<sup>-9</sup> m/s and 6.1x10<sup>-8</sup> m/s. The ground surface at this borehole was 1160 m amsl (SRK 1994) making the upper hydraulic conductivity test between elevation 1155.4 m and 1144.8 m. Three piezometers were installed in this borehole using very large screen zones. The upper piezometer installation was not completed (no sand pack was installed, and the piezometer pipe was attached to the middle piezometer) due to frozen conditions. In 1994 following drilling the measured groundwater level was at 6.1 m below grade, elevation 1153.9 m. In September 2004 the measured water level (all three piezometers) was between 4.8 m and 5.2 m below grade, elevation 1155.2 to 1154.2 m.

#### 3.0 FIELD INVESTIGATION

#### 3.1 General

The field program undertaken for this investigation was performed in stages between August and September of 2004. The field work involved site reconnaissance, test pitting, drilling, hydraulic conductivity testing and geophysics. The investigation tasks were conducted at a number of locations around the Faro Pit and the Waste rock dumps.

The conceptual design report recommended a detailed program of additional site investigations required to advance the plug dam to a preliminary design stage. The 2004 program undertook some of these investigations in order to gather some site specific information at a few key locations. It is expected that if the design for the Plug Dam is to proceed beyond conceptual design a detailed investigation program will need to be performed at the Plug Dam and Faro Creek locations, similar to those recommended (BGC 2004).

One standpipe piezometer, BGC04-01 was installed in the Faro Creek area. Monitoring of the water levels can be performed at this location and it will likely be used as part of future detailed investigations at this location. Packer tests were performed at various depths in the bedrock of the Plug Dam foundation and abutments to provide an estimate of the field hydraulic conductivity. Falling head tests were performed throughout drilling of the overburden soils at the Faro Creek location to estimate the hydraulic conductivity at that location. Test pitting and surface sampling was performed to determine the properties of overburden soils on the left abutment of the Plug dam. This investigation was used to determine the suitability of nearby deposits as construction materials in the Plug Dam.

The following sections discuss the methods of field investigation and provides the results of those investigations. In Section 4 the conceptual design of the Plug Dam is revisited and revised on the basis of the results of the investigation.

#### 3.2 Site Reconnaissance

The site reconnaissance consisted of a walking inspection of the Plug Dam area and the Faro Creek area. Photograph 1a, on Drawing No. 1 in the photograph section, shows a view of the Plug Dam site. Marked on this photograph are the positions of the boreholes drilled and the approximate location of the proposed pit water level when raised to elevation 1168 m. Photograph 1b shows a similar view of the former Faro Creek channel area.

Two different views of the right abutment of the Plug Dam are shown in Drawing No. 2 (photograph section). Photo 2a shows the pillar of rock between the main pit and Zone II pit. This area was previously mapped as having a number of faults dissecting the pillar (BGC 2004) the approximate position of these faults is shown on Figure 4. Photo 2b shows a view looking from the left abutment at the right abutment, looking along the alignment of the proposed Plug Dam.

An overview of the left abutment is shown in Photograph 3 (Drawing No. 3 in the photograph section). Included on this photo is the position of borehole BGC04-04 and the approximate water elevation when raised to elevation 1168 m.

During the site reconnaissance 36 different exposed bedrock locations were marked along the edge of the Faro Pit. The location and elevation of these bedrock exposures are shown as BE#1 through BE#36 on Figures 3, 6 and 7.

#### 3.3 Drilling

### 3.3.1 ODEX Drilling

The drilling was performed using a track mounted Prospector Drill using 171 cm (6.34 inch) O.D. (152 cm, or 6 inch I.D.) casing. The drill was provided and operated by Midnight Sun Drilling Ltd. (Midnight Sun) from Whitehorse, Yukon. Mr. Mike McCrank, EIT of BGC was on site during the investigation of this area. Drilling was completed between August 9 and 14, 2004 (almost three days of downtime were experienced). The location of this borehole is shown on Figures 3 and 7.

The borehole log for BGC04-01 is attached in Appendix I. Three different materials were encountered; a waste rock/road fill, in-situ till and colluvial soils. These units are underlain by a schistose bedrock.

An attempt was made to convert this ODEX rig to diamond drilling so that the program could continue immediately following drilling of BGC04-01. This conversion proved to be unsuccessful and was abandoned. Following demobilization of the BGC inspector the ODEX drill was used to set casing (117 cm O.D.) at each of the three diamond drill hole locations at the Plug Dam site. Further discussion is provided in Section 3.3.2.

#### 3.3.2 Diamond Drilling

The drilling was performed using a truck mounted JQS 300 drill. The drill rig was supplied and operated by Midnight Sun from Whitehorse, Yukon. Drilling was completed between August 31 and September 9, 2004. A total of three boreholes were completed, the locations of the boreholes are shown on Figures 3 and 6. The drilling was performed under the full time supervision of Mr. Gerry Ferris, P.Eng. of BGC.

At each borehole, HW casing was set prior to initiation of core drilling. At BGC04-02, an ODEX casing had been set to a depth of 4.26 m (14 feet) as noted above. The HW casing was installed in the center of this ODEX casing to a depth of 5.33 m (17.5 feet). At BGC04-03 and BGC04-04 the ODEX casing had only been inserted to depths of approximately 1.2 m (4 feet). Rather than set the HW casing inside this short length of ODEX casing the HW casing was installed adjacent to it. The base of the HW casing was set to a depth of 1.2 m (4 feet). The boreholes were then cored in five foot core runs to the desired depth with a thick walled NQ3 diamond rotary bit, resulting in 44.96 mm diameter core. Water was used as the drilling fluid for all the holes. All boreholes were drilled vertically. Drilling proceeded extremely rapidly, a 5 foot core run was completed in about 10 minutes (drilling rate of 6 inches per minute).

Initial geotechnical logging was performed at the drill site as the core was brought out of the ground. Given the speed of drilling, core logging was completed after the core had been transported to the guard house. The core logging information collected included:

- Total core recovery (TCR),
- Solid core recovery (SCR),
- Rock Quality Designation (RQD),
- Strength index,
- Weathering and alteration,
- Bedrock lithology,
- Joint shape and roughness, joint alteration and/or infill, joint aperture,
- Discontinuity inclination with respect to the core axis, and
- Occurrence of broken core.

The borehole logs created based on drilling are attached in Appendix I. Each joint, fracture and drill break was inspected with respect to type, roughness, infilling and aperture. A summary of the core fractures, minus the drill breaks, is included immediately following the appropriate borehole log.

An attempt was made to estimate the degree of joint aperture in-situ, based on an examination of the joint surface characteristics in the core samples. Joint aperture was logged as "tight" T, "Partially open" P and "Open" O and is included on the summary of the core fractures. The tight aperture condition was usually associated with fractures along foliation, and had no staining. These fractures were difficult to distinguish from drill-induced fractures. Partially open and open fractures frequently displayed surface staining; weathering or some degree of wall rock mismatch.

A photo of the core collected from BGC04-02 is shown in Drawing No. 4 in the photo section. A photo of the core collected from BGC04-03 is shown in Drawing No. 5 in the photo section. A photo of the core collected from BGC04-04 is shown in Drawing No. 6 in the photo section. As can be seen in these photos the core was highly fractured with many more fractures than shown in the borehole logs and summary of core fractures. As noted above an attempt was made to distinguish between the natural fractures and core breaks, and the borehole log and fracture

sheets represent only the natural fractures. It is thought that the large amount of core fracturing experienced is due to the speed of drilling and the weakness along the foliation. During core logging examination, the core could be broken by hand along the weak foliation planes.

Often the core was so highly broken up and fractured by drilling that logging of distinct fractures was difficult. Quartz zones were encountered during drilling (as indicated on the logs) and it was thought that occasionally fragments of quartz become stuck in the core catcher, resulting in the softer schistose rock being ground out of the way by the quartz. This may be reason for very low core recoveries in certain sections.

## 3.4 Hydraulic Conductivity Testing

## 3.4.1 Rising/Falling Head tests

Hydraulic conductivity tests, known as rising or falling head tests depending on whether water was removed or added to the standpipe, were performed at borehole BGC04-01.

Falling head tests were performed as part of the drilling of the borehole. This was accomplished by advancing the ODEX drill string to the desired depth, then pulling back the string by 3.05 m (10 feet). This exposed a 3.05 m section of soil/rock, which was then tested by filling the upper part of the casing with water. The casing was filled until the water level in the casing was equal to the ground surface level. The rate at which the water level dropped, once water was no longer added, in the casing was plotted versus time. The resultant data was used to calculate the horizontal hydraulic conductivity of the soil adjacent to the test interval. These calculations are attached in Appendix II.

Following installation of the 50 mm I.D PVC piezometer (installation details included on the borehole log) a falling head test was performed in the piezometer. The falling head test was performed using the same methodology as the falling head tests performed during drilling. The calculations performed to determine the horizontal hydraulic conductivity are attached in Appendix II. This falling head test was performed immediately following installation, prior to development of the well.

The well was developed by removing three times the volume of water contained in the PVC piezometer. Following well development a slug test was performed in the piezometer. The water level in the piezometer was allowed to stabilize after the development activities and a datalogger was inserted into the well prior to dropping the "slug" into the casing. The "slug" consisted of a metal bar attached to a rope. The data logger recorded the water level increase as slug was dropped into the casing, and then the time required for the water level to drop back to the initial level. The datalogger was then was used to measure the water level rise after the slug was removed from the casing. This data was then used to calculate the horizontal hydraulic conductivity, shown in Appendix II. The slug test was performed by Mr. Dan Mackie of SRK Consulting Inc. and the raw data was provided to BGC.

The calculations, along with a summary of the results are included in Appendix II. The hydraulic conductivity calculation was performed according to the methodology outlined by Hvorslev (1951).

#### 3.4.2 Packer Tests

Packer tests were carried out in the bedrock portion of the diamond drill holes. The top of the upper test zone was limited by the base of the cased zone. The casing depth at BGC04-02 was set by the base of the larger diameter casing set using the ODEX drill rig.

Following drilling of each borehole to its final depth, the borehole was flushed with clean water and the drill rods were removed. Water pressure testing was carried out in the "open" borehole to determine the hydraulic conductivity profile of the surrounding bedrock.

Double inflatable (pneumatic) packers, manufactured by RST Instruments of Vancouver, B.C. were supplied by Midnight Sun. The packers were capable of isolating either 2.22 m or 3.75 m intervals using perforated steel pipe between the packers. The packers were inflated using nitrogen gas to at least three times the maximum test pressure. Water was pumped into the test section under constant pressure. The flow was measured at BGC04-02 using a digital totalizing flow meter. This flow meter supplied by Midnight Sun was oversized for the testing equipment and was later revealed to require flow rates above about 5 Igal/min to register correctly. For the packer testing performed in the remaining boreholes an analog "Neptune" flow meter was used to measure the total flow during a test. The Neptune flow meter had an estimated minimum measurable flow of 0.01 Igal, which is equal to a flow rate of 0.4 I/min for a 5 minute test.

For most of the water pressure tests, the injection pressure was increased in three increments and then decreased for two decrements while the flow was measured continuously. The sequential pressures utilized were approximately equivalent to 1/3P, 2/3P, 3/3P, 2/3P and 1/3P. P was equal to 1 psi per foot of depth, at the top of the test interval. Each increment and decrement of pressure was maintained until stabilized pressure/flow conditions were achieved within the test section. The test was conducted for a minimum of 15 min. Some of the water pressure tests were conducted with a reduced amount of pressure increments due to time/budget restrictions. In these cases the 3/3P pressure was used for the test.

The results of the water pressure testing are summarized in Table 1 and presented graphically on the geotechnical logs included in Appendix I. Hydraulic conductivities were calculated based on the results of each water pressure test using the analysis method presented in Hvorslev (1951) a copy of these calculations are included in Appendix II.

**Table 1 Hydraulic Conductivity Data** 

Borehole	Test	Date	Test Interval	Hydraulic	Comments
	No.	Tested	(m)	Conductivity	
				(m/sec)	
BGC04-02	1	Sept 1/04	8.45 – 10.67	>1.0 x 10 <sup>-4</sup>	Note 1
BGC04-02	2	Sept 1/04	9.71 – 1,1.93	>1.0 x 10 <sup>-4</sup>	Note 1
BGC04-02	3	Sept 1/04	13.06 - 15.28	3.6 x 10 <sup>-6</sup>	Note 2
BGC04-02	4	Sept 1/04	15.81 - 18.03	3.1 x 10 <sup>-6</sup>	Note 2
BGC04-03	1	Sept 5/04	3.01 – 5.23	5.1 x 10 <sup>-6</sup>	
BGC04-03	2	Sept 5/04	5.75 – 7.97	1.2 x 10 <sup>-7</sup>	
BGC04-03	3	Sept 5/04	8.49 – 10.71	<2.7 x 10 <sup>-9</sup>	Note 3
BGC04-03	4	Sept 5/04	11.24 – 13.46	<2.6 x 10 <sup>-9</sup>	Note 3
BGC04-03	5	Sept 5/04	13.98 – 16.20	<2.2 x 10 <sup>-9</sup>	Note 3
BGC04-03	6	Sept 5/04	16.72 – 18.94	<2.0 x 10 <sup>-9</sup>	Note 3
BGC04-03	7	Sept 5/04	19.46 – 21.68	1.2 x 10 <sup>-9</sup>	
BGC04-03	8	Sept 5/04	21.90 – 24.12	4.1 x 10 <sup>-7</sup>	
BGC04-04	1	Sept 8/04	2.79 – 5.79	1.0 x 10 <sup>-6</sup>	
BGC04-04	2	Sept 9/04	3.61 – 7.36	4.3 x 10 <sup>-7</sup>	
BGC04-04	3	Sept 9/04	7.27 – 11.02	7.2 x 10 <sup>-9</sup>	
BGC04-04	4	Sept 9/04	10.92 – 14.67	7.3 x 10 <sup>-9</sup>	
BGC04-04	5	Sept 9/04	14.58 – 18.33	1.8 x 10 <sup>-8</sup>	
BGC04-04	6	Sept 9/04	18.24 – 21.99	1.1 x 10 <sup>-7</sup>	
BGC04-04	7	Sept 9/04	21.90 – 25.65	1.3 x 10 <sup>-7</sup>	
BGC04-04	8	Sept 9/04	25.56 – 29.30	<9.4 x 10 <sup>-10</sup>	Note 3
BGC04-04	9	Sept 9/04	29.78 – 33.53	<7.8 x 10 <sup>-10</sup>	Note 3
BGC04-04	10	Sept 9/04	32.57 – 36.32	3.1 x 10 <sup>-8</sup>	

Notes:

<sup>1 –</sup> Pumping water at the maximum pump capacity. Pressure beyond the system compliance could not be generated. Hydraulic conductivity was calculated based on the pumping rate and the assumption that the water level feeding the packer was equal to the ground surface. The actual hydraulic conductivity is higher than the stated value.

<sup>2 –</sup> Digital flow meter could not measure low flows properly, hydraulic conductivity calculated based on a flow rate of 20 l/min which was determined to be the lower working limit of the flow meter. An analog flow meter was used for the remaining boreholes. The actual hydraulic conductivity is likely lower than this calculated value.

<sup>3 –</sup> Take of zero measured, hydraulic conductivity calculated based on the lowest flow rate considered measurable by the equipment.

## 3.5 Test pit Investigation

#### 3.5.1 Test pit Excavation

Six test pits were excavated in the overburden soils on the left abutment area to investigate the potential use of this material as Zone 1 (core) fill for the Plug Dam. The test pits were excavated on September 14, 2004 using the Anvil Range Caterpillar 235 tracked excavator. The test pits were excavated and sampled under the supervision of Mr. Gerry Ferris, P.Eng. of BGC. The location of these six test pits are shown on Figures 3 and 6.

A copy of the test pit logs created based on this investigation is included in Appendix I. Photographs of the test pits excavated on the left abutment area are included on Drawings No 7 through 12 in the photos section. In general, the soil encountered consists of silty sand with some gravel to silty, gravely sand. The liquid limit of the portion of the samples finer than the No. 40 sieve varied from 17 to 25. The plastic limit varied from 8 to 15. The natural water content of the samples was less than the plastic limit. A copy of the laboratory testing completed on samples from the test pits is included in Appendix III. The broadly graded nature of this material resembles a till, which has sufficient fines content to be suitable as a core material for the dam. The sand and gravel content will provide a high degree of shearing resistance when placed in compacted lifts in the dam.

Three test pits were excavated at the crest of Northeast waste dump. Anecdotal information suggested that this area had been used as a waste dump for till that was removed during overburden stripping. The position of these test pits is shown on Figure 8. A copy of the test pit logs based on this investigation is included in Appendix I. These three test pits were excavated to determine the amount of natural Quaternary soils present in the area for use as Zone I fill. The test pitting program found no undisturbed Quaternary materials, nor was any material encountered to indicate that this was a "till dump" from overburden stripping. At both BGCTP04-07 and -09 only waste rock was encountered to the maximum reach of the excavator. At BGCTP04-08 a 0.5 m thick disturbed mix of Quaternary material was encountered at the base of the excavation. This led to the conclusion that the material exposed on the face of the dump is likely disturbed and dumped material, mixed with waste rock, rather than part of a natural deposit or indicative of a "till dump" that could be exploited as a borrow area for dam core material.

The results of the laboratory testing program performed on samples taken from test pits on the left abutment are included on the borehole logs, in Appendix I and in Appendix III.

#### 3.5.2 Surface Sampling

Surface samples were collected at a number of locations on the Northeast waste dump. This surface sampling program was intended to supplement the test pitting. The location of the surface samples are shown on Figure 8. The surface samples were collected by Mr. Gerry Ferris, P.Eng. either on September 13 or 15, 2004. Photographs taken during the collection of these surface samples are included in Drawings 13 through 20 in the photograph section. These locations are denoted by the name of the sample collected at each location.

Surface samples GWF22 through GWF27 were collected at the base of "till dumps" as shown in Figure 7. The soil encountered at these locations varied from sandy gravel with some cobbles to gravely sand with some cobbles. Moisture contents of these samples were measured and the results are included in Appendix III. Given the test pit program performed and visual inspection of the crest of the dumps it was concluded, that none to little Zone I core material would be available from these locations. Based on this review, the material exposed in this area may be more suitable, after processing as Zone 2 filter material. It is considered unlikely however, that this area represents a significant resource in terms of volume of material available.

Surface samples GWF28 and GWF29 were collected from a sand and gravel dump located on the crest of the Northeast waste dump, as shown in Figure 8. The soil encountered at these two surface sampling locations consisted of sandy gravel with some cobble to gravely sand with some cobble. A summary of the laboratory testing results for these samples are attached in Appendix III. This material potentially could be used, following processing as Zone 2 filter material.

#### 3.6 Geophysics

Geophysical surveys were performed at the Faro Mine site for programs undertaken by both BGC and SRK in 2004. The geophysical contractor, Aurora Geophysics Ltd. (Aurora) from Whitehorse Yukon was on site from October 7 to 18, 2004 for all the programs. The work conducted for the Plug Dam project consisted of three seismic refraction lines in the right abutment/pillar zone. The locations of the three lines are shown on Figures 3 and 6. The purpose of these geophysics lines was to determine the bedrock contact elevation and to confirm the dimensions of the rock pillar between the Main Pit and Zone II pit.

The location of each of the three geophysics lines was laid out in accordance with the requirements of BGC prior to Aurora's arrival at site. The survey information along each line was provided to Aurora. The methodology for performing the geophysical survey and preliminary results are included in Appendix IV.

The preliminary results from the Line 1 survey indicate the interpreted top of bedrock (based on seismic wave velocities) varies between elevation 1163 and 1176 m. The results from the Line 2 survey indicate that the interpreted bedrock surface decreases in elevation from 1170 m near the rim of the Faro pit, to about elevation 1167 m about 40 m from the edge of the exposed rock wall. Then the bedrock elevation increases to about 1176 m. The results from the Line 3 survey indicated that the interpreted bedrock surface elevation varies between elevation 1171 and 1173 m.

## 3.7 Discussion of Findings

#### 3.7.1 Maximum Reservoir Elevation

In original conceptual design report the maximum water elevation for the raised Faro Pit was 1173 m. The design water elevation was selected based on assumptions regarding the quality of rock in the pillar between the Main pit and Zone II pit.

At the Faro Creek valley location the measured bedrock elevation at the edge of the Faro pit is about 1160 m, marked as BE#7 through BE#15 on Figure 4 and on Figure 10. These measurements were made at the edge of the pit. At Borehole BGC04-01 the top of bedrock was encountered at elevation 1155.3 m, this borehole was located within the bedrock low of the former creek channel.

At the Plug Dam site, the geophysics (seismic refraction) performed in the pillar area between the Main pit and the Zone II pit indicated intact bedrock is at a lower elevation than originally thought. The exposed bedrock on the pit wall is at an elevation of about 1180 m. The previous assessment was that the upper 4 to 6 m of the rock would be highly weathered and require a seepage cut-off. However, the seismic assessment indicated that the transition from a velocity of about 1000 m/s to 4500 m/s (intact rock) was between 1167 to 1171 m. Additional investigation will be required in this area (as indicated in the original conceptual design report) to confirm the intact, tight bedrock elevation for tie in of the cut-off. The results of the preliminary geophysics assessment indicates that the upper 9 to 13 m of bedrock is badly fractured. This is likely due, in a large part to blast damage from mining activities in the Zone II and Main Pit, adjacent to the pillar area.

To maintain the previous maximum reservoir level of Elevation 1173 m amsl the pillar area would require fairly extensive treatment (ranging from removal and replacement, consolidation grouting to extension of the core placement on this rock face). In light of this result, it is recommended that the maximum reservoir elevation be reduced to 1168 m. Under this scenario, seepage would still be possible through the materials filling the Faro Creek valley area on the west side of Faro pit.

Constructing the Plug Dam so that a water level of 1168 is retained in the Faro pit it will create about 16,300,000 m<sup>3</sup> of additional storage in the pit, as shown in Figure 11.

If seepage out of the Faro Creek area is not acceptable then a seepage cut-off will be required in this area or an even lower maximum water level could be considered. Additional investigation in this area will be required to determine the requirements for seepage cut-off or the elevation of low permeability rock. The preliminary investigation performed in this area encountered bedrock with a hydraulic conductivity of about 5x10-6 m/s to an elevation of 1150 m.

## 3.7.2 Hydraulic Conductivity - Plug Dam Area

The hydraulic conductivity in the right and left abutments were within the range previously estimated. At the right abutment (BGC04-03) the permeability is below 1x10<sup>-7</sup> m/s (the approximate limit of grout ability) at elevation 1150 m. On the left abutment (BGC04-04) rock with this low hydraulic conductivity is reached at elevation 1165 m.

The hydraulic conductivity below the base of the road, BGC04-02 however was significantly different than expected. The borehole was collared at elevation of 1152.6 m. The estimated top of bedrock is 1149 m (this elevation is based on third party reports from the ODEX drilling of the casing). The hydraulic conductivity of the rock was higher than could be measured using the available equipment, interpreted to have hydraulic conductivity greater than 1x10<sup>-4</sup> m/s. This zone of high hydraulic conductivity extends down to about elevation 1139 m. Given the inaccuracies of the flow meter used at BGC04-02 it is not conclusive but it appears that intact, tight (i.e. hydraulic conductivity less than 1x10<sup>-7</sup> m/s) bedrock would be located at about elevation 1136 m.

#### 3.7.3 Hydraulic Conductivity – Faro Creek Area

Previous assessments have assumed that the unconsolidated overburden sediments within the bedrock low defining the Faro Creek had a hydraulic conductivity, in the range of 1x10<sup>-6</sup> m/s. Based on the testing to date this estimate has proven to be fairly accurate. The bedrock immediately beneath these sediments however was found to be more permeable, with a hydraulic conductivity of about 5x10<sup>-6</sup> m/s. The drilling performed did not extend to depth to find the elevation where the rock permeability reduced, as this was not the purpose of the investigation. The results indicate that the underlying rock will extend the seepage area acting as a conduit for water flow from the Faro Pit. Indeed, given this result it is thought possible that a seepage zone could extend along the entire pit perimeter. Inflow to the pit would come mainly from the north and east sides of the pit and outflow through the south and west sides.

An assessment of the overall seepage from the pit would be a requirement of the next stage of investigation in the Plug Dam. The starting point for this assessment would be a water balance of the existing Faro Pit, which BGC understands is being prepared this year.

#### 4.0 REVISED CONCEPTUAL DESIGN

#### 4.1 General

The following section discusses the conceptual design for the Plug dam, with consideration of the results of the investigation performed.

The Plug Dam section chosen in the initial conceptual design was a zoned rockfill dam with a central core of relatively impervious material, upstream and downstream filter and transition zones. The key difference in the revised conceptual design, based on the 2004 drilling results is the need to deepen the seepage cut off below the dam foundation and conduct an extensive consolidation grouting program of the core contact foundation. The 2004 drilling program failed to provide details of the upper 5 m of the dam foundation in the center of the access road. Casing was installed by the driller through what was believed to be overburden or road fill prior to BGC being on site. As a result, the 3 m depth of the core trench needs to be confirmed in a subsequent program of drilling or test pitting. Consolidation grouting will be required to elevation 1139 m in the highly permeable upper portion of rock. It should be noted that a deep core trench that extends to an elevation of 1139 m could be considered, however investigation will be required prior to this determination.

Typically, such a deep core trench proves to be the more expensive option, due to the volume of material that must be excavated and the volume of core material that must be placed into the core trench. Future investigations will be required to determine the depth at which suitable conditions for core placement on rock are found. It is important to note that the central impervious core dam section shown for the Plug Dam assumes that suitable foundation conditions for the placement of core materials can be found within a reasonable depth. If this is not the case, alternative dam sections may have to be considered due to the need to integrate the impervious element of the embankment with the seepage cut-off in the foundation. Alternative seepage cut-off methods may include a slurry trench cut-off utilizing soil-bentonite mixtures or plastic concrete that extends through the embankment and into the bedrock. In the extreme case, alternative dam alignments may have to be identified to avoid unfavourable foundation conditions.

In view of the need to treat a potentially extensive zone of fractured bedrock below the core trench, the grout curtain in the foundation has been expanded from a single line shown in the 2003 conceptual design report to a three line grout curtain extending to elevation 1130 m. The grout curtain for the abutment area is planned to consist of a two line curtain, leaving a possibility for a middle line, to be grouted as necessary. A schematic showing this concept is shown on Figure 12. This conceptual design was chosen based on the following considerations:

- Simple design that can be constructed using readily available construction equipment, with a minimal amount of technical supervision in a short construction season.
- Construction materials include waste rock, till and sand and gravel, which are readily

available at the site.

- The rockfill side slopes can readily be flattened or steepened to accommodate any type of material. Previous design concepts allowed for the use of sulphide bearing waste in the upstream shell, below the minimum water level elevation.
- Minimal abutment foundation preparation required, which can be done over the late winter- early spring before the summer construction season.
- The high hydraulic conductivity measured in the upper portions of the foundation area.
- Grout curtain to seal potential water transmitting fractures in the bedrock above elevation 1130 m.

Prior to fill placement, the entire footprint of the dam will be stripped of colluvial debris and scaled of loose rock. The road base covering the foundation will be removed under the entire dam footprint. To minimize disturbance to the rock in the dam foundation, the core trench will not be blasted. Minor rock excavation will, however be required in the right abutment to shape the core contact area. Ideally, the impervious fill should be placed on a slope no greater than 45° from the horizontal to ensure that during compaction, the lowermost lifts in contact with rock are adequately compacted. Steeper rock slopes will be trimmed or concrete fillets placed in order to create smooth transitions on the core contact surface. The core contact area will be hand scaled and blown clean with compressed air prior to fill placement. Dental concrete and slush grouting of open surface cracks may be required, especially in the right abutment area.

During construction of the Plug Dam, three additional items of work will be required:

- Relocation of the water discharge pipeline from the Zone II pump well, which passes through the dam footprint along the toe of the left abutment.
- Removal and reconfiguration of the water diversion ditch on the 1173 bench on the left abutment.
- System to collect seepage water from the downstream toe of the dam.

Relocation and re-arrangement of the first two facilities should be done with mine site staff input and may be done under a separate contract or work activity by Deloitte. The seepage collection system along the downstream toe will be installed during dam construction and may involve a collection pond with a pumping system to return the seepage water over the Plug Dam into the Faro Pit.

The design criteria outlined in the conceptual design report have not been altered, and the reader is referred to that report (BGC 2004) for a review of the criteria.

#### 4.2 Embankment Section and Construction

#### 4.2.1 Zone 1 Impervious Earth Fill

The investigation of the glacial/colluvial material on the left abutment revealed that the material consisted of a low plasticity broadly graded silty to gravely sand. This material is suitable for use as zone 1 material. Final recommendation to use this material as opposed to a more uniformed fine grained material from the Vangorda Plateau will be made during a later design phase. An economic evaluation of the requirements for Zone 2 filter material will dictate the final selection.

It was assumed that prior to construction, further investigations will be carried out to identify potential borrow areas for dam construction materials, both in terms of the quality and quantities of materials available. Later detailed designs of the dam will need to consider minimization of processing to keep the cost of the construction down.

The core will be placed in lifts and compacted at optimum moisture content to a dry density equal to or greater than the maximum dry density obtained in the Standard Proctor Test. The bedrock contact zone will be placed at slightly wet of optimum moisture content, to ensure that the till is squeezed into the surface irregularities of the bedrock, without voids or areas of low compaction.

#### 4.2.2 Zone 2 Filter

The gradation and number of filters will depend on the distribution of grain size curves obtained for the Zone 1 impervious core material and the gradation of the Zone 3 rockfill. Processed sand and gravel will be used to provide a material that meets the filter gradations. Granular borrow sources are located within 6 km of the dam site, on the crest of the Northeast dump and the Faro creek borrow area. It has been assumed that appropriate quality and quantities of material will be available from these two sources. Processing is expected prior to the used of materials from these borrow areas prior to use within the dam.

The filter zones were generously sized in order to facilitate placement and compaction. Filter materials will be placed in lifts as the impervious core and rockfill shells are raised, and compacted to a dry density between 95% and 98% of the maximum dry density. The 2 m depth of cover of granular materials over the impervious core was intended to offer thermal protection for the core and will be augmented by rigid soil insulation and a road base for traffic if required. The material details depth of thermal cover protection must be assessed in future design studies by conducting thermal modelling using site-specific climatic factors and soil properties.

#### 4.2.3 Zone 3 Rockfill

It was assumed that sufficient rockfill would be obtained from the adjacent Faro waste rock dumps. Some of this material contains potentially acid generating (PAG) rock units, such as pyrite bearing quartzites, massive sulphide ores or disseminated sulphides. The SRK plug dam options considered using PAG material in the upstream shell, below the water line. This is still a valid option, as long as the future water levels in the pit do not change. Further consideration of the location of PAG materials within the dam section will be dependent on the final operational conditions for the Faro Pit water level. For the purposes of this study, it was assumed that the rockfill used in the dam will be clean, non-PAG rock.

Rockfill will consist of metamorphic rock units such as phyllite, schist, gneiss and minor volcanics or calc-silicate. Since the waste rocks have been exposed to weathering for a period of time, it should be possible to selectively excavate materials that are strong, durable and not subject to chemical or physical breakdown due to weathering. Maximum particle size will be 300 mm. The rockfill will be placed in lifts, with nominal compaction by the bulldozer or spreading equipment. The rockfill will be raised in lifts concurrent with the filters and till core.

No rip rap has been included in the dam section. It was assumed that the rockfill used in the upstream shell would satisfy erosion protection requirements for the dam. This assumption will be checked in future detailed design for the Plug Dam.

## 4.3 Seepage Assessment

Upon installation of the Plug Dam it is expected that there would two areas of potential seepage loss in bedrock low areas around the perimeter of the Faro Pit:

- The south corner of the pit, adjacent to the Zone II Pit and including the Plug Dam foundation;
- The southwest wall, also related to the former Faro Creek valley sediments and disturbance; and,

In addition to the seepage from these two bedrock low areas general seepage from the Faro Pit is to be expected. BGC understands that a water balance for the Faro Pit has been prepared in 2004, this study would provide a summary of the current seepage from the pit. Based on the drilling/testing programs the hydraulic conductivity increases with increasing elevation. Therefore, general seepage losses from the pit will increase as the water level in the pit is increased. As described in the following two sub-sections, the total estimated seepage losses from the two areas mentioned above ranges between approximately 234 m³/day and 890 m³/day.

### South Corner and Plug Dam Foundation

The Zone II Pit will act as a local groundwater sink along the south perimeter of the Faro Pit (or below the right abutment and central portion of the proposed plug dam). The water elevation in the Zone II pit pumping well has fluctuated between approximately 1106 m and 1116 m amsl, between March 14, 1997 and September 30, 2003 (BGC 2004)

Estimates of seepage losses from the Faro Pit into the Zone II Pit have been carried out based on information obtained from the 1991 and 1993 SRK reports and this program. These results and field observations used in performing/the estimate include:

- Below 1143 m (BH16), wall rocks are predominantly schists and phyllites, do not maintain open fractures to any great depth and have a hydraulic conductivity less than 1 x 10<sup>-8</sup> m/s (or are essentially impervious).
- Along the southern pit perimeter (BGC04-03), above 1150 m, wall rocks are comprised of a highly fractured, blast damaged rock mass. Hydraulic conductivity above 1150 m ranges between approximately 1x10<sup>-5</sup> m/s and 1 x 10<sup>-6</sup> m/s.
- An average hydraulic conductivity of about 1 x10<sup>-7</sup> m/s was determined for left abutment area between 1147 and 1154, with hydraulic conductivity about 1 x10<sup>-8</sup> m/s above this zone and 1 x10<sup>-9</sup> m/s below.

For the purposes of estimating seepage losses through the southern perimeter, we have assumed the following:

- Because of the impervious rock mass below 1143 m, the majority of seepage losses will occur through the blast damaged upper wall rocks.
- As the observed range of water of water levels in the Zone II Pit is well below 1143 m, a
  free flowing water face will develop in the blast damaged wall rocks of the Zone II pit,
  above 1143 m.
- Very little flow will occur below the left abutment, through wall rocks along the eastern perimeter of the Faro Pit.

A series of simple, hand drawn flow nets, were constructed using Cross Section B-B' from Drawing 9, to estimate seepage losses in this area. Based on the assumption that a free flowing water surface develops on the upper wall of the Zone II pit, the hydraulic gradient along this cross section was calculated to be approximately 0.2. The approximate seepage loss per metre length was calculated to range between approximately 0.3 m³/day and 3 m³/day. Assuming seepage occurs over a perpendicular distance of approximately 240 m, measured from the toe of the left abutment, the resulting estimated total seepage quantity is approximately 72 m³/day to 720 m³/day.

### Southwest Wall (former Faro Creek Valley)

As discussed previously the overburden soils have a hydraulic conductivity of about 1x10<sup>-6</sup> m/s and the underlying bedrock has a hydraulic conductivity of 5x10<sup>-6</sup> m/s. The upper portion of the bedrock has a hydraulic conductivity about ½ of an order of magnitude than the valley fill sediments. For this preliminary assessment we have assumed that the seepage will occurred through a 25 m thick zone have a width of 150 m. Applying Darcy's Law and with assumed representative values for hydraulic conductivity and gradient of 5 x 10<sup>-6</sup> m/s and 0.1, respectively, the estimated seepage through this zone was calculated to be about 162 m<sup>3</sup>/day.

These sediments are overlain by at least another 8 m of waste rock (to el. 1181±). The hydraulic conductivity of the waste rock is expected to be at least two orders of magnitude higher than the in situ sediments. Seepage through the rockfill is not an issue if the pit pond water level is maintained below Elevation 1168 m amsl. Additional investigation will need to be performed in the former Faro Creek area to determine the need for a seepage cut off.

#### 4.4.2 Seepage Cut-off Elements

Two different grout curtains are proposed; a triple line beneath the dam and a double line in the abutment areas extending for 120 m along the right abutment (Figure 4). Beneath the Zone 1 core material consolidation grouting is proposed to an elevation of 1139 m. The rock mass is characterized by at least five joint sets, generally inclined from the vertical to varying degrees. Therefore, the proposed orientation of the grout holes is vertical, which will result in the grout holes intersecting all fracture systems. In general, a rock mass having a hydraulic conductivity of about 1 X10<sup>-7</sup> m/s or greater is considered "groutable" with Portland cement-based grouts.

The rock mass below the foundation area, under the current road, is highly permeable with hydraulic conductivity greater than 1x10<sup>-4</sup> m/s. Consolidation grouting, with final spacing of 0.5 m is proposed to seal the highly fractured rock. It has been assumed that at least 3 m of stripping will be required in the core trench to reach bedrock in the foundation that is intact enough to benefit from consolidation grouting. The need for this grouting and core trench is based on the drilling and hydraulic testing performed at BGC04-02. The purpose of the consolidation grouting is to strengthen the rock mass under the core contact area and to fill the voids with grout, thereby creating a grout sealed cap through which the grout curtain can be constructed.

The triple line grout curtain for the foundation area was selected based on the results of drilling and hydraulic conductivity testing at BGC04-02. These results combined with the low seismic velocities measured in the right abutment pillar area indicate highly fractured rock in many areas. The double line of grouting proposed for the abutments will be performed similar to the triple line, leaving the center line un-grouted initially and then testing the need to extend the double line to a triple.

The grout curtain will tie in to the zone of relatively impermeable rock expected to be located below Elevation 1136 m. The bottom of the grout curtain has been set at Elevation 1130 m in the foundation area beneath the road. This will provide at least 6 m of overlap into the lower impervious rock mass. In the left abutment area the base of the grout curtain can be tentatively set at elevation 1159 m. In the right abutment the grout curtain should extend to elevation 1143 m (as assumed in the original conceptual design). Additional drilling and water pressure testing must be performed to finalize the grout curtain details

The grout curtain is expected to decrease seepage losses into the Zone II Pit by one to two orders of magnitude (0.7 m³/day to 72 m³/day). Detailed seepage analyses should be undertaken at later design stages to confirm the expected seepage quantities.

## 5.0 QUANTITIES AND COST ESTIMATE

Table 2 presents a summary of the estimated quantities, unit prices and costs for the plug dam and grout curtain, based on the central impervious core section shown in Drawing 12.

The unit rates used for the various items are based on rates, which have been used for previous estimates at the site. As a starting point, the following rates were used by BGC for Faro earthworks in the past:

- Unit prices assume use of large-scale equipment.
- Excavate and load soil- \$1.50/m<sup>3</sup>.
- Haul- \$0.18/tonne-km
- Dump and spread- \$0.50/m<sup>3</sup>
- Compact- \$0.50/m<sup>3</sup>
- Excavate and load rockfill- same as for soil, assuming no blasting

After an initial unit rate was derived based on the above factors, further adjustments were made on the basis of recent bid prices for the breach of the Fresh Water Supply Dam Breach Project done in late 2003 and other cost estimates provided for various Faro Mine site closure tasks.

In summary, the estimated cost is \$4.1 million, which includes a 25% contingency. Major items that are not included in this estimate are:

- Site investigations and engineering.
- · Permits and regulatory approvals.
- Detailed access for work.
- Resident engineering and construction quality control and quality assurance.
- Surveying.
- Dam Instrumentation.
- Escalation and extra work allowances.

A lump sum allowance of \$60,000 was included to cover the cost of relocating the discharge pipeline from the Zone II pit and the diversion ditch on the left abutment. This work could be done in advance under a separate contract or by mine site staff. The following sections summarize each of the items in more detail.

A lump sum allowance of \$90,000 was included for mobilization of equipment.

#### 5.1.1 Excavation

Excavation includes bulk overburden excavation and stripping and core trench rock excavation.

### 5.1.1.1 Bulk Overburden Excavation and Stripping.

Bulk overburden excavation and stripping includes removal of the mine haul road base under the dam footprint, removal of the left bank diversion ditch berm and liner as well as the accumulated colluvial debris and loose rock on the abutment slopes. An average thickness of 0.5 m was assumed over the entire dam footprint. The excavated material would be hauled to a designated waste dump site assumed to be on the existing waste rock dumps, within 1 km of the dam site. This also includes excavation of the 3 m deep core trench, assuming all the excavation will be of overburden material.

#### 5.1.1.2 Core Trench Rock Excavation

This includes bedrock trimming required on the right abutment in order to prepare the bedrock slopes for placement of the Zone 1 impervious core material. This excavation is expected to involve a very limited amount of blasting. The excavated material will be hauled to the designated waste site, assumed to be within 1 km of the dam.

#### 5.1.2 Foundation Preparation

Foundation preparation includes all the work required to prepare the contact area prior to placement of the impervious fill. This includes scaling and cleaning, followed by slush grouting and dental concrete as required.

Scaling and cleaning involves a lot of hand labour to remove loosened pieces of rock and debris after the completion of the rock excavation in the core contact area. Any cracks or voids filled with unconsolidated materials must be cleaned out, at least to a depth equal to three times their width. The open cracks are then backfilled with dental concrete or slush grout depending on their width. In areas where steep side "steps" of rock remain, concrete fillets must be placed to achieve a 1:1 slope.

Prior to placement of impervious fill, the core contact area must be blown clean of loose debris using compressed air.

This item also includes lump sum allowances for relocating the pipeline from the Zone II pumping well and re-directing the left abutment runoff diversion ditch. Currently, the diversion ditch is breached in the vicinity of the dam site and water is flowing over the left abutment rock slope, across the dam foundation and into the Faro pit. Water in the diversion ditch comes from the waste dumps and slopes south of the dam. It may be possible to widen the bench at the crest of the dam and have the water flow directly into the Faro pit with the increased water level behind the plug dam. The pump well discharge could then be routed across the waste dump material and discharge into the diversion ditch. Discussion with mine site staff will be required to further assess these issues.

## 5.1.3 Foundation Grouting

The proposed foundation grouting consists of two components; consolidation grouting beneath the core and curtain grouting that extends from the left abutment, across the base of the road and up to the crest of the right abutment. The centreline of the grout curtain is centered on the upstream one-third point of the core contact, Figure 12. From the right abutment crest, the grout curtain extends for another 110-120 m to the west, along the rock pillar between the main pit and the Zone II Pit, (Drawing 5). The grout holes will be collared on an excavated bedrock surface. Some rock removal in this area may be done during construction, which may require realignment of the grout curtain to suit site conditions.

#### 5.1.3.1 Consolidation Grouting

Consolidation grouting will be carried out immediately following bulk excavation and stripping is completed in the dam foundation area. Grouting involves a progressive sequence of drilling and grouting. A primary spacing of 3 m was assumed. In the consolidation grouting it was assumed that a round of drilling of secondary holes, spaced at 1.5 m centers would be required. High taking secondary holes will require at least one more split spaced hole (tertiary) to be drilled and grouted. For estimating purposes, it was assumed that all primary holes (3 m c-c) and all secondary holes (1.5m c-c) will be drilled and grouted. One-half (50%) of the tertiary holes will be drilled and grouted.

Cement takes in the primary holes were assumed to be "High" (225 kg/m). Takes in the secondaries was assumed to be "High" (225 kg/m), with "moderately high" takes (110 kg/m) in the tertiary holes, and "low" (15 kg/m) in the quaternary holes. The use of sulphate resistant cement is recommended due to the presence of sulphides in the dam foundation rocks.

#### 5.1.3.2 Curtain Grouting

Foundation grouting will be carried out soon after the bulk excavation and stripping is completed and following final foundation preparation. Curtain grouting in the foundation area will be performed following completion of the consolidation grouting. The curtain grouting involves a progressive sequence of drilling and grouting. A primary hole spacing of 3 m was assumed. It was assumed that a split spacing closure sequence would be followed, in which holes are initially drilled at a wider spacing, say 12 m c-c, then grouted. Next, holes are drilled halfway in between the first set of holes and grouted. The process is repeated until all the holes are at a 3 m c-c primary spacing. Depending on the grout takes in this stage of holes, additional (secondary) holes spaced 1.5 m from high taking primary holes will be drilled and grouted as required. High taking secondary holes will require at least one more split spaced hole (tertiary) to be drilled and grouted. For estimating purposes, it was assumed that all primary holes (3 m c-c) will be drilled and grouted. One-half (50%) of the secondary holes will be drilled and grouted and 25% of the tertiary holes (0.75 m c-c) will be drilled and grouted.

Cement takes in the primary holes were assumed to be "Moderate" (75 kg/m). Takes in the secondaries was assumed to be "Moderately Low" (37 kg/m), with "low" takes (15 kg/m) in the tertiary holes. The use of sulphate resistant cement is recommended due to the presence of sulphides in the dam foundation rocks.

Drill holes are expected to be 75 mm diameter rotary drilled vertical holes up to about 40 m deep. In the left abutment and dam foundation, it was assumed that the entire hole would be drilled to the bottom, then grouted from the bottom of the hole to the top in 3 m stages. Vertically drilled holes are expected to intersect all of the discontinuities in the rock mass, and will help to maintained stable hole conditions. It is expected that drilling of inclined grout holes will be problematical, especially in the right abutment.

In the right abutment, the upper 10 m of hole are expected to be in poor rock conditions. Therefore, top down grouting was assumed in this section of the hole. In this method, the hole is only drilled to a depth of one grout stage (3 m), then, grouted. When the grout has set, the hole is re-drilled to the bottom of the first stage and deepened by another 3 m. The lower 3 m stage is then grouted. Below 10 m, it is expected that ground conditions will improve to allow drilling to the bottom of the grout curtain. The rest of the hole is then grouted from the bottom up in 3 m stages, as proposed for the left abutment and dam foundation grout holes.

As an option, drilling and grouting of the right bank holes in the pillar area, to the right of the dam crest, can be done after the dam is constructed, but before water is allowed to rise behind the dam. Access to the top of the right abutment can then be provided over the top of the completed dam. Otherwise, a temporary access road will be required from the top of the right abutment down to the grout curtain centreline.

Prior to grouting, each grout hole will be water pressure tested in 3 m intervals. This will serve as a check on rock mass permeability and the effects of closure as grouting progresses.

#### 5.1.4 Embankment Materials

The unit prices for the dam embankment materials were derived from the assumptions listed at the beginning of this section.

The Zone 1 impervious core material is assumed to be obtained from on top of the left abutment. Unit prices reflect a short one-way haul distance, moisture conditioning plus the price for excavating, loading, hauling, placing and compacting the fill.

The Zone 2a and 2b fine and coarse filters are assumed to come from existing granular borrow areas located adjacent to the North Fork Rose Creek or on top of the Northeast waste dump, both of these sites are within 3 km of the dam. The unit price covers bulk excavation of the granular material, processing (washing and screening), loading, hauling, placing, spreading and compacting.

The Zone 3 rockfill assumes clean, non-acid generating rockfill to be obtained from the waste rock dumps around the Faro Pit within a 2 km one way haul distance. The price includes excavation, loading, hauling, placement and compaction. No costs have been included for environmental testing and monitoring of the rockfill material, assuming that a clean, acceptable source has been identified prior to construction.

**Table 2 Faro Pit Plug Dam Construction Cost Estimate** 



## 6.0 CONCLUSIONS AND RECOMMENDATIONS

A conceptual design for the Plug Dam was developed on the basis of a preliminary geotechnical investigation. The proposed concept is an earth and rockfill dam with a central impervious core, founded on bedrock. A significant amount of consolidation grouting will be required underneath the foundation to fill in the highly broken rock. A grout curtain will be required beneath the dam foundation to tie-in to low permeability rock below Elevation 1136 m.

The right abutment is a critical element of the design due to the proximity of the Zone II Pit. The pillar of rock between the Faro Pit and the Zone II Pit is traversed by several fault zones, which were mapped in the open pit. The rock mass is expected to be of poor quality due to the presence of these faults and the fact that the pit walls on both sides of the pillar are affected by blast damage.

The proposed design of the dam utilizes locally obtainable materials, and is relatively easy to construct within one construction season. The estimated capital cost of this alternative is \$4.1 million, excluding mobilization, demobilization, escalation and extra work allowances.

Further investigation of the Plug Dam and the Faro Creek areas is required to advance the design beyond the conceptual level. Such a program was outlined in the original conceptual design report. A critical component of the next phase of investigation is to determine the depth of the core trench cut-off required and to confirm the type of seepage control required for the dam and foundation. This aspect will be required to confirm the eventual configuration of the dam section, as well as the best alignment of the structure to avoid potentially costly foundation treatment measures.

## 7.0 CLOSURE

We trust that this information will meet with your requirements at this time. Should you have any questions or require any additional information, please do not hesitate to contact the undersigned.

Yours truly,

**BGC** Engineering Inc.

Per

Gerry Ferris, M.Sc., P.Eng.

Geotechnical Engineer

Reviewed by:

Holger Hartmaier, M.Eng., P.Eng. Senior Geotechnical Engineer

## **Bibliography**

- BGC Engineering Inc. 2004 Faro Pit Plug Dam Conceptual Design Report. Report prepared for SRK Consulting Inc. and Deloitte & Touche Inc., dated June 30, 2004
- Hvorslev, J. (1951). "Time Lag and Soil Permeability in Groundwater Measurements", Memorandum to Rob Dunsmore, Aquila Networks Canada, August 9, 2002.
- Robertson GeoConsultants Inc., (1996), Anvil Range Mining Complex- Integrated Comprehensive Abandonment Plan (ICAP), prepared for Anvil Range Mining Corporation, RGC Report No. 033001/3, Drawing 4-7, dated November 1996.
- Robertson GeoConsultants Inc., (1997), Anvil Range Mining Complex- Integrated Comprehensive Abandonment Plan (ICAP), prepared for Anvil Range Mining Corporation, RGC Report No. 033001/3, Appendix F, January, 1997.
- Steffen, Robertson & Kirsten (B.C.) Inc. (SRK), (1991), "Water Quality Assessment Tailings Disposal in the Faro Pit", Prepared for Kilborn Limited, July, 1991.
- Steffen, Robertson & Kirsten (B.C.) Inc. (SRK), (1993), "Groundwater Investigation, North Fork of Rose Creek, Faro Mine, Yukon Territory", Prepared for Anvil Range Mining Corporation, December, 1993.






Photo 1a looking downstream at Plug Dam location.




Photo 1b looking towards Faro Creek location.

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

#### **PLUG DAM & FARO CREEK**

PROJECT No.	DWG. No.	REV.
0257-027-02	1	0




Photo 2a overview of the right abutment and "pillar" area between Faro Main Pit and Zone II Pit.




Photo 2b looking at right abutment from crest of left abutment.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

### Deloitte & Touche



# BGC Engineering Inc. AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

#### **RIGHT ABUTMENT**

PROJECT No.	DWG. No.	REV.
0257-027-02	2	0



Photo 3 overview of left abutment.

OCT 2004 DRAWN SLF		BGC ENGINEERING I	NC.	PROJECT PLUG DAM CON	NCEPTUAL DESIGN N	0. 2
REFERENCED DRAWING DESCRIPTION AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC	BGC	AN APPLIED EARTH SCIENCES COMPA  Calgary, Alberta Phone: (403)			BUTMENT	
PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.	CLIENT	Deloitte & Touche		PROJECT No. <b>0257-027-02</b>	DWG. No.	REV.



Photo 4 core collected from BGC04-02.

DATE: OCT 2004	DRAWN SLF		BGC ENGINE	ERING INC.	PROJECT PLUG DAM CO	NCEPTUAL DESIGN N	O. 2
AS A MUTUAL PROTE OURSELVES, ALL REI THE CONFIDENTIAL I	DRAWING DESCRIPTION CTION TO OUR CLIENT, THE PUBLIC AND PORTS AND DRAWINGS ARE SUBMITTED FOR NFORMATION OF OUR CLIENT FOR A SPECIFIC	BGC	AN APPLIED EARTH SCIE	Phone: (403) 250-5185	TITLE	C04-02	
DATA, STATEMENTS,	ORIZATION FOR USE AND/OR PUBLICATION OF TOONCLUSIONS OR ABSTRACTS FROM OR PORTS AND DRAWINGS IS RESERVED PENDING OVAL.	CLIENT	Deloitte & Touche		PROJECT No. <b>0257-027-02</b>	DWG. No.	REV.



Photo 5 core collected from BGC04-03.

DATE: OCT 2004	DRAWN SLF		BGC ENGINE	ERING INC.	PROJECT PLUG DAM CO	NCEPTUAL DESIGN N	NO. 2
AS A MUTUAL PROTE OURSELVES, ALL REF THE CONFIDENTIAL I	DRAWING DESCRIPTION CTION TO OUR CLIENT, THE PUBLIC AND ORTS AND DRAWINGS ARE SUBMITTED FOR NFORMATION OF OUR CLIENT FOR A SPECIFIC	BGC	AN APPLIED EARTH SCI	Phone: (403) 250-5185	TITLE	C04-03	
DATA, STATEMENTS,	ORIZATION FOR USE AND/OR PUBLICATION OF TOONCLUSIONS OR ABSTRACTS FROM OR PORTS AND DRAWINGS IS RESERVED PENDING OVAL.	CLIENT	Deloitte & Touche		PROJECT No. <b>0257-027-02</b>	DWG. No.	REV. 0




Photo 6 core collected from BGC04-04

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTENAPPROVAL.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

### Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT	
	PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

### BGC04-04

PROJECT No.	DWG. No.	REV.
0257-027-02	6	0



Photo 7a waste rock and upper part of organics.



Photo 7b view of wall of test pit, showing waste rock, organics and the lower silty sand.



Photo 7c base of test pit.

CLIENT:

## Deloitte & Touche

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

	-	-	-	-	-
-	-	-	-	-	-
-	-	-	-	-	-
REV.	DATE	REVISION NOTES	DRAWN	CHECKED	APPROVED

SCALE:	N/A	and the same of th
DATE: OCTO	BER 2004	
DRAWN:	SLF	
DESIGNED:	GWF	
CHECKED:	GWF	
APPROVED:		

PROJECT PLUG DAM CONCEPTUAL DESIGN NO. 2					
TITLE					
BGCTP04-01					
PROJECT No.	DWG. No.	REV.			



# BGC Engineering Inc. AN APPLIED EARTH SCIENCES COMPANY

Calgary Alberta Phone: (403) 250-5185



Photo 8a transition from waste rock, organics to silty sand.



Photo 8b view of base of pit, note sloughing of waste rock.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

#### **BGCTP04-02**

PROJECT No.	DWG. No.	REV.
0257-027-02	8	0



Photo 8a upper part of test pit.



Photo 8b base of test pit.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

**BGCTP04-03** 

PROJECT No.	DWG. No.	REV.
0257-027-02	9	0



Photo 10a upper part of test pit.



Photo 10b upper soil, just below the organics.



Photo 10c base to test pit.

CLIENT:

## Deloitte & Touche

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

	-	-	-	-	-
-	-	-	-	-	-
-	-	-	-	-	-
REV.	DATE	REVISION NOTES	DRAWN	CHECKED	APPROVED

SCALE:	N/A	
DATE: OCTO	BER 2004	
DRAWN:	SLF	
DESIGNED:	GWF	
CHECKED:	GWF	
APPROVED:		

PROJECT PLUG DAM CONCEPTUAL DESIGN NO. 2				
TITLE BGCTP04-04				
PROJECT No.	DWG. No.	REV.		
0257-027-02	10	0		





Photo 11a upper part of test pit.



Photo 11b lower part of test pit.

SC	ALE:	N/A	DESIGNED:	GWF	
DA	TE:	OCTOBER 2004	CHECKED:	GWF	
DR.	AWN:	SLF	APPROVED:		

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT		
	PLUG DAM CONCEPTUAL DESIGN NO. 2	

BGCTP04-05

PROJECT No.	DWG. No.	REV.
0257-027-02	11	0



Photo 12a showing the organic soil.



Photo 12b upper portion of soil deposit.



Photo 12c base of test pit.

CLIENT:

## Deloitte & Touche

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

	-	-	-	-	-
-	-	-	-	-	-
-	-	-	-	-	-
REV.	DATE	REVISION NOTES	DRAWN	CHECKED	APPROVED

SCALE:	N/A	
DATE: OCTO	BER 2004	
DRAWN:	SLF	
DESIGNED:	GWF	
CHECKED:	GWF	
APPROVED:		

PROJECT PLUG DAM CONCEPTUAL DESIGN NO. 2				
BGCTP04-06				
PROJECT No.	DWG. No.	REV.		
0257-027-02	12	0		



# BGC Engineering Inc. AN APPLIED EARTH SCIENCES COMPANY

Calgary Alberta Phone: (403) 250-5185



Photo 13, till dump sample location. Soil sample GWF 22 collected from here.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

PROJECT No.	DWG. No.	REV.
0257-027-02	13	0



Photo 14a, photo of till dump prior to sample collection.



Photo 14b, sample GWP 23 collected.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

PROJECT No.	DWG. No.	REV.
0257-027-02	14	0



Photo 15a dump face prior to sampling.



Photo 15b, Soil sample GWF24 collected

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

PROJECT No.	DWG. No.	REV.
0257-027-02	15	0



Photo 16a, surface prior to sampling.



Photo 16b, following collection of sample GWF 25.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

PROJECT No.	DWG. No.	REV.
0257-027-02	16	0




Photo 17a, prior to disturbance.



Photo 17b, following collection of sample GWF 26.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

PROJECT No.	DWG. No.	REV.
0257-027-02	17	0



Photo 18a, prior to disturbance.



Photo 18b, following collection of GWF 27.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

PROJECT No.	DWG. No.	REV.
0257-027-02	18	0



Photo 19a, prior to sampling.



Photo 19b, following collection of sample GWF 28.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

PROJECT No.	DWG. No.	REV.
0257-027-02	19	0



Photo 120a, face of dump prior to disturbance.



Photo 20b, collection of sample GWF 29.

SCALE:	N/A	DESIGNED:	GWF
DATE:	OCTOBER 2004	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

## Deloitte & Touche



# **BGC** Engineering Inc.

AN APPLIED EARTH SCIENCES COMPANY


Calgary, Alberta. Phone: (403) 250-5185


PROJECT

#### PLUG DAM CONCEPTUAL DESIGN NO. 2

TITLE

PROJECT No.	DWG. No.	REV.
0257-027-02	20	0





SCALE:	As Shown	DESIGNED:	GWF	
DATE:	November 2004	CHECKED:	ННН	
DRAWN:	JMS	APPROVED:		

CLIENT: Deloitte & Touche



# **BGC** Engineering Inc.


AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta. Phone: (403) 250-5185

#### PLUG DAM - CONCEPTUAL DESIGN NO. 2

#### SITE LOCATION PLAN

PROJECT No.	FIGURE No.	REV.
0257-027-02	1	0



**Photo Data:** 

Date: July 25, 2003 Scale: 1:11,800 Approx. CLIENT:

## Deloitte & Touche

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

	-	-	-	-	-	
		-				
-	-	-	i	-	-	
		-				
-	-	-	Ī	-	-	
		-				
REV.	DATE	REVISION NOTES	DRAWN	CHECKED	APPROVED	

SCALE:	As Shown	
PATRIOVE	MBER 2004	
DRAWN:	SLF	
DESIGNED:	GWF	
CHECKED:	ННН	
APPROVED:		


PROJECT	PLUG DAM CONC	EPTUAL DESIGN NO	. 2				
TITLE	AERIAL PHOTOGRAPH SHOWING CURRENT SITE CONDITIONS						
PROJECT	PROJECT No. FIGURE No. REV.						


0257-027-02 2 0





# BGC Engineering Inc. AN APPLIED EARTH SCIENCES COMPANY


algary Alberta Phone: (403) 250-5185




























**Core Logging Sheet - Fracture Logging** 

Run 1 6.07 FO PL SM Calcite 46 Iron stained Tight  7.52 FO PL R None 59 Iron stained Partially open Rubble in fracture.	ments
Run 1 6.07 FO PL SM Calcite 46 Iron stained light 7.52 FO PL R None 59 Iron stained Partially open Rubble in fracture.	nents
Run 1 6.07 FO PL SM Calcite 46 Iron stained light 7.52 FO PL R None 59 Iron stained Partially open Rubble in fracture.	nents
Run 1 6.07 FO PL SM Calcite 46 Iron stained light 7.52 FO PL R None 59 Iron stained Partially open Rubble in fracture.	
7.52 FO PL R None 59 Iron stained Partially open Rubble in fracture.	
Run 2 7.47 F PL R Calcite 20 Iron stained Open	
7.06 FO PL R None 41 Iron stained Partially open	
Run 3 No loggable fractures, broken core.	
Run 4 No loggable fractures, broken core.	
12 12 F ST VR None 44 None Open	
12.04 FO PL SM Calcite 50 None Partially open Rubble between	en these two.
12.00 FO PL SM/R None 56 None Tight	
Run 5 11.76 FO PL SM None 57 None Tight	
11.75 FO PL SM Calcite 57 None Partially open	
11.51 FO PL SM None 53 None Partially open Potential drill break	1_
11.48 FO C R None 46 None Partially open Rubble above and by	
13.23 FO PL SM None 56 None Partially open	
Run 6 13.03 F PL R Calcite 24 None Partially open	
12.95 F PL R Calcite 6 None Open	
14.85 FO PI SM Gouge material 57 None Open Fine phyllite mica a	ouge material.
Run 7 14.69 FO PL R None 52 None Partially open	,g
16.71 FO PL SM Calcite, sericite 30 None Tight	
16.61 FO PL SM Sericite 44 None Partially open	
Run 8 16.40 FO PL SM Sericite 40 None Tight	
16.18 F PL VR Sericite, silt 20 None Partially open	
16.15 F PL VR Silt 28 None Partially open	
18.19 F U VR Sericite, silt 52 None Open	
17.88 FO PL SM Sericite 47 None Tight	
Run 9 17.83 F PL R Silt 40 None Open	
17.31 FO PL SM Silt, sericite 40 None Tight	
17.22 F PL R Calcite 5 None Partially open	
10.71 L LL P Calaita 40 None Open	
Run 10 19.71 3 0 K Calcite 40 None Partially open	
Type: J Joint Shape: PL Planar Surface: P Polished Project Number: 02	257-027-01
F Fault C Curved K Slickensided Borehole: BGC04-0	
S Shear U Undulating SM Smooth Depth:19.8 m	
B Bedding ST Stepped R Rough Logged By: Gerry F	erris
FO Foliation I Irregular VR Very Rough Date: August 31, 20	

**Core Logging Sheet - Fracture Logging** 

	. /				ore Logging C		, , , , , , , , , , , , , , , , , , , ,	_	,¢
RUTU	hiper Dept	TAbe	shar	e Sur	ace Intil	Andle v	art Aries Arresali	Fracture Apera	
, 40	1.42	FO	PL PL	R R	None	85	AIL	P. Open	Comments
	1.42	FO	PL	R	None	75	Iron stained	Open	
1	1.49	FO	PL	R	None	80	-	Open	
	1.51 2.07	F FO	PL PL	SM SM	None calcite	75 86	Iron stained	tight tight	
	2.34	FO	PL	R	-	80	Iron stained	Open	Heavy Iron Staining
	2.43	J	PL	VR	calcite	28	Iron stained	Open	
	2.49 2.55	FO FO	PL PL	R SM	-	66 62	Iron stained Iron stained	tight P. Open	Light Iron Staining Heavy Iron Staining
2	2.62	J	PL	VR	-	32	Iron stained	Open	Heavy Iron Staining
	2.64	FO	PL	SM	calcite	66	-	P. Open	
	2.69 2.72	FO J	U PL	SM R	-	65 0	Iron stained Iron stained	P. Open tight	Light Iron Staining Heavy Iron Staining
	2.74	FO	PL	SM	-	64	-	tight	Tiody non-claiming
	3.05	FO	PL	R	-	70	Iron stained	P. Open	
	3.17 3.23	F FO	PL PL	SM R	Healed -	55 60	-	very tight tight	
	3.38	J	PL	SM	-	45	Iron stained	P. Open	Heavy Iron Staining
	3.4	FO	PL	R	-	60	Iron stained	tight	
	3.57 3.63	FO FO	PL PL	R SM	-	62 60	-	tight tight	
3	3.78	FO	PL	SM	-	60	Iron stained	tight	
	3.81 3.89	F FO	PL PL	VR SM	-	15 65	Iron stained	Open P. Open	Heavy Iron Staining
	3.89	FO	PL PL	R	-	59	Iron stained Iron stained	P. Open Open	Heavy Iron Staining Heavy Iron Staining
	4.04	FO	PL	R	-	53	Iron stained	Open	Heavy Iron Staining
	4.11 4.24	FO FO	ST PL	R R	calcite -	54 54	- Iron stained	Open P. Open	Heavy Iron Staining
	4.24	FO	ST	R	-	40	Iron stained Iron stained	P. Open Tight	neavy non Stailing
	4.94	J	PL	R	-	0	Iron stained	Partially Open	
1	5.05 5.24	J FO	PL PL	SM R	-	60 50	Iron stained	Tight Partially Open	
4	5.52	FO	PL	R	Rubble in joint	60	Iron stained Iron stained		Platey
	5.66	J	PL	R	-	15	Iron stained	Partially Open	Heavy iron staining
	5.75 6.73	J	U PL	VR R	-	10 30	Iron stained Iron stained		Heavy iron staining Heavy iron staining
5	6.88	J	PL	R	-	79	Iron stained	Partially Open	neavy non staining
	7.01	J	PL	R	-	0	Iron stained	Partially Open	
7	10.29 11.60	FO FO	PL PL	SM/R R	Calcite -	60 76	Iron stained	Partially Open Open	
8	11.79	FO	ST	R	-	80	-	Open	
٥	11.85	FO	PL	R	-	70	-	tight	
9	11.89 13.39	FO F	PL PL	VR R	silt -	64 18	- Iron stained	P. Open Tight	
J	13.92	FO	PL	R	-	64	Iron stained	Tight	Slight iron staining
10	14.50	F	PL	R	Calcite	21	-	Tight	Olimbat in an atalinin a
	14.80 15.14	F FO	PL PL	R SM	- Silt	46 56	Iron stained Iron stained	Tight	Slight iron staining
11	16.00	FO	PL	SM	Silt	15	-	Open	Possible drill break
	16.23 17.04	FO FO	PL PL	R SM	Silt	62 56	- Iron stained	Partially Open	Rubble Slight iron staining
	17.04	J	PL	R	-	1	Iron stained Iron stained	Open	Slight iron staining Slight iron staining
	17.29	J	PL	VR	Calcite	90	-	Open	
12	17.40 17.53	FO FO	PL PL	SM SM	-	50 56	Iron stained -	Partially Open Tight	Slight iron staining Broken core at this location
	17.67	FO	PL	SM	Calcite	61	-	Tight	
	17.68	F	PL	P	Calcite	3	-		Partially healed with calcite.
14	17.94 20.92	FO FO	PL PL	SM SM	Silt, Calcite calcite	62 40	-	Partially Open Open	
	21.02	J	PL	R	calcite	5	-	Open	
15	22.40	F F	PL PL	SM R	Sericite Sericite	24 30	-	Open P. Open	
15	22.47 22.52	FO	PL PL	SM	Sericite	24	-	P. Open P. Open	
	23.19	FO	PL	SM	Sericite	44	-	P. Open	
	23.52 23.76	FO FO	PL PL	SM SM	-	38 52	-	tight tight	
40	23.76	J	PL	R	- Healed	25	-	very tight	drill break
16	23.80	FO	PL	SM	-	52	-	tight	
	23.99 24.00	J F	PL PL	R R	Healed -	24 25	-	very tight tight	drill break
	24.00	FO	PL	R	-	80	-	tight	
4-	25.43	F	PL	R	-	71	-	P. Open	
17	25.51 25.57	FO F	PL PL	VR R	-	63 30	-	P. Open tight	Possible drill break
Туре:		Joint	Shape:	PL	Planar	Surface:	Р	Polished	Project Number: 0257-027-01
	F	Fault		С	Curved				Borehole: BGC04-03
		Shear Bedding			Undulating Stepped			Smooth Rough	Depth:21.03 m Logged By: Gerry Ferris
		Foliation			Irregular			Very Rough	Date: September 3, 2004
						_			

**Core Logging Sheet - Fracture Logging** 

Core Logging Sneet - Fracture Logging  Litting Special Comments  2.26 FO ST R - 68 Iron staining Open Heavy iron staining									
RUTTU	hiper Depty			Sur <sup>1</sup>	, i	Angle	nt Aris Alterail	or cture a	ture
AL MU	Tipe Dept	TAbe	Shar	Sur	Infill	Aug.C	ore Alter	Kig Wile.	Comments
2	2.26	FO	ST	R	-	68	Iron staining	Орсп	ricavy non staining.
2	2.41 2.54	FO J	U PL	SM SM	-	68 28	Iron staining Iron staining		Heavy iron staining. Heavy iron staining.
	2.92	FO	PL	R	Silt	73	-	Tight	riod y non otali ing
3	4.04	J	PL	VR	Silt	0	Iron staining	Tight	
	4.17 4.75	FO FO	PL PL	R SM	Silt Silt	32 65	-	Tight Partially open	Trace silt on joint surface.
4	5.31	J	PL	R	Silt	14	-	Partially open	
	5.56	J	PL	SM	-	20	-		Rubble, broken core
	6.05 6.20	FO J	PL PL	R R	Silt	56 40	-	Tight	Yellow silt on joint surface.
5	6.88	J	PL	SM	Silt	37	-	Tight Tight	Yellow silt on joint surface.
	7.24	FO	PL	SM	Silt	64	-	Partially open	į
6	7.90	FO	PL	SM	Sand	49	-	Filled	Sand and rubble, 38 mm thick.
7	8.76 9.88	FO FO	PL PL	SM SM	Silt and sand Silt	40 47	-	Filled Tight	Silt and Sand, 3 mm thick. Yellow silt on joint surface.
8	11.76	FO	PL	R	Sand	24	-	Filled	Sand, 3 mm thick.
	13.06	J	PL	SM	Silt	77	-	Filled	Silt, 3 mm thick.
9	13.20	FO	PL	SM	Silt	47	-	Tight	Cond 25 mm think
	13.31 14.33	FO J	ST PL	R SM	Sand Silt	46 22	-	Filled Tight	Sand, 25 mm thick. Silt coating on joint surfaces.
10	14.63	FO	PL	SM	Silt	47		Filled	Silt, 6 mm thick.
	14.73	J	ST	R	-	22	-	Partially open	
11	15.14 17.68	J J	PL PL	R R	Silt -	24 39	-	Partially open Tight	
12	17.00	FO	PL	SM		44	-	Coated	Rubble.
	17.78	FO	PL	SM	Silt and sand	50	-	Coated	
	18.16	FO	PL	SM	Silt	70	-	Rubble	
13	18.82 19.20	F F	ST PL	R SM	- Silt	86 80	-	Partially open Filled	Silt, 13 mm thick.
	19.43	FO	PL	R	-	26	-	Tight	
14	19.84	FO	PL	R	-	54	-	Partially open	
15	20.27 21.64	F F	PL PL	SM R	-	22 32	-	Partially open Tight	Drill break.
	23.70	<u> </u>	PL	R	Silt	48	-	Tight	Drill break.
16	23.55	FO	ST	R	Silt	48	-	Partially open	
17	24.13	FO	PL	SM	Silt	73	-	, ,	Reddish silt.
	24.49 25.70	F	PL PL	R R	- Silt	13 38	-	Tight Tight	
18	26.31	F	PL	R	Silt	5	-	Tight	
	26.34	FO	PL	R	Rubble	74	-	Tight	
	28.09 28.22	F	PL PL	VR SM	Silt Silt	56 62	-	Tight Filled	Silt, 25 mm thick.
40	28.30	F	PL	R	Sand	56	-	Filled	Sand, 25 mm thick.
19	28.37	F	PL	R	Silt	30	-	Partially open	
	28.40	FO	PL	SM	Silt	78	-	Coated	0.14 10
	28.45 28.88	FO J	PL PL	SM R	Silt Silt	74 12	-	Filled Partially open	Silt, 13 mm thick.
20	29.35	F	PL	R	-	30	-	Tight	
20	29.34	J	PL	R	-	90	-	Tight	
	29.44 30.66	FO F	PL PL	R R	Silt -	58 18	-	Tight Partially open	
21	30.91	F	PL	SM	Silt	63	-	Tight	
22	32.56	J	PL	R	-	10	-	Tight	
	32.99 33.66	FO F	PL PL	SM SM	Silt -	54 26	-	Partially open	
	33.66	FO	PL PL	SM R	- Silt	56 56	-	Tight Tight	
23	34.14	J	PL	R	-	0	-	Tight	
	34.23	F	PL	VR	Sand	86	-	Open	
	34.32 35.56	J	PL PL	SM R	- Silt	25 5	-	Tight Partially open	
24	36.14	FO	PL	SM	Silt	70	-	Tight	
	36.45	FO	PL	SM	Silt	75	-	Tight	
25	36.58	J	PL	R	-	25	-	Partially open	Donaible drill breek
Type:	37.36 <b>J</b>	J Joint	PL Shape:	R <b>PL</b>	Silt Planar	32 Surface:	<u>-</u> Р	Tight Polished	Possible drill break. Project Number: 0257-027-01
. , , , ,	F	Fault	3apo.		Curved		K	Slickensided	Borehole: BGC04-04
		Shear			Undulating			Smooth	Depth: 37.8 m
		Bedding Foliation			Stepped Irregular			Rough Very Rough	Logged By: Gerry Ferris Date: September 7, 2004
	10	. Unation		- 1	ogulai		AIX	vory Mougii	24.0. Coptombol 1, 2007

### BORING/MONITORING WELL # BGC04-01

Project: Plug Dam Investigation

Page 1 of 3
Project No.: 0257-027-01

Location: Faro Creek

Co-ordinates (m): 584341.00E, 6914552.00N

AN APPLIED EARTH SCIENCES COMPANY

Phone (403) 250 5185

Calgary, AB

Ground Elevation (m): 1167.100 Top Casing Elevation (m): 1167.530

First Water:

Stabilized Water Level: 8.84

Drill Designation: RIG 10

Drilling Contractor: Midnight Sun Drilling

Drill Method : ODEX

Sampling Method : Air Cuttings Return

Air Monitoring Device : Boring Diameter/Depth :

Start Date: 09 Aug 04 Finish Date: 14 Aug 04

Final Depth of Hole (m): 16.70

Logged by : MJM Reviewed by : GWF

Sample Type Sample No.	gic Description	Backfill	Instrument Details	SPT Blows per 300mm	VANE PEAK REMOLD	0 80 FIELD LA	B   •	UC/2 Pocket P
		 	Instru	SPT Blo	★ %1 W <sub>p</sub> % × —	Moisture	Content & W%	SPT (blows/300 SPT N
Fill Waste Rock		Cuttings						
Sand Silty, gravelly, trace clay; light broadlernating layers of finer and co	own. arser fragments.	Cu						
@ 6.10 m: mixed light grey, light	brown							
BGC ENGINEERING IN	(Continued on next page)							

### **BORING/MONITORING WELL # BGC04-01** Page 2 of 3 Project: Plug Dam Investigation Project No.: 0257-027-01 Start Date: 09 Aug 04 Location : Faro Creek Drill Designation: RIG 10 Finish Date: 14 Aug 04 Co-ordinates (m): 584341.00E, 6914552.00N **Drilling Contractor**: Midnight Sun Drilling Final Depth of Hole (m): 16.70 Drill Method: ODEX Ground Elevation (m): 1167.100 Sampling Method : Air Cuttings Return Logged by : MJM Top Casing Elevation (m): 1167.530 Reviewed by : GWF First Water: Air Monitoring Device: Stabilized Water Level: 8.84 Boring Diameter/Depth: Su - kPa per 300mm 40 80 120 160 Instrument Details UC/2 <u>VANE</u> FIELD LAB PEAK Lithologic Description REMOLD Pocket Pen /2 Sample Type Sample No. Blows Depth (m) Backfill (blows/300mm) Moisture Content & SPT N W% 0 80 @ 8.2 m: grey 9 10 2 • -12 Schistose Bedrock Dark grey to black. Bentonite -13 Silica Sand 15 (Continued on next page)

BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB Phone (403) 250 5185

### **BORING/MONITORING WELL # BGC04-01**

Project: Plug Dam Investigation

Location: Faro Creek Co-ordinates (m): 584341.00E, 6914552.00N

Ground Elevation (m): 1167.100 Top Casing Elevation (m): 1167.530

First Water:

Stabilized Water Level: 8.84

Drill Designation: RIG 10

Drilling Contractor: Midnight Sun Drilling

**Drill Method**: ODEX

Sampling Method : Air Cuttings Return

Air Monitoring Device:

Boring Diameter/Depth:

Page 3 of 3

Project No.: 0257-027-01

Start Date: 09 Aug 04 Finish Date: 14 Aug 04 Final Depth of Hole (m): 16.70

Logged by : MJM Reviewed by : GWF

Test Increment (m) Hydraulic Conductivity (m/s)	
Test Increment (m) Hydraulic Conductivity (m/s)	
Test Increment (m) Hydraulic Conductivity (m/s)	
Piezometric Details:  50 mm ID schedule 40 PVC pipe, screen as indicated. Stick-up of 0.31m.  Falling head water tests performed during drilling.  Test Increment (m) Hydraulic Conductivity (m/s) 0 - 4.3 6.2 x 10 -5 4.3 - 7.3 8.7 x 10 -6	
Piezometric Details:  50 mm ID schedule 40 PVC pipe, screen as indicated. Stick-up of 0.31m.  Falling head water tests performed during drilling.  Test Increment (m) Hydraulic Conductivity (m/s) 0 - 4.3 6.2 x 10 -5 4.3 - 7.3 8.7 x 10 -6	w <sub>t</sub> %
50 mm ID schedule 40 PVC pipe, screen as indicated. Stick-up of 0.31m.  Falling head water tests performed during drilling.  Test Increment (m) Hydraulic Conductivity (m/s) 0 - 4.3 6.2 x 10 -5 4.3 - 7.3 8.7 x 10 -6	
50 mm ID schedule 40 PVC pipe, screen as indicated. Stick-up of 0.31m.  Falling head water tests performed during drilling.  Test Increment (m) Hydraulic Conductivity (m/s) 0 - 4.3 6.2 x 10 -5 4.3 - 7.3 8.7 x 10 -6	
50 mm ID schedule 40 PVC pipe, screen as indicated. Stick-up of 0.31m.  Falling head water tests performed during drilling.  Test Increment (m) Hydraulic Conductivity (m/s) 0 - 4.3 6.2 x 10 -5 4.3 - 7.3 8.7 x 10 -6	
Falling head water tests performed during drilling.  Test Increment (m) Hydraulic Conductivity (m/s) 0 - 4.3 6.2 x 10 -5 4.3 - 7.3 8.7 x 10 -6	
Test Increment (m) Hydraulic Conductivity (m/s) 0 - 4.3	
0 - 4.3 6.2 x 10 - 5 4.3 - 7.3 8.7 x 10 - 6	
4.3 - 7.3   8.7 x 10 -6	
10.4 - 13.4 7.0 x 10 -6 13.4 - 16.5 1.1 x 10 -5	
Slug Test Results for screen zone (13.89 - 16.79 m)	
Falling Head k = 1.73 x 10 -5 m/s	
- Rising Head k = 1.80 x 10 -5 m/s	

**BGC ENGINEERING INC.** 

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

### DRILL HOLE # BGC04-02 Page 1 of 3 Project No.: 0257-027-01 Project: Plug Dam Investigation Location: Center of access road Drill Designation: Rig 6 Start Date: 31 Aug 04 **Drilling Contractor**: Midnight Sun Drilling Finish Date: 31 Aug 04 Co-ordinates (m): 584,927.00E, 6,914,164.00N Ground Elevation (m): 1152.6 Drill Method: Diamond Final Depth of Hole (m): 19.8 Depth to Top of Rock (m): Unknown Datum: Geodetic Core: NQ3 Fluid: Water Dip (degrees from horizontal): 90 Logged by: GWF Direction: -Casing: HW Cased To (m): 5.00 Reviewed by : GWF Total Core Casing/Core Diameter Recovery % Weathering Grade Instrument Details Fracture Angle wrt Core Axis Strength Index Lithologic Description Flush Return Hydraulic Conductivity Depth (m) Run No. RQD % (m/sec) 30° 60° 10<sup>-6</sup> 10⁴ 20 40 60 9.5 cm casing installed to a depth of 4.25 m prior to start of diamond drilling with BGC supervision. 2 HW 3 Driller reported hard drilling at 3 m depth. 4 NW 5 Muscovite - Biotite Schist Slightly weathered, foliated, light grey green, weak Muscovite - Biotite Schist. 1 R2 NQ3 6 Foliated at 45° wrt to core axis with folding on core W1 Light grey creamy scale. R1/ 2 R2 NQ3 7 W1/ R2/ R2 NQ3 (Continued on next page)


BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB Phone (403) 250-5185

### DRILL HOLE # BGC04-02 Page 2 of 3 Project: Plug Dam investigation Project No.: 0257-027-01 Start Date: 31 Aug 04 Location: Center of access road Drill Designation: Rig 6 Finish Date: 31 Aug 04 Co-ordinates (m): 584,927.00E, 6,914,164.00N Drilling Contractor: Midnight Sun Drilling Drill Method: Diamond Final Depth of Hole (m): 19.8 Ground Elevation (m): 1152.6 Depth to Top of Rock (m): Unknown Core: NQ3 Datum: Geodetic Fluid: Water Logged by : GWF Dip (degrees from horizontal): 90 Casing: HW Cased To (m): 5.00 Reviewed by : GWF Direction: -Total Core Recovery % Casing/Core Diameter Weathering Grade Fracture Angle wrt Core Axis Instrument Details Strength Index Lithologic Description Flush Return Hydraulic Depth (m) onductivity (m/sec) Run No. 30° 60° 40 60 Fresh R2 3 NQ3 9 Quartz, multiple fractures and healed zones, some <u>calcite infill, vuggy.</u> Quartz veins, multiple quartz healed fractures. No visible R5 return 5 cm quartz band at 10 m. NQ3 4 wo Heavy fractures, quartz healed, mica in matrix, thin White ey return calcité banding. R2 Thin calcite banding. Grey R1 5 NQ3 Multiple quartz bands, metal flecs. R3 -12 Grey Highly altered mica minerals, joints healed with R4 calcite and metalic material. WO Quartz with 2 major veins, one 5 cm grey phyllite W1 R5 vein and one 4 cm galena vein. 6 NQ3 13 Porous. R4 5 cm quartz vein at 13.5 m. Copper coloured metal flecs, calcite. Light grey/green. Light grey R2 NQ3 wo 15 ₽ R0/ Quartz bands. tinge 8 R4 NQ3 (Continued on next page) BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY Client: Deloitte & Touche Inc. Faro Mine Calgary, AB Phone (403) 250-5185

### DRILL HOLE # BGC04-02 Page 3 of 3 Project: Plug Dam Investigation Project No.: 0257-027-01 Start Date: 31 Aug 04 Drill Designation: Rig 6 Location: Center of access road Finish Date: 31 Aug 04 Drilling Contractor: Midnight Sun Drilling Co-ordinates (m): 584,927.00E, 6,914,164.00N Drill Method: Diamond Final Depth of Hole (m): 19.8 Ground Elevation (m): 1152.6 Depth to Top of Rock (m): Unknown Core: NQ3 Datum: Geodetic Fluid: Water Logged by: GWF Dip (degrees from horizontal): 90 Casing: HW Cased To (m): 5.00 Reviewed by : GWF Direction: -Total Core Recovery % Casing/Core Diameter Weathering Grade Instrument Details Fracture Angle wrt Core Axis Strength Index Lithologic Description Flush Return Hydraulic Conductivity (m/sec) Run No. 30° 60° 40 60 10-4 20





BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250-5185

### DRILL HOLE # BGC04-03 Page 1 of 4 Project: Plug Dam Investigation Project No.: 0257-027-01 Start Date: 03 Mar 04 Location: Right Abutment, Bench 1 Drill Designation: Rig 6 Co-ordinates (m): 584,896.00E, 6,914,159.00N Drilling Contractor: Midnight Sun Drilling Finish Date: 04 Sep 04 Drill Method: Diamond Final Depth of Hole (m): 21.0 Ground Elevation (m): 1158.2 Depth to Top of Rock (m): 0.6 Core: NQ3 Datum: Geodetic Fluid: Water Logged by: GWF Dip (degrees from horizontal): 90 Casing: NW Cased To (m): 0.91 Reviewed by : GWF Direction: -Total Core Casing/Core Diameter Recovery % Weathering Grade Instrument Details Fracture Angle wrt Core Axis Strength Index Lithologic Description Flush Return Hydraulic Depth (m) onductivity (m/sec) Run No. 40 60 20 Overburden NW Muscovite - Biotite schist. Metalic lustre R3 NQ3 1 Slightly weathered, moderately strong, foliated, grey Muscovite - Biotite schist. Foliated at 75° with respect to core axis. 2 R3/ 1.29 to 1.37 m: Quartz. 2 NQ3 R4 2.47 m: foliated at 60° wrt core axis. 3 3 R4 NQ3 W1 4 Dark grey Carbonaceous Schist. Slightly weathered, foliated, weak, black to dark grey Carbonaceous Schist. Some pyrite/sulphide minerals present. 5 R2 NQ3 6 R2/ No return R3 5 NQ3 Quartz. R5 Muscovite - Biotite Schist. WO R3 NQ3 Fresh, foliated, medium strong, grey to grey green 6 Muscovite-Biotite Schist. (Continued on next page) BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY Client: Deloitte & Touche Inc. Faro Mine

Calgary, AB

Phone (403) 250-5185

### DRILL HOLE # BGC04-03 Page 2 of 4 Project: Plug Dam Investigation Project No.: 0257-027-01 Start Date: 03 Mar 04 Location: Right Abutment, Bench 1 Drill Designation: Rig 6 Finish Date: 04 Sep 04 Co-ordinates (m): 584,896.00E, 6,914,159.00N Drilling Contractor: Midnight Sun Drilling Final Depth of Hole (m): 21.0 Drill Method: Diamond Ground Elevation (m): 1158.2 Depth to Top of Rock (m): 0.6 Core: NQ3 Datum: Geodetic Fluid: Water Logged by : GWF Dip (degrees from horizontal): 90 Reviewed by : GWF Direction: -Casing: NW Cased To (m): 0.91 Total Core Recovery % Casing/Core Diameter Weathering Grade Fracture Angle wrt Core Axis Instrument Details Strength Index Lithologic Description Flush Return Hydraulic Depth (m) Conductivity (m/sec) Run No. RQD % 30° 60° 40 60 Light metalic lustre 6 R3 NQ3 9 return R2 7 NQ3 ဍ 10 Dark grey with thin 3 mm grey-green bands. R4 Grey-green with thin bands of dark grey and occasional quartz within matrix. 11 NQ3 8 R2 WO 12 NQ3 9 Medium metalic lustre -13 R3/ R4 Light grey, foliated at 66° wrt core axis. At 14.83 m: 3 mm quartz intrusion at 14.83 m. 10 NQ3 R2 15 More porous structure, mottled grey-green and dark NQ3 11 grey. R1/ R2 (Continued on next page) BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY Client: Deloitte & Touche Inc. Faro Mine

Calgary, AB

Phone (403) 250-5185

### DRILL HOLE # BGC04-03 Page 3 of 4 Project No.: 0257-027-01 Project: Plug Dam Investigation Location: Right Abutment, Bench 1 Start Date: 03 Mar 04 Drill Designation: Rig 6 Drilling Contractor: Midnight Sun Drilling Finish Date: 04 Sep 04 Co-ordinates (m): 584,896.00E, 6,914,159.00N Final Depth of Hole (m): 21.0 Drill Method: Diamond Ground Elevation (m): 1158.2 Depth to Top of Rock (m): 0.6 Datum: Geodetic Core: NQ3 Fluid: Water Dip (degrees from horizontal): 90 Logged by: GWF Direction: -Casing: NW Cased To (m): 0.91 Reviewed by : GWF Total Core Casing/Core Diameter Weathering Grade nstrument Details Fracture Angle wrt Core Axis Strength Index Lithologic Description Flush Return Hydraulic Conductivity (m/sec) Depth (m) Run No. RQD % 30° 60° 40 60 15.98 m to 16.0 m: Massive quartz. Foliated at 45° wrt core axis. 11 R3 NQ3 Medium metalic lustre 12 NQ3 <u>17.24 m; 13 mm quartz vein.</u> 18 Foliated at 40° wrt core axis. Calcite or sericite on some fractures. WO 13 NQ3 19 Creamy light grey R2 -20 NQ3 14 R5 Massive quartz. <u>@</u> R2 NQ3 15 22 Creamy 22.53 m to 22.56 m: quartz vein. Quartz vein at 40° wrt core axis, 50 mm thick with a 23 vuggy surface and associated black metalic rocks. 16 R1 NQ3 (Continued on next page) BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250-5185

### DRILL HOLE # BGC04-03 Page 4 of 4 Project No.: 0257-027-01 Project: Plug Dam Investigation Location: Right Abutment, Bench 1 Drill Designation: Rig 6 Start Date: 03 Mar 04 Co-ordinates (m): 584,896.00E, 6,914,159.00N Drilling Contractor: Midnight Sun Drilling Finish Date: 04 Sep 04 Final Depth of Hole (m): 21.0 Ground Elevation (m): 1158.2 Drill Method: Diamond Datum: Geodetic Core: NQ3 Depth to Top of Rock (m): 0.6 Dip (degrees from horizontal): 90 Fluid: Water Logged by: GWF Casing: NW Cased To (m): 0.91 Reviewed by : GWF Direction: -Total Core Casing/Core Diameter Weathering Grade Instrument Details Fracture Angle wrt Core Axis Strength Index Lithologic Description Flush Return Hydraulic Conductivity (m/sec) Depth (m) Run No. RQD % 30° 60° 10<sup>-8</sup> 10.6 10-4 60 Light creamy grey 17 R2 NQ3 25 Backfilled with cement grout. 26 27 28 29 30 31 32

AN APPLIED EARTH SCIENCES COMPANY

BGC ENGINEERING INC.

Calgary, AB Phone (403) 250-5185

### DRILL HOLE # BGC04-04 Page 1 of 5 Project No.: 0257-027-01 Project: Plug Dam Investigation Drill Designation: Rig 6 Start Date: 07 Sep 04 Location: Left Abutment Co-ordinates (m): 584,978.00E, 6,914,192.00N Drilling Contractor: Midnight Sun Drilling Finish Date: 08 Sep 04 Ground Elevation (m): 1172.3 Drill Method: Diamond Final Depth of Hole (m): 37.8 Datum: Geodetic Core: NQ3 Depth to Top of Rock (m): 0.5 Dip (degrees from horizontal): 90 Fluid: Water Logged by: GWF Direction: -Casing: NW Cased To (m): 0.61 Reviewed by : GWF Total Core Casing/Core Diameter Recovery % Weathering Grade Fracture Angle wrt Core Axis Instrument Details Strength Index Lithologic Description Flush Return Hydraulic Conductivity Depth (m) Run No. 10-6 30° 60° 10-8 10-4 40 60 Creamy tan NW Quartz rubble, heavy iron staining. 1 1 R5 NQ3 Quartz with phyllite infill. Muscovite - Biotite Schist. W1 Slightly weathered; foliated; medium strong; light 2 grey. Muscovite - Biotite Schist. 2 R3 NQ3 More altered, higher mica content; foliated at 57° wrt core axis; most fractures are iron stained; fresh. 3 Dark grey to black. 3 NQ3 Minor chlorite. - 4 Creamy grey R2 5 NQ3 4 W0 50 mm quartz vein 6 High concentration of black crystals. NQ3 5 R3 Thinly banded grey, dark grey and white. 6 NQ3 (Continued on next page) BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB Phone (403) 250-5185

### DRILL HOLE # BGC04-04 Page 2 of 5 Project No.: 0257-027-01 Project: Plug Dam Investigation Drill Designation: Rig 6 Start Date: 07 Sep 04 Location: Left Abutment Co-ordinates (m): 584,978.00E, 6,914,192.00N Drilling Contractor: Midnight Sun Drilling Finish Date: 08 Sep 04 Ground Elevation (m): 1172.3 Drill Method: Diamond Final Depth of Hole (m): 37.8 Datum: Geodetic Core: NQ3 Depth to Top of Rock (m): 0.5 Dip (degrees from horizontal): 90 Fluid: Water Logged by: GWF Direction : -Casing: NW Cased To (m): 0.61 Reviewed by : GWF Total Core Casing/Core Diameter Recovery % Weathering Grade Instrument Details Fracture Angle wrt Core Axis Strength Index Lithologic Description Flush Return Hydraulic Conductivity Depth (m) Run No. RQD % 10-4 30° 60° 10-6 40 60 6 NQ3 9 Creamy grey 7 NQ3 -10 50 mm quartz vein. R3 -11 8 NQ3 Reddish tinge Dark grey, thinly banded with light grey-green. W0 NQ3 9 13 50 mm quartz vein. Light grey 10 R2 NQ3 Four quartz veins between 14.69 m and 14.81 m. One is 75 mm thick. -15 Creamy grey R2/ NQ3 11 R3 (Continued on next page) BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY Client: Deloitte & Touche Inc. Faro Mine Calgary, AB Phone (403) 250-5185

### DRILL HOLE # BGC04-04

Project: Plug Dam Investigation

Location: Left Abutment

Co-ordinates (m): 584,978.00E, 6,914,192.00N

Ground Elevation (m): 1172.3

Datum: Geodetic

Dip (degrees from horizontal): 90

Direction:-

Drill Designation: Rig 6

Drilling Contractor: Midnight Sun Drilling

Drill Method: Diamond

Core: NQ3 Fluid: Water

Casing: NW Cased To (m): 0.61

Start Date: 07 Sep 04

Finish Date: 08 Sep 04
Final Depth of Hole (m): 37.8
Depth to Top of Rock (m): 0.5

Page 3 of 5

Project No.: 0257-027-01

Logged by : GWF Reviewed by : GWF

Lithologic Description    Part   Part						eachig : Title Cacca To (m) :				
11	S Depth (m) Flush Return	Run No.	Weathering Grade	Strength Index	Casing/Core Diameter	Lithologic Description	Instrument Details		RQD%	
17	16	11			NQ3					
18	Creamy grey	12			NQ3	Multiple drill breaks in this zone.				
Grey green with some dark purple banding.  Dark purple inclusion. 19.81 to 19.91 m; this zone is covered and filled with a reddish-brown silt.  Quartz rubble.  Quartz rubble.  R2/R3 NQ3  Quartz rubble.  Park grey-green with some dark purple banding.  Quartz rubble.	8									
14 W0 1981 to 19.91 m: this zone is covered and filled with a reddish-brown silt.  15	ω Dark grey	13		R2	NQ3	1 25 mm quartz vein. j				
2 R2/R3 NQ3    Park grey-green with yellow silt cutting through foliation, mica.		14	W0	,	NQ3	Dark purple inclusion.  19.81 to 19.91 m: this zone is covered and filled with a reddish-brown silt.		•		
Dark grey-green with yellow silt cutting through foliation, mica.		15		R2/ R3	NQ3					
16 NQ3	3	16			NQ3	Dark grey-green with yellow silt cutting through		•		

BGC ENGINEERING INC.
AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB Phone (403) 250-5185

### DRILL HOLE # BGC04-04 Page 4 of 5 Project No.: 0257-027-01 Project: Plug Dam Investigation Start Date: 07 Sep 04 Location : Left Abutment Drill Designation: Rig 6 Drilling Contractor: Midnight Sun Drilling Finish Date: 08 Sep 04 Co-ordinates (m): 584,978.00E, 6,914,192.00N Drill Method: Diamond Final Depth of Hole (m): 37.8 Ground Elevation (m): 1172.3 Core: NQ3 Depth to Top of Rock (m): 0.5 Datum: Geodetic Fluid: Water Logged by : GWF Dip (degrees from horizontal): 90 Reviewed by : GWF Direction: -Casing: NW Cased To (m): 0.61 Total Core Casing/Core Diameter Recovery % Weathering Grade Fracture Angle wrt Core Axis Instrument Details Strength Index Lithologic Description Flush Return Hydraulic Conductivity (m/sec) Depth (m) Run No. RQD % 30° 60° R2/ NQ3 17 R3 24.92 m: 13 mm quartz vein. 25.07 m: 25 mm quartz vein. -25 -26 NQ3 Massive quartz. 18 27 R3 ₽ Creamy grey to whitish grey 19 NQ3 WO -28 R1/ R2 -29 20 NQ3 R2/ R3 -30 R4 21 NQ3 -31 R3 22 NQ3 (Continued on next page) BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY Client: Deloitte & Touche Inc. Faro Mine

Calgary, AB Phone (403) 250-5185

### DRILL HOLE # BGC04-04 Page 5 of 5 Project No.: 0257-027-01 Project: Plug Dam Investigation Location: Left Abutment Drill Designation: Rig 6 Start Date: 07 Sep 04 Co-ordinates (m): 584,978.00E, 6,914,192.00N Drilling Contractor: Midnight Sun Drilling Finish Date: 08 Sep 04 Final Depth of Hole (m): 37.8 Ground Elevation (m): 1172.3 Drill Method: Diamond Datum: Geodetic Core: NQ3 Depth to Top of Rock (m): 0.5 Dip (degrees from horizontal): 90 Fluid: Water Logged by: GWF Direction: -Casing: NW Cased To (m): 0.61 Reviewed by : GWF Casing/Core Diameter Weathering Grade nstrument Details Fracture Angle wrt Core Axis Strength Index Lithologic Description Flush Return Hydraulic Conductivity Depth (m) Run No. ROD % 10⁴ 30° 60° 22 NQ3 -33 Marble zone. 23 NQ3 -34 Creamy grey to whitish grey R3 Dark grey with thin quartz and dark grey (purplish) W0 banding. -35 24 NQ3 Marbled surface with dark grey and quartz, occasional zone of mica concentration, metalics. 36 NQ3 25 Massive, medium grained gabbro, mostly grey with R4 15% black specs. Backfilled with cement grout. 38 39 BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY Client: Deloitte & Touche Inc. Faro Mine

Calgary, AB

Phone (403) 250-5185

### TEST PIT # BGC TP04-01 Page 1 of 1 Project No.: 0257-027-01 Project: Plug Dam Investigation Location : Left abutment Excavator: Anvil's 235 Hoe Start Date: 13 Sep 04 Co-ordinates (m): 585036 E, 6914154 N Operator: John Salo Finish Date: 13 Sep 04 Comments: Excavated to maximum reach of excavator. Final Depth of Pit (m): 4.9 Ground Elevation (m): 1182.7 Datum: Geodetic Logged by : GWF Reviewed by : GWF Su - kPa 120 FIELD LAB VANE UC/2 Lithologic Description PEAK Sample Type Sample No. Pocket Pen /2 REMOLD Δ o Depth (m) Moisture Content W% 0 20 40 60 80 WASTE ROCK Cobbles to sand sized, reddish colour. **ORGANICS** Mix of topsoil, volcanic ash and decaying trees. 2 3 SAND Silty, some gravel, trace clay, trace cobbles; olive brown; moist; low plasticity; stiff. m GWF-01 0 - 5 Backfilled with excavcated material. No seepage. Some sloughing of waste rock and organic layer. 6 7 BGC ENGINEERING INC. Client: Deloitte & Touche Inc. Faro Mine AN APPLIED EARTH SCIENCES COMPANY Calgary, AB Phone (403) 250 5185

### TEST PIT # BGC TP04-02 Page 1 of 1 Project No.: 0257-027-01 Project : Plug Dam Investigation Location: Left abutment Excavator: Anvil's 235 Hoe Start Date: 13 Sep 04 Co-ordinates (m): 585060 E, 6914139 N Operator: John Salo Finish Date: 13 Sep 04 Ground Elevation (m): 1183.0 Comments: Excavated to maximum reach of excavator. Final Depth of Pit (m): 4.6 Datum: Geodetic Logged by : GWF Reviewed by : GWF Su - kPa 40 80 160 120 FIELD LAB VANE UC/2 Lithologic Description PEAK Sample Type Sample No. Δ Pocket Pen /2 REMOLD $\Diamond$ Depth (m) Moisture Content 20 40 80 60 WASTE ROCK Cobbles, some gravel, some sand; reddish colour. - 2 SAND (FILL) 3 Reddish colour. TOPSOIL Sand, organics, trace volcanic ash. 4 SAND 0 Silty, some gravel, trace clay, trace cobbles; moist; low plasticity; olive brown. Backfilled with excavcated material. 5 No seepage. Some sloughing of waste rock. 6 7

BGC ENGINEERING INC.
AN APPLIED EARTH SCIENCES COMPANY

Phone (403) 250 5185

Calgary, AB

### TEST PIT # BGC TP04-03 Page 1 of 1 Project No.: 0257-027-01 Project: Plug Dam Investigation Start Date: 13 Sep 04 Location: Left abutment Excavator: Anvil's 235 Hoe Co-ordinates (m): 585014 E, 6914179 N Operator: John Salo Finish Date: 13 Sep 04 Ground Elevation (m): 1183.1 Comments: Excavated to confirmation of bedrock surfational Depth of Pit (m): 4.0 Datum: Geodetic Logged by: GWF Reviewed by : GWF Su - kPa 80 160 40 120 FIELD LAB VANE UC/2 Lithologic Description PEAK Sample Type Sample No. Pocket Pen /2 Δ REMOLD 0 Depth (m) Moisture Content -- 0 20 40 60 80 TOPSOIL Black, organics SAND GWF-–⇔ ∆ Silty, gravelly, some clay, trace cobbles; moist; olive brown; low plasticity. 0.7 m: 39.1% silt, 41.2% sand, 19.7% gravel. m GWF ox-× 1.5 m: 38.8% silt, 41.4% sand, 19.8% gravel. - 2 m **GWF** $0 \times \times$ 2.4 m: 20.9% silt, 43.3% sand, 35.8% gravel. 3 ₩ > 3.2 m: 24.2% silt, 43.3% sand, 32.5% gravel. GWF 07 WEATHERED SCHISTOSE BEDROCK GWF 0 X Backfilled with excavated material. No seepage or sloughing. 5 6 7 **BGC ENGINEERING INC.** Client: Deloitte & Touche Inc. Faro Mine AN APPLIED EARTH SCIENCES COMPANY Calgary, AB Phone (403) 250 5185

### TEST PIT # BGC TP04-04 Page 1 of 1 Project: Plug Dam Investigation Project No.: 0257-027-01 Location: Left abutment Excavator: Anvil's 235 Hoe Start Date: 13 Sep 04 Co-ordinates (m): 585047 E, 6914196 N Operator: John Salo Finish Date: 13 Sep 04 Ground Elevation (m): 1184.8 Comments: Excavated to maximum reach of excavator. Final Depth of Pit (m): 4.5 Datum: Geodetic Logged by: GWF Reviewed by : GWF Su - kPa 80 160 40 120 FIELD LAB VANE UC/2 Lithologic Description PEAK Sample Type Sample No. Δ Pocket Pen /2 REMOLD Moisture Content W<sub>P</sub>% X 40 20 60 80 TOPSOIL Black organic topsoil and volcanic ash. GWF 11 SAND 0 Silty, some grave!, trace cobbles; moist; reddish brown. 0.5 m: 28.5% silt, 55.9% sand, 15.6% gravel. SILT GWF-0 AND SAND, some gravel, some clay, trace cobbles; moist; olive brown; low plasticity. - 2 3 GWF-3 $\gg \rightarrow$ Backfilled with excavated material. No seepage or sloughing. - 5 - 6 7 BGC ENGINEERING INC. Client: Deloitte & Touche Inc. Faro Mine AN APPLIED EARTH SCIENCES COMPANY Calgary, AB Phone (403) 250 5185

### TEST PIT # BGC TP04-05 Page 1 of 1 Project: Plug Dam Investigation Project No.: 0257-027-01 Excavator: Anvil's 235 Hoe Start Date: 13 Sep 04 Location: Left abutment Operator : John Salo Finish Date: 13 Sep 04 Co-ordinates (m): 585042 E, 6914243 N Comments: Excavated to maximum reach of excavator. Final Depth of Pit (m): 4.4 Ground Elevation (m): 1188.3 Logged by : GWF Datum: Geodetic Reviewed by : GWF Su - kPa 80 120 VANE FIELD LAB UC/2 Lithologic Description PEAK Sample Type Sample No. Δ Pocket Pen /2 REMOLD $\Diamond$ Depth (m) Moisture Content W% - 0 -20 40 60 80 TOPSOIL Black organics and volcanic ash. Silty, some gravel, trace clay; moist; reddish tan colour; low plasticity. SAND Silty, gravelly, some clay, trace cobble; moist; tan; low plasticity. m GWF 13 0 2 GWF 14 ⊗-Mn GWF-15 0 - 4 4.0 m: Some cobbles. GWF 16 0 Backfilled with excavated material. No seepage or sloughing. - 5 6 BGC ENGINEERING INC. Client: Deloitte & Touche Inc. Faro Mine AN APPLIED EARTH SCIENCES COMPANY Calgary, AB Phone (403) 250 5185

### TEST PIT # BGC TP04-06 Page 1 of 1 Project: Plug Dam Investigation Project No.: 0257-027-01 Excavator: Anvil's 235 Hoe Start Date: 13 Sep 04 Location: Left abutment Co-ordinates (m): 585062 E, 6914267 N Operator: John Salo Finish Date: 13 Sep 04 Ground Elevation (m): 1190.2 Comments: Excavated to maximum reach of excavator. Final Depth of Pit (m): 4.4 Logged by : GWF Datum: Geodetic Reviewed by : GWF Su - kPa 40 80 120 160 FIELD LAB VANE UC/2 Lithologic Description PEAK Sample Type Sample No. Δ Pocket Pen /2 REMOLD **\Q** ှ် Depth (m) Moisture Content W₂% × W<sub>L</sub>% 0 20 80 40 TOPSOIL Black organic soil and volcanic ash. SAND Silty, some gravel, trace clay; moist; tan. 1 SAND Silty, some gravel, trace cobbles; low plasticity to non-plastic; olive; moist. GWF-19 0 1.5 m: 23.9% silt, 51.0% sand, 25.1% gravel. 2 3 GWF-17 $0 \times\!\!\times$ 3.9 m: 31.6% silt, 57.0% sand, 11.4% gravel. 4 GWFm 0 4.2 m: 26.9% silt, 54.6% sand, 18.5% gravel. Backfilled with excavated material. No seepage or sloughing. - 5 6 7

BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY Calgary, AB

			TEST PIT #			F	Page 1 of	1								
Proje	ect : F	Plug D	am Investigation		Project No. : 0257-027-01											
Co-o Grou	rdina	tes (r levati		ilo	Start Date: 13 Sep 04 Finish Date: 13 Sep 04 th of excavator.Final Depth of Pit (m): 4.0 Logged by: GWF Reviewed by: GWF											
					1		Su - kPa									
					4	0 80	120	160								
(r	Sample Type	No.	Lithologic Desc	cription	VANE PEAK REMOLD	FIELD LA	B ▲	UC/2 Pocket Pe	n /2							
Depth (m)	nple	Sample No.			W <sub>p</sub> %	Mois	sture Conte	nt	WL%							
	Sar	Sar		× –	.0 40	0	<del></del>	- ×								
0  -  -  -			WASTE ROCK Boulders to sand sized particles, dominated by cobble s	ize; reddish brown.												
_ 1																
F																
-																
<u> </u>																
[																
}																
- - 3																
-																
-																
_																
<del>-</del> 4			Backfilled with excavated material.	-												
_			No seepage. Extensive sloughing of waste rock.													
-		1														
- - 5							İ									
-																
-																
[-																
<del>-</del> 6																
_																
-																
- 7																
<b>├</b> ′																
-																
<u> </u>			•													
<del>-</del> 8-		<u> </u>	A. MIN MARKET	.,												
1 1		IRC	GC ENGINEERING INC.													
	_ _		PPLIED EARTH SCIENCES COMPANY	Client: Deloitte & Touche In	c. Faro N	line										
$\lfloor B \rfloor$	GC	C	algary, AB Phone (403) 250 5185													

-		TEST PIT # BGC TP04-08			P	age 1 of								
Project :	Plug [	am Investigation		Project N	<b>o.</b> : 02	57-027-0								
	ates (r Elevati		Finish Da excavator.Final De Logged I	Start Date: 13 Sep 04 Finish Date: 13 Sep 04 Final Depth of Pit (m): 5.0 Logged by: GWF Reviewed by: GWF										
				Su - kPa										
			40	40 80 120 160										
ype	0.	Lithologic Description	VANE PEAK	FIELD LAB  ◆ ■	<b>▲</b>	UC/2 Pocket Pe								
Depth (m) Sample Type	Sample No.		REMOLD W <sub>P</sub> %	♦ □ Moistu	re Conter									
o Dep San	San		× –		0 — — 60	80								
		WASTE ROCK  Boulders to sand sized particles, dominated by cobbles; angular; reddish brown.												
		bounders to saint sized particles, dominated by couples, angular, redusin brown.												
1														
2														
		SAND (FILL)												
3		Some cobbles, some gravel, some silt; moist. Placed as part of a dump.												
4														
400	GWF-													
5 m	GWF- 20	Backfilled with excavated material.												
		No seepage. Extensive sloughing of waste rock.												
6														
٠														
7														
.8						l								
		GC ENGINEERING INC.	Touche Inc. Faro M	line										
BGC		PPLIED EARTH SCIENCES COMPANY												
GC	ANA	Client: Deloitte &	Touche Inc. Faro M	line										

_				TEST PIT # B	GC TP04-09			F	Page 1 o	f 1					
Proje	ect : F	Plug E	Dam Investigation			Project No. : 0257-027-01									
Co-o Grou	rdina	tes (r levati	of north dump n): E, N on (m): tic	Excavator : Anvil's 23 Operator : John Salo Comments : Excavat		Start Date: 13 Sep 04 Finish Date: 13 Sep 04 Final Depth of Pit (m): 4.2 Logged by: GWF Reviewed by: GWF									
	1 1						· · · · · · · · · · · · · · · · · · ·	Su - kPa							
							n 46								
							10 80	120	D 16						
	4			Lithologic Descri	ption	VANE PEAK	FIELD LAI		UC/2						
<del>_</del>	Туре	No.		J		REMOLD	• <b>I</b>	i .	Pocket F	Pen /2					
th (n	Sample Type	Sample No.					Mois	ture Conte	ent						
Depth (m)	San	San				W <sub>p</sub> % −	 20 40	0 — -		X					
—0 <del>—</del>			WASTE ROCK					<u>-</u>		,					
-			Boulders to sand sized particles, d	ominated by cobbles: a	nguiar: reddish brown										
-			boulders to saild sized particles, d	ommated by cobbles, a	ngalar, readistr brown.			•							
-															
<b>—</b> 1															
_															
- - -															
-															
— 2 -															
_															
_															
-															
— 3 –															
_															
_															
-															
<u> </u>							·								
_			Backfilled with excavated material												
_			Extensive sloughing of waste rock	. Dry.											
-															
<del></del> 5 															
<del>-</del>															
_															
- 6	İ														
- 0															
_								İ							
-															
- 7															
ļ '															
_															
_															
- 8	<u></u>				W 1. 12 W 1.										
L L L DOO ENOINEEDING INC															
			C ENGINEERING INC.		Client: Deloitte & Touche In	c. Faro N	<i>fline</i>								
R	7	•	APPLIED EARTH SCIENCES COMPANY		2 20,0 w 1000/10 III										
	ال	71 C:	algary AB Phone (403) 250 5185												



Summary of Hydrualic Conductivity Testing - BGC04-01

			K (m/s)	
Location	Date	Interval	Standard Hvorsley   Comments	omments
BGC04-01	9-Aug-04	0 - 4.3m	1.89E-05	1.89E-05 During Drilling, Falling head
BGC04-01	109-Aug-04	4.3 - 7.3 m	2.69E-06	2.69E-06 During Drilling, Falling head
BGC04-01	09-Aug-04	7.3 - 10.4 m	1.76E-06	1.76E-06 During Drilling, Falling head
BGC04-01	14-Aug-04	10.4 - 13.41	2.17E-06	2.17E-06 During Drilling, Falling head
BGC04-01	14-Aug-04	13.41 - 16.46	3.31E-06	3.31E-06 During Drilling, Falling head
BGC04-01	15-Aug-04	Well screen	2.18E-06 1	2.18E-06 Test performed immediately following installation, well was not developed. Falling Head
BGC04-01	08-Sep-04	Well screen	5.17E-06 V	5.17E-06 Well was developed on the 7th, Slug test performed and measurements made with "level logger"
BGC04-01	08-Sep-04	Well screen	5.38E-06	5.38E-06 Well was developed on the 7th, Slug test performed and measurements made with "level logger"

Well screen is from 13.89m to 16.76m

Note:

## BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY

Project: Project Number: Borehole Number: Date of Test: Client:

Total Elapsed Time (S)

Seconds

Minutes

Initial Level

Elaspsed Time

E	E	Ε.	E	E	2 minutes
1.80 m	0	0.0857 m	0.0857 m	4.27 m	2
Static Water Level:	Stick-up:	Piezometer Radius (r):	Drill Hole Radius (R):	Test Interval (L):	To (from graph below):
					- 1

	1.8		r² In(	7	
	¥		1 2	 	58 seconds
1.80 m	m 0	0.0857 m	0.0857 m	4.27 m	2 minutes
evel:		Jins (r):	IS (R):		below):

	Change in Water Level (h) Initial Change in Water Level (h <sub>o</sub> )
П	Head Ratio =
1.89E-05 m/s	r² in(L/R) 2L T <sub>0</sub>
ж П	¥ 1

			Ţ	I	T													I				Ţ		T				•		 <u> </u>	4000		
																										_	/	•			3500		
																					/	/	/	1						 -	3000		
																<i>y</i>	/	/	/												2500		
															/	_															2000	Time (sec)	
COLICE													/	<u> </u>																	1500	•	
SDIDDE OF				+							<i> </i>	1																		-	1000		
7 IIIII 7			 	1		+	Đ.			1																					200		
10 (SIOIII GIADII DEIOM).		1			•		Basic Time Lag	0.37	_		•					0.1	1													0.01	0		
																iti	я	be	əн					_						<u>.</u>			_
	Head Ratic	(%)		100%	%08	81%	61%	20%	45%	36%	31%	27%	23%	70%	15%	11%	2%	2%		***************************************													
	Change in Head Ratio	Level (m)	0.00	1.80	1.44	1.45	1.09	06:0	0.76	0.65	0.56	0.48	0.42		0.27	0.19	60:0	0.03															
	Depth to Water Level		1.80															1.77															
		-	882	Sage	è	leiking.	2883	dhe	712.45 8252	eie:		Ses.	7000	To a	1000	1888 A	32	No.	-	-	-	-		-	$\dashv$	-	$\vdash$	_	$\dashv$	$\dashv$	$\rightarrow$	+	$\dashv$

30 30 445 460 600 900 1200 1200 1200 1200 3000 3000 3600

8 2 4 3 5 12 12 P 3 P

띵쇲잉이ㅇ

### BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY (5) (6)

Client:
Project:
Project Number:
Borehole Number:
Date of Test:

	K = 2.69E-06 m/		$K = \frac{r^2 \ln(L/R)}{r^2 \ln(L/R)}$	7 - 2L T <sub>0</sub>	1600 seronds
2.00 m	0.4 m	0.0857 m	0.0857 m	3.05 m	O minufes
Static Water Level:	Stick-up:	Piezometer Radius (r):	Drill Hole Radius (R):	Test Interval (L):	T. (from graph below):

Ī	I		Ghange in Water Level (h)	Initial Change in Water Level (h <sub>0</sub> )		
	K = 2.69E-06  m/s		$K = \frac{r^2 \ln(L/R)}{r^2 \ln(L/R)}$	-	1600 seconds	
2.00 m	0.4 m	0.0857 m	0.0857 m	3.05 m	0 minutes	
c Water Level:	c-up: 0.4 m	ometer Radius (r):	Hole Radius (R): 0.0857 m	Interval (L):	rom graph below):	

																					•	_		_			3500			
																											2500 3000			
										_	_	7												-	-		2000	Time (sec)	(326)	
1600 seconds						1	/	/																			1500			
0 minutes				1		/															-			 			1000			
T <sub>0</sub> (from graph below):			*	1			Basic Time Lag																				0 500			
T <sub>0</sub> (from gr		-						0.37	,				(	%	) c	ובוכ	pe	əŀ	ı							0.01			<del></del>	
	Change in Head Ratio	(%)	1	100%											i	l														
	Change in	Water Level (m)	0:00	1.05	16'0	0:30	0.89	0.87	0.84	0.73	0.62	6.53	0.35	0.14	T0:0	0.03														
	Denth to Water Level	(m)	1.05	0.00	0.14	0.15	0.16	0.18	0.22	0.32	0.43	0.52	0.70	0.91	1.04	1.02														
	Total	Elapsed Time (S)	0	.0	09	- 06	120	180	008	009	. 006	1200	1800	2550	3000	3600														
	1 Time	Seconds	evel	0	09	0	0	0	0	0	0	0	0	30	0	0														
	Elaspsed Time	Minutes	Initial Level	0	0	1.5	2	3	ß	10	15	70	30	42	20	09														

4000

# Bac Engineering Inc.

	A AN APPLIED EARTH SCIENCES COMP
Client:	Deloitte & Touche Inc Fa
Project:	Plug Dam Investigation
Project Number:	
Borehole Number:	PGC0
Date of Test:	14-Aug-04

Elaspsed Time
Minutes Seconds

Deloitte & Touche Inc Faro Mine	Plug Dam Investigation	0257-027-01	BGC04-01, 10.4 to 13.41m	14-Aug-04	

			Change in Water Level (h)	Initial Change in Water Level (h <sub>0</sub> )	
	K = 2.17E-06 m/s		K = r <sup>2</sup> ln(L/R) Hes	2L T <sub>0</sub>	1980 seconds
3.00 m	0.5 m	0.0857 m	0.0857 m	3.05 m	low): 0 minutes
Static Water Level:	Stick-up:	Piezometer Radius (r):	Drill Hole Radius (R):	Test Interval (L):	To (from graph below):
o Mine			1m		

	_																<b></b>	<b>,</b>		<b>,,</b>					,	 			4000		
		-	f								F																		4		
	H																				1		ļ								
	$\parallel$	+	+	+	-			-			+	/	7_			+							+	 	<u>                                      </u>	 		+	3200		
	H	7		+	1					•	1					+	H	-		L	7	_	Ŧ					-			
	H	+	‡	+	+			7		_/	1					-	F				1		+			 _		1	0		
	Ħ	1		+	1			1		1	‡					+							†	 				1	3000		
	H	1	t		1				7	'	ļ					1	L				1		1			_		1			
	Н	1	$\frac{1}{1}$	1	1				$\overline{}$							ľ	-				1			 				1	2500		
	H	+	_	-	+			1			-					+	<u> </u>  -	L		<u> </u>	+		$\frac{1}{1}$				-		25		
	H	1	-	-	1		1	4			-					1	-	_		-	1		1	 						77	
	Ħ	1	1		1		/				‡					1	1						ļ		L	 		<del>-</del>	2000	Time (sec)	
		1	1	1	1	_					1												1	_					14	Ë	
		-	ł			+					+					$\frac{1}{2}$	+			-	+		+								
	Н	+	+	+	+	$\vdash$	L				+				-	+	-	-		$\vdash$	+		+	 				+	1500		
	H			1	1						+		• •••			#	+	F		F	7		+								
		1	1	#	1						1						-				#								_		
		1	İ		+											$^{\dagger}$					1							1	1000		
			+	1		_											-			-	$\dashv$										
	H	+	1	4	_		_										H			-	-		+		L	 			0		
		1	1	+	1	<u> </u>	1				+						F	F					1		L	 		1	200		
	H	1	†	ļ	۱	Basic Time Lag					1					#	‡	L		+	4		1		F						
						Basic										I	ŀ			_	+							1	0		
	П						0.37								ċ													0.01			
-					_							(	%	) c		E N	pe	ЭH	[ 												_
Depth to Water Level Water Head Ratio	(%)		100%	%/6	95%	94%	93%	%06	%88	84%	78%	%99	21%	21%	41%	35%	23%	15%													
nge in	Level (m)	.00	.00		.85	:81	:78	.71	2.64	.51	.34	- 26:	.71	.52	.22	96:	. 69:	.44												T	T
<u>ء</u> ج	Ę :	0	33	2	2	2	2		2	2	<b>2</b>	F	1000000			0	0	0	_					_	Щ				1	1	$\downarrow$
er Leve																															
to Wat	Œ	3.00	0.00	0.10	0.15	0.19	0.22	0.29	0.36	0.49	0.66	1.03	1.29	1.48	1.78	2.04	2.31	2.56													
Depth																															
Total	ne (S)	0	0	15	30	45	- 09	- 06	120	180	300		- 006	200	800	400	. 000	∵ 009≀													Ţ
- 6	ĭ⊨															鱶															

# GC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY

	BGC ENGINEERING II AN APPLIED EARTH SCIENCES COM Deloitte & Touche Inc F Plug Dam Inwestiga
Project Number:	0257-027-01
Borehole Number:	BGC04-01, 13.4 - 16
Date of Test:	14-Aug-04

Minutes

П	Head Ratio = Change in Water Level (h) Initial Change in Water Level (h)																												- - - -
3.31E-06 m/s	r² In(L/R)	?																									<u> </u>	/	_
X =	<b>∀</b>	1300 seconds																							_				_
8.90 m 0.5 m	0.0857 m																					/	/	/					_
Static Water Level: Stick-up:	Drill Hole Radius (R):	T <sub>o</sub> (from graph below):	•	1	•		•	1.	Basic Time Lag	0.37			•	-	<b>(</b>	%	) 0	tion in		þe	ÐH.								_
0, 0, 1		•	Change in Hoad Datio	(%)			%86	%26	%96			%06																	
Mine			Change in	Water Level (m)	0.00	8:90	8.75	8.64	8.53	8.44	8.21	8.02	99'/	7.00	2:27	4.45	3.51	2.17	1.43	0.92	0.58	0:07							
Deloitte & Touche Inc Faro Mine Plug Dam Investigation	BGC04-01, 13.4 - 16.5m	10 800 14	love I vote/W of Africa	(m)	8.90	0.00	0.15	0.26	0.37				1.24			4.45	5.39		7.47	7.98	8.32	8.83							
Deloit			Total	Elapsed Time (S)	0	0	1.5	30	45	- 09	06	120	180	300	009	006	1200	1800	2400	3000	3600	62640							
i	Imper:		ed Time	Seconds	i Level	0	15	30	45	09	0	0	0	0	0	0	0	0	0	0	0	0							

70000

00009

20000

40000

30000

20000

10000

0.01

Time (sec)

## BGC ENGINEERING INC.

Client: Deloite & T
Project: Project Number: BGC04-01, W
Date of Test:

Deloitte & Touche Inc Faro Mine Plug Dam Irvestigation	0257-027-01	BGC04-01, Well Screen 13.9 to 16.8m	14-010-04
---	-------------	-------------------------------------	-----------

Depth to Water Level

Total Elapsed Time (S)

Seconds

Minutes Sec Initial Level

Elaspsed Time

818000

					75 55
8.85 m	0.5 m	0.025 m	0.0857 m	2.87 m	2 minutes
Static Water Level:	Stick-up:	Piezometer Radius (r):	Drill Hole Radius (R):	Test Interval (L):	T. (from graph below).

			Change in Water Level (h)	Initial Change in Water Level (h <sub>0</sub> )		
			Hood Datio	I ICAN NAUO I		
	2.18E-06 m/s		r <sup>2</sup> In(L/R)	2L T <sub>0</sub>		
	¥ ⊨		7	1	55 seconds	
8.85 m	0.5 m	0.025 m	0.0857 m	2.87 m	2 minutes	

	П	Τ	Γ		Ι										Ţ					T	П	T		T			Ι			12000		
																													+	10000		
								_	_																	,			•			
					-																			1						8000		
																													<b>+</b>			
																											/	<u> </u>		0009		le (sec)
																								1	1	<i>/</i>			-		j	
					+							-	-										+	/			-			4000	1	
					-								-		1							1	1				ļ					
												-								/	/									2002		
												ļ			<u> </u>	_	/	_	*											,	•	
			be .	0.37			*					*														•		••••			)	
Ĥ		ļ	pasic lime Lag	0.37					Ċ	T.O	(	.º/	<sub>0</sub> )	oiđ	55	ıq t	29	4	5	0.01										0.001		
Head Ratio (%)		100%	84%	77%	71%	%09	20%	35%	18%	%9	3%	2%	1%	1%	80	%0	%0	%0	%0	%0	2											

(m) 8.885 0.000 0.000 1.142 2.20

45 60 90 120 120 120 180 900 2700 2700 5100 600 600 600 7200 9000 9000 9000


### BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY

Client: Project Number: Borehole Number: Date of Test:

Deloitte & Touche Inc. - Faro Mine Plug Dam Investigation 0257-027-01 BGCQ4-01, Well Screen 13.9 to 16.8 m

Head Ratio (%	100%	%66	%86	%66	%96	82%	91%	%06	%68	86%	91%	91%	%06	%68	86%	86%	%98	85%	84%	80%	79%	82%	%62	78%	%6/	77%	81%	77%	75%	75%	74%	71%	73%
Change in Water Level (m)	0.81	0.80	080	0.80	0.78	0.67	0.74	0.73	0.72	0.72	0.74	0.74	0.73	0.72	0.72	0.70	0.70	0.69	0.69	0.65	0.64	0.66	0.64	0.64	0.64	0.63	0.65	0.63	0.61	0.61	09:0	0.58	09:0
Depth to Water Level Depth to Water Level Change in Water Level (cm) (m)	4.77	4.76	4.76	4.76	4.74	4.63	4.70	4.69	4.68	4.68	4.70	4.70	4.69	4.68	4.68	4.66	4.66	4.65	4.65	4.61	4.60	4.62	4.60	4.60	4.60	4.59	4.61	4.59	4.57	4.57	4.56	4.54	4.56
Depth to Water Level	477.10	476.30	475.50	476.00	473.60	462.70	469.60	468,80	468.00	468.30	469.60	469.90	469.30	468.30	468.30	465.90	465.60	465.30	464.50	460.80	460.30	462.10	460.00	459.50	460.00	458.70	461.30	458.70	456.80	456.5	456	453.9	455.5
Total Elapsed Time (S)	2	2	3	3	4	4	2	2	9	9	7	7	8	8	6	6	10	10	11	11	12	12	13	13	14	14	15	15	16	16	17	17	18
Total Elapsed Time	0:00:05	0:00:02	£0:00:0	£0:00:0	6:00:0	0:00:04	50:00:0	50:00:0	90:00:0	90:00:0	20:00:0	0:00:0	80:00:0	80:00:0	60:00:0	60:00:0	0:00:10	0::00:0	0:00:11	0:00:11	0:00:12	0:00:12	0:00:13	0:00:13	0:00:14	0:00:14	0:00:15	0:00:15	0:00:16	91:00:0	0:00:17	0:00:17	0:00:18

	lead Ratio = Change in Water Level (h) Initial Change in Water Level (h <sub>0</sub> )
s/m 94	, †   ,
K = 5.17E-06 m/s	K = r <sup>2</sup> ln(L/R) 2L T <sub>0</sub> nds
X	K = 71 seconds
3.96 m 0 m	Jus (7): 0.035 m ss (R): 0.09857 m J: 2.87 m below): 0 minutes
Static Water Level: Stick-up:	Plezometer Radius (7): 0.025 m  Drill Hole Radius (R): 0.09857 m  Test Interval (L): 2.87 m  T <sub>0</sub> (from graph below): 0 minu



### BGC ENGINEERING INC. AN APPLIED EARTH SCIENCES COMPANY

Client:
Project:
Project Number:
Borehole Number:
Date of Test:

3.12	311,70 3,12 312,30 3,12 314,40 3,14	311.70 3.12 312.30 3.12 31440 3.14	311.70 3.1.2 312.30 3.1.2 314.40 3.14 315.50 3.16	311.70 3.12 312.30 3.12 314.40 3.14 315.00 3.15	311.70 3.12 312.30 3.12 314.40 3.14 315.50 3.16 316.50 3.15	311.70 3.12 312.30 3.12 314.40 3.14 314.50 3.16 316.50 3.15	311.70 3.12 312.30 3.12 314.40 3.14 315.50 3.16 316.50 3.17 317.9 3.18
312.70	312.30	312.30	312.70 312.30 314.40 315.50	311.70 312.30 314.40 315.50 314.70	312.30 312.30 315.50 315.50 316.50	311.70 314.40 315.50 314.70 316.50	31.70 31.23 31.440 315.50 315.50 316.50 317.9
312.30 3.12	312.30 3.12	312.30 3.12 314.40 3.14	312.30 3.12 314.40 3.14 315.50 3.16	312.30 3.12 314.40 3.14 315.50 3.16 314.70 3.15	312.30 3.12 314.40 3.14 315.50 3.16 315.70 3.15 316.50 3.17	312.30 3.12 314.40 3.14 315.00 3.16 316.50 3.17	312.30 3.12 314.40 3.14 315.50 3.16 314.70 3.15 316.50 3.17 317.9 3.17
20110	31440 3.14	314.40 3.14	314.40 3.14 3.15 3.15	314.40 3.14 315.50 3.16 314.70 3.15	314.40 3.14 315.50 3.16 314.70 3.15 316.50 3.17	314.40 3.14 315.50 3.16 314.50 3.15 316.50 3.17	31440 3.14 315.50 3.16 314.70 3.15 316.50 3.17 317.9 3.18
315.50 3.16 314.70 3.15 316.50 3.17 317.9 3.18	314.70 3.15 316.50 3.17 317.9 3.18 315.7 3.18	316.50 3.15 316.50 3.17 317.9 3.18 315.7 3.16	316.50 3.17 317.9 3.18 315.7 3.16	317.9 3.18 315.7 3.16	315.7 3.16	315./ 3.16	

Static Water Level: 3.96 m	er Radius (r): 0.02	0	22	To (from graph below): 0 minutes			1						0.37					(1	%	) 0	tion in the second		pı	291	1					Carto	70000					0.01	0 100		
					Head Ratio (%)		100%	%56	94%	100%	100%	%66	%86	95%	94%	93%	95%	%06	88%	88%	89%	88%	85%	87%	82%	81%	82%	80%	79%	80%	80%	78%	77%	77%	%92	74%	%92	75%	72%
					Change in Water Level	Œ	1.15	1.09	1.08	1.05	1.05	1.04	1.03	1.00	0.99	0.97	0.97	0.94	0.93	0.92	0.94	0.93	0.89	0.92	0.86	0.85	0.86	0.85	0.83	0.84	0.84	0.82	0.81	0.81	080	0.78	080	0.79	92.0
Faro Mine		13.9 to 16.8 m			Depth to Water Level Change in Water Level	Œ	2.81	2.87	2.88	2.91	2.91	2.92	2.93	2.96	2.97	2.99	2.99	3.02	3.04	3.04	3.02	3.03	3.07	3.05	3.10	3.11	3.10	3.12	3.13	3.12	3.12	3.14	3.16	3.15	3.17	3.18	3.16	3.17	3.20
Deloitte & Touche Inc Faro Mine	Plug Dam Investigation 0257-027-01	BGC04-01, Well Screen 13.9 to 16.8 m	08-Sep-04		Depth to Water Level	(m)	280.80	286.90	288.00	290.90	290.70	292.00	293.30	296.00	297.30	298.70	299.20	301.60	303.50	304.00	302.40	303.20	306.90	304.50	309.90	310.90	309.90	311.50	313.30	311.70	312.30	314.40	315.50	314.70	316.50	317.9	315.7	317.3	320
ωļ	•	- ii		1		Time (S)	0	0	ī	1	2	2	2	3	4	4	5	2	9	9	7	7	8		6	6	10	91	11	11	12	17	£	13	41	14	53	7,7	16

9


20

9

Time (sec)

300

200



### **Constant Head (Lugeon) Test Analysis**

Diamond Drillhole: BGC04-02

Water Test Interval: 8.45m to 10.67m

Project Number: 0257-027-01

Static W.L. from stick-up: 4.00 m
Stick-up A.G.L. along dip: 0.00 m

Date:

Sept 1/04

Static W.L. below G.L.:

4.00 m (vertical)

Height of gauge A.G.L.:

1.14 m (vertical)

Bottom of Interval: 10.67 m

Top of Interval: 8.45 m

Length of Interval L: 2.22 m


Middle of Interval to D.F.: 9.56 m (vertical)

Open Hole Radius R: 0.0375 m

Time (min)	Volume (Litres)	Q (Lpm)	Gauge Pressure (psi)	Q (m³/sec)	Total Head (mH₂O)	K (m/sec)
·						
1	83	83.00	-1.6	1.38E-03	4.0	1.0E-04

Q ave: 1.38E-03 (m<sup>3</sup>/sec)

Comments: Static WL estimated at 4.0 m below ground. Could not develop gauge pressure above those measured in calibration test, therefore "take" exceeded capacity of pump (83 Lpm). Water level assummed to be at ground surface.



### **Graphical Analysis**

Q ave: 1.38E-03 (m<sup>3</sup>/sec)

Head H from Plot:

4.00 (m)

 $K = \frac{Qln(L/R)}{2(pi)LH}$ 

K = 1.0E-04 m/s

### **Constant Head (Lugeon) Test Analysis**

Diamond Drillhole: BGC04-02

Water Test Interval: 9.71m to 11.93m

Project Number: 0257-027-01

Client: Deloitte & Touche Inc. Project Site: Plug Dam General Location: Road North Coordinate: 6914164 **East Coordinate:** 584927 Azimuth: deg Dip: 90 deg Sept 1/04 Date:

 Date:
 Sept 1/04

 Static W.L. from stick-up:
 4.00 m

 Stick-up A.G.L. along dip:
 0.00 m

Static W.L. below G.L.:

4.00 m (vertical)

Height of gauge A.G.L.:

1.14 m (vertical)

Bottom of Interval: 11.93 m

Top of Interval: 9.71 m

Length of Interval L: 2.22 m

Middle of Interval to D.F.: 10.82 m (vertical)


Open Hole Radius R: 0.0375 m

Time (min)	Volume (Litres)	Q (Lpm)	Gauge Pressure (psi)	Q (m³/sec)	Total Head (mH₂O)	K (m/sec)
1	83	83.00	-1.6	1.38E-03	4.0	1.0E-04

Q ave: 1.38E-03 (m<sup>3</sup>/sec)

Comments: Static WL estimated at 4.0 m below ground. Could not develop gauge pressure above those measured in calibration test, therefore "take" exceeded capacity of pump (83)

Lpm). Water level assummed to be at ground surface.



### **Graphical Analysis**

Q ave: 1.38E-03 (m<sup>3</sup>/sec)

Head H from Plot: 3.99 (m)

 $K = \frac{Qln(L/R)}{2(pi)LH}$ 

K = 1.0E-04 m/s

### **Constant Head (Lugeon) Test Analysis**

Diamond Drillhole: BGC04-02

Water Test Interval: 13.06m to 15.28m

Project Number: 0257-027-01

Client: Deloitte & Touche Inc. Project Site: Plug Dam General Location: Road North Coordinate: 6914164 584927 East Coordinate: Azimuth: deg Dip: 90 deg Sept 1/04 Date:

Static W.L. from stick-up: 4.00 m

Stick-up A.G.L. along dip: 0.00 m

Static W.L. below G.L.:

4.00 m (vertical)

Height of gauge A.G.L.:

1.14 m (vertical)

 Bottom of Interval:
 15.28 m

 Top of Interval:
 13.06 m

 Length of Interval L:
 2.22 m


Middle of Interval to D.F.: 14.17 m (vertical)

Open Hole Radius R: 0.0375 m

Time (min)	Volume (Litres)	Q (Lpm)	Gauge Pressure (psi)	Q (m³/sec)	Total Head (mH₂O)	K (m/sec)
1	20	20.00	31.0	3.33E-04	26.9	3.6E-06

Q ave: 3.33E-04 (m<sup>3</sup>/sec)

Comments: Static WL estimated at 4.0 m below ground. Flow rate of 0.5 Litres for pressure of 31 psi. Flow meter later found to be malfunctioning for low flow rates. Flow rates of upto 20 Lpm registered as 0.



### **Graphical Analysis**

Q ave: 3.33E-04 (m<sup>3</sup>/sec)

Head H from Plot: 26.94 (m)

 $K = \frac{Qln(L/R)}{2(pi)LH}$ 

K = 3.6E-06 m/s

Diamond Drillhole: BGC04-02

Water Test Interval: 15.81m to 18.03m

Project Number:

**General Location:** 

North Coordinate:

0257-027-01

Client:

Plug Dam Road

**East Coordinate:** 

Project Site:

Azimuth: Dip:

Date: Static W.L. from stick-up:

Stick-up A.G.L. along dip:

Static W.L. below G.L.:

Height of gauge A.G.L.:

Bottom of Interval:

Top of Interval: Length of Interval L:

Middle of Interval to D.F.:

Open Hole Radius R:

Deloitte & Touche Inc.

6914164

584927

deg 90 deg Sept 1/04

4.00 m

0.00 m

4.00 m (vertical)

1.14 m (vertical) 18.03 m

15.81 m 2.22 m


16.92 m (vertical)

0.0375 m

Time (min)	Volume (Litres)	Q (Lpm)	Gauge Pressure (psi)	Q (m³/sec)	Total Head (mH₂O)	K (m/sec)
1	20	20.00	38.0	3.33E-04	31.9	3.1E-06

Q ave: 3.33E-04 (m<sup>3</sup>/sec)

Comments: Static WL estimated at 4.0 m below ground. Flow rate of 0 Litres for pressure of 38 psi. Flow meter later found to be malfunctioning for low flow rates. Flow rates of upto 20 Lpm registered as 0.



#### **Graphical Analysis**

Q ave:

3.33E-04 (m<sup>3</sup>/sec)

Head H from Plot:

31.86 (m)

Qln(L/R) 2(pi)LH

K= 3.1E-06 m/s

Diamond Drillhole: BGC04-03

Water Test Interval: 3.01m to 5.23m

Project Number:

0257-027-01

Client:

Deloitte & Touche Inc.

Project Site: General Location: Plug Dam Right Abutment 6914159 584896

East Coordinate: Azimuth:

North Coordinate:

Dip: Date:

Static W.L. from stick-up:

Stick-up A.G.L. along dip:

Static W.L. below G.L.:

Height of gauge A.G.L.:

Bottom of Interval:

Top of Interval:

Length of Interval L:

Middle of Interval to D.F.:

Open Hole Radius R:

deg 90 deg Sept 5/04

4.00 m

0.00 m

4.00 m (vertical)

1.14 m (vertical) 5.23 m

3.01 m 2.22 m


4.12 m (vertical)

0.0375 m

Time (min)	Volume (Litres)	Q (Lpm)	Gauge Pressure (psi)	Q (m³/sec)	Total Head (mH₂O)	K (m/sec)
5	86.15	17.23	16.0	2.87E-04	16.4	5.1E-06
5	125.02	25.00	26.0	4.17E-04	23.4	5.2E-06
5	82.97	16.59	16.0	2.77E-04	16.4	4.9E-06
5	59.55	11.91	9.0	1.99E-04	11.5	5.1E-06

Q ave: 2.95E-04 (m<sup>3</sup>/sec)

Comments: Static WL estimated at 4.0 m below ground. Flow rate measured in Igal and converted to Litres.



## **Graphical Analysis**

Q ave: 2.95E-04 (m<sup>3</sup>/sec)

Head H from Plot:

16.86 (m)

Qln(L/R) 2(pi)LH

5.1E-06 m/s

Diamond Drillhole: BGC04-03

Water Test Interval: 5.75m to 7.97m

Project Number:

0257-027-01

Client:
Project Site:
General Location:

North Coordinate:

East Coordinate: Azimuth:

Dip:

Deloitte & Touche Inc.
Plug Dam
Right Abutment
6914159
584896
deg
90 deg

Sept 4/04

			Gauge		Total	
Time	Volume	Q	Pressure	Q	Head	ĸ
(min)	(Litres)	(Lpm)	(psi)	(m³/sec)	(mH₂O)	(m/sec)
5	.34	0.07	5.5	1.13E-06	9.0	3.7E-08
5	1.18	0.24	12.0	3.93E-06	13.6	8.5E-08
5	2.66	0.53	16.5	8.87E-06	16.7	1.5E-07
5	.86	0.17	10.0	2.87E-06	12.2	6.9E-08
5	0.04	0.01	5.5	1.33F-07	9.0	4.3F-09

Q ave: 3.39E-06 (m<sup>3</sup>/sec)

Date:

Static W.L. from stick-up: 4.00 m Stick-up A.G.L. along dip: 0.00 m

Static W.L. below G.L.: Height of gauge A.G.L.: 4.00 m (vertical)

Bottom of Interval:

Top of Interval:

7.97 m 5.75 m 2.22 m


Length of Interval L:
Middle of Interval to D.F.:

2.22 m 6.86 m (vertical)

Open Hole Radius R:

0.0375 m

Comments: Static WL estimated at 4.0 m below ground. Flow rate measured in Igal and converted to L. Volume of 0.04L for a 5 min test was input when "take" was 0, which is estimated lowest flow possibly read with this flow meter.



#### **Graphical Analysis**

Q ave: 3.39E-06 (m<sup>3</sup>/sec)

Head H from Plot:

8.11 (m)

 $K = \frac{Qln(L/R)}{2(pi)LH}$ 

K = 1.2E-07 m/s

Diamond Drillhole: BGC04-03

Water Test Interval: 8.49m to 10.71m

**Project Number:** 

0257-027-01

Client: Deloitte & Touche Inc. Project Site: Plug Dam **General Location:** Right Abutment North Coordinate: 6914159 584896 East Coordinate: Azimuth: Dip: Date:

	90 de
	Sept 4/04
/.L. from stick-up:	4.00 m

Static W

Stick-up A.G.L. along dip:

Static W.L. below G.L.:

Height of gauge A.G.L.:

Bottom of Interval: Top of Interval:

Length of Interval L: Middle of Interval to D.F.:

Open Hole Radius R:

	deg
90	deg
Sept 4/0	4
4.00	m
0.00	m
4.00	m (vertical)
	•

1.14 m (vertical)

10.71 m 8.49 m 2.22 m


9.60 m (vertical)

0.0375 m

Time (min)	Volume (Litres)	Q (Lpm)	Gauge Pressure (psi)	Q (m³/sec)	Total Head (mH₂O)	K (m/sec)
5	0.04	0.01	6.0	1.33E-07	9.4	4.2E-09
5	0.04	0.01	13.0	1.33E-07	14.3	2.7E-09
5	0.04	0.01	20.0	1.33E-07	19.2	2.0E-09

Q ave: 1.33E-07 (m<sup>3</sup>/sec)

Comments: Static WL estimated at 4.0 m below ground. Flow rate measured in Igal and converted to L. Volume of 0.04L for a 5 min test was input when "take" was 0, which is estimated lowest flow possibly read with this flow meter.



#### **Graphical Analysis**

Q ave:

1.33E-07 (m<sup>3</sup>/sec)

Head H from Plot:

14.28 (m)

Qln(L/R) 2(pi)LH

2.7E-09 m/s

Diamond Drillhole: BGC04-03

Water Test Interval: 11.24m to 13.46m

Project Number:

0257-027-01

Deloitte & Touche Inc. Client: Project Site: Plug Dam **General Location:** Right Abutment North Coordinate: 6914159 **East Coordinate:** 584896 Azimuth: deg Dip: 90 deg

Sept 4/04 Date: 4.00 m

Static W.L. from stick-up:

0.00 m Stick-up A.G.L. along dip:

Static W.L. below G.L.:

4.00 m (vertical) Height of gauge A.G.L.: 1.14 m (vertical)

Bottom of Interval: Top of Interval:

Length of Interval L:

13.46 m 11.24 m 2.22 m

12.35 m (vertical)


Middle of Interval to D.F.:

Open Hole Radius R: 0.0375 m

			Gauge		Total	
Time	Volume	Q	Pressure	Q	Head	K
(min)	(Litres)	(Lpm)	(psi)	(m³/sec)	(mH <sub>2</sub> O)	(m/sec)
5	0.04	0.01	10.0	1.33E-07	12.2	3.2E-09
5	0.04	0.01	16.0	1.33E-07	16.4	2.4E-09
5	0.04	0.01	25.0	1.33E-07	22.7	1.7E-09
5	0.04	0.01	13.0	1.33E-07	14.3	2.7E-09
5	0.04	0.01	7.0	1.33E-07	10.1	3.9E-09

Q ave: 1.33E-07 (m3/sec)

Comments: Static WL estimated at 4.0 m below ground. Flow rate measured in Igal and converted to L. Volume of 0.04L for a 5 min test was input when "take" was 0, which is estimated lowest flow possibly read with this flow meter.



#### **Graphical Analysis**

1.33E-07 (m<sup>3</sup>/sec) Q ave:

Head H from Plot:

15.11 (m)

Qln(L/R) 2(pi)LH

> 2.6E-09 m/s K≔

Diamond Drillhole: BGC04-03

Water Test Interval: 16.72m to 18.94m

Project Number: 0257-027-01

Deloitte & Touche Inc. Client: Plug Dam Project Site: **General Location:** Right Abutment 6914159 North Coordinate: 584896 **East Coordinate:** Azimuth: deg Dip: 90 deg Sept 4/04 Date:

Time (min)	Volume (Litres)	Q (Lpm)	Pressure (psi)	Q (m³/sec)	Head (mH₂O)	K (m/sec)
5	0.04	0.01	11.0	1.33E-07	12.9	3.0E-09
5	0.04	0.01	23.0	1.33E-07	21.3	1.8E-09
5	0.04	0.01	36.0	1.33E-07	30.5	1.3E-09
5	0.04	0.01	23.0	1.33E-07	21.3	1.8E-09
5	0.04	0.01	11.0	1.33E-07	12.9	3.0E-09

Gauge

Q ave: 1.33E-07 (m<sup>3</sup>/sec)

Total

Static W.L. from stick-up: 4.00 m Stick-up A.G.L. along dip: 0.00 m

Static W.L. below G.L.:

4.00 m (vertical)

Height of gauge A.G.L.:

1.14 m (vertical)

Bottom of Interval: 18.94 m


Top of Interval: 16.72 m

Length of Interval L: 2.22 m

Middle of Interval to D.F.: 17.83 m (vertical)

Open Hole Radius R: 0.0375 m

Comments: Static WL estimated at 4.0 m below ground. Flow rate measured in Igal and converted to L. Volume of 0.04L for a 5 min test was input when "take" was 0, which is estimated lowest flow possibly read with this flow meter.



#### **Graphical Analysis**

Q ave: 1.33E-07 (m<sup>3</sup>/sec)

Head H from Plot: 19.76 (m)

 $K = \frac{Qln(L/R)}{2(pi)LH}$ 

K = 2.0E-09 m/s

Diamond Drillhole: BGC04-03

Water Test Interval: 19.46m to 21.68m

Project Number: 0257-027-01

Deloitte & Touche Inc. Client: Plug Dam Project Site: General Location: Right Abutment 6914159 North Coordinate: 584896 East Coordinate: Azimuth: deg 90 deg Dip: Sept 4/04 Date:

Static W.L. from stick-up: 4.00 m

Stick-up A.G.L. along dip: 0.00 m

Static W.L. below G.L.:

4.00 m (vertical)

Height of gauge A.G.L.:

1.14 m (vertical)

 Bottom of Interval:
 21.68 m

 Top of Interval:
 19.46 m

 Length of Interval L:
 2.22 m


Middle of Interval to D.F.: 20.57 m (vertical)

Open Hole Radius R: 0.0375 m

Time (min)	Volume (Litres)	Q (Lpm)	Gauge Pressure (psi)	Q (m³/sec)	Total Head (mH₂O)	K (m/sec)
5	1.05	0.21	14.0	3.50E-06	15.0	6.8E-08
5	0.55	0.11	29.0	1.83E-06	25.5	2.1E-08
5	4.91	0.98	43.0	1.64E-05	35.4	1.4E-07
5	0.18	0.04	29.0	6.00E-07	25.5	6.9E-09
5	0.04	0.01	14.0	1.33E-07	15.0	2.6E-09

Q ave: 4.49E-06 (m<sup>3</sup>/sec)

Comments: Static WL estimated at 4.0 m below ground. Flow rate measured in Igal and converted to L. Volume of 0.04L for a 5 min test was input when "take" was 0, which is estimated lowest flow possibly read with this flow meter.



## **Graphical Analysis**

Q ave: 4.49E-06 (m<sup>3</sup>/sec)

Head H from Plot: 10.99 (m)

 $K = \frac{Qln(L/R)}{2(pi)LH}$ 

K = 1.2E-07 m/s

Diamond Drillhole: BGC04-03

Water Test Interval: 21.90m to 24.12m

**Project Number:** 

0257-027-01

•			
Client:	Deloitte & Touche Inc.		
Project Site:	Plug Dam		
General Location:	Right Abutment		
North Coordinate:	6914159		
East Coordinate:	584896		
Azimuth:	deg		
Dip:	90 deg		
Date:	Sept 4/04		

Time (min)	Volume (Litres)	Q (Lpm)	Pressure (psi)	Q (m³/sec)	Head (mH₂O)	K (m/sec)
5	1.27	0.25	15.0	4.23E-06	15.7	7.9E-08
5	5.36	1.07	30.0	1.79E-05	26.2	2.0E-07
5	19.21	3.84	45.0	6.40E-05	36.8	5.1E-07
5	5.52	1.10	30.0	1.84E-05	26.2	2.1E-07
5	1.05	0.21	15.0	3.50E-06	15.7	6.5E-08

Gauge

Q ave: 2.16E-05 (m<sup>3</sup>/sec)

Total

Static W.L. from stick-up:

4.00 m

Stick-up A.G.L. along dip:

0.00 m

Static W.L. below G.L.:

4.00 m (vertical)

Height of gauge A.G.L.:

1.14 m (vertical)

Bottom of Interval:

24.12 m

Top of Interval: Length of Interval L: 21.90 m 2.22 m


Middle of Interval to D.F.:

23.01 m (vertical)

Open Hole Radius R:

0.0375 m

Comments: Static WL estimated at 4.0 m below ground. Flow rate measured in Igal and converted.



## **Graphical Analysis**

Q ave: 2.16E-05 (m<sup>3</sup>/sec)

Head H from Plot:

15.47 (m)

Qln(L/R) 2(pi)LH

4.1E-07 m/s

Diamond Drillhole: BGC04-04

Water Test Interval: 2.79m to 5.79m (Single Packer)

**Project Number:** 

0257-027-01

Client:

Project Site: General Location: Left Abutment 6914159 North Coordinate: East Coordinate:

Azimuth: Dip:

Date:

Static W.L. from stick-up:

Stick-up A.G.L. along dip:

Static W.L. below G.L.:

Height of gauge A.G.L.:

Bottom of Interval:

Top of interval:

Length of Interval L:

Middle of Interval to D.F.:

Open Hole Radius R:

Deloitte	&	Touche	Inc.

Time

(min)

5

Plug Dam 584896

> deg 90 deg Sept 8/04

5.75 m

0.00 m

5.75 m (vertical)

1.30 m (vertical)

5.79 m

2.79 m 3.00 m

4.29 m (vertical) 0.0375 m

Volume

(Litres)

15.68

Q

(Lpm)

3.14

Comments: Static WL measured at 5.75 m below ground. Flow rate measured in Igal and converted to L.

Pressure

(psi)

7.0

Q

(m³/sec)

5.23E-05

Q ave: 5.23E-05 (m3/sec)

Pressure


(mH<sub>2</sub>O)

12.0

Κ

(m/sec)

1.0E-06



### **Graphical Analysis**

Q ave: 5.23E-05 (m<sup>3</sup>/sec)

Head H from Plot:

11.97 (m)

Qln(L/R) 2(pi)LH

1.0E-06 m/s

Diamond Drillhole: BGC04-04

Water Test Interval: 3.61m to 7.36m

Project Number:

0257-027-01

Client: Project Site: **General Location:** 

North Coordinate: East Coordinate:

Azimuth: Dip: Date:

Static W.L. from stick-up:

Stick-up A.G.L. along dip:

Static W.L. below G.L.:

Height of gauge A.G.L.:

Bottom of Interval: Top of Interval:

Length of Interval L: Middle of Interval to D.F.:

Open Hole Radius R:

_	_	•	_	_	_		_			_
·-	1	- :4			0	_		 L.	_	

Deloitte & Touche Inc
Plug Dam
Left Abutment
6914159
584896

deg 90 deg Sept 9/04

> 5.75 m 0.00 m

5.75 m (vertical) 1.30 m (vertical)

7.36 m 3.61 m


3.75 m 5.49 m (vertical)

0.0375 m

Time (min)	Volume (Litres)	Q (Lpm)	Gauge Pressure (psi)	Q (m³/sec)	Total Head (mH₂O)	K (m/sec)
5	9.27	1.85	10.0	3.09E-05	14.1	4.3E-07

Q ave: 3.09E-05 (m<sup>3</sup>/sec)

Comments: Static WL measured at 5.75 m below ground. Flow rate measured in Igal and converted to L.



#### **Graphical Analysis**

3.09E-05 (m<sup>3</sup>/sec) Q ave:

14.08 (m) Head H from Plot:

Qln(L/R) 2(pi)LH

4.3E-07 m/s K =

Diamond Drillhole: BGC04-04

Water Test Interval: 7.27m to 11.02m

**Project Number:** 0257-027-01

Deloitte & Touche Inc. Client: Project Site: Plug Dam General Location: Left Abutment North Coordinate: 6914159 East Coordinate: 584896 Azimuth: deg Dip: 90 deg Sept 9/04 Date:

Time (min)	Volume (Litres)	Q (Lpm)	Pressure (psi)	Q (m³/sec)	Head (mH₂O)	K (m/sec)
10	0.45	0.05	19.0	7.50E-07	20.4	7.2E-09

Gauge

Q ave: 7.50E-07 (m<sup>3</sup>/sec)

Total

Static W.L. from stick-up:

Stick-up A.G.L. along dip: 0.00 m

5.75 m

Static W.L. below G.L.: 5.75 m (vertical)
Height of gauge A.G.L.: 1.30 m (vertical)

Bottom of Interval: 11.02 m


Top of Interval: 7.27 m

Length of Interval L: 3.75 m

Middle of Interval to D.F.: 9.15 m (vertical)

Open Hole Radius R: 0.0375 m

Comments: Static WL measured at 5.75 m below ground. Flow rate measured in Igal and converted to L.



#### **Graphical Analysis**

Q ave: 7.50E-07 (m<sup>3</sup>/sec)

Head H from Plot: 20.41 (m)

 $K = \frac{Qln(L/R)}{2(pi)LH}$ 

K = 7.2E-09 m/s

Diamond Drillhole: BGC04-04

Water Test Interval: 10.92m to 14.67m

**Project Number:** 0257-027-01

 Client:
 Deloitte & Touche Inc.

 Project Site:
 Plug Dam

 General Location:
 Left Abutment

 North Coordinate:
 6914159

 East Coordinate:
 584896

 Azimuth:
 deg

 Dip:
 90 deg

 Date:
 Sept 9/04

Date: Sept 9/04
Static W.L. from stick-up: 5.75 m

Stick-up A.G.L. along dip: 0.00 m

Static W.L. below G.L.: 5.75 m (vertical)

Height of gauge A.G.L.: 1.30 m (vertical)

 Bottom of Interval:
 14.67 m

 Top of Interval:
 10.92 m

 Length of Interval L:
 3.75 m


Middle of Interval to D.F.: 12.80 m (vertical)

Open Hole Radius R: 0.0375 m

			Gauge		Total	
Time	Volume	Q	Pressure	Q	Head	к
(min)	(Litres)	(Lpm)	(psi)	(m³/sec)	(mH₂O)	(m/sec)
5	0.23	0.05	19.0	7.67E-07	20.4	7.3E-09
				-		

Q ave: 7.67E-07 (m3/sec)

Comments: Static WL measured at 5.75 m below ground. Flow rate measured in Igal and converted to L.



#### **Graphical Analysis**

Q ave: 7.67E-07 (m<sup>3</sup>/sec)

Head H from Plot: 20.41 (m)

 $K = \frac{Qln(L/R)}{2(pi)LH}$ 

K = 7.3E-09 m/s

Diamond Drillhole: BGC04-04

Water Test Interval: 14.58m to 18.33m

Project Number:

**General Location:** North Coordinate: East Coordinate:

0257-027-01

Client: Project Site:

Azimuth: Dip:

Date:

Static W.L. from stick-up:

Stick-up A.G.L. along dip: Static W.L. below G.L.:

Height of gauge A.G.L.:

Bottom of Interval:

Top of Interval:

Length of Interval L:

Middle of Interval to D.F.:

Open Hole Radius R:

Deloitte	&	Touche	Inc.	
Cionic	u	rouciic	1110.	

Delottle & Touche III	u
Plug Dam	
Left Abutment	
6914159	
584896	

deg 90 deg Sept 9/04

5.75 m

0.00 m

5.75 m (vertical) 1.30 m (vertical)

18.33 m 14.58 m


3.75 m

16.46 m (vertical) 0.0375 m

Time (min)	Volume (Litres)	Q (Lpm)	Gauge Pressure (psi)	Q (m³/sec)	Total Head (mH₂O)	K (m/sec)
11	1.36	0.12	22.0	2.06E-06	22.5	1.8E-08

Q ave: 2.06E-06 (m<sup>3</sup>/sec)

Comments: Static WL measured at 5.75 m below ground. Flow rate measured in Igal and converted to L.



#### **Graphical Analysis**

Q ave:

2.06E-06 (m<sup>3</sup>/sec)

Head H from Plot:

22.52 (m)

Qln(L/R) 2(pi)LH

1.8E-08 m/s K =

Diamond Drillhole: BGC04-04

Water Test Interval: 18.24m to 21.99m

Project Number:

0257-027-01

Client:

Project Site: **General Location:**  Left Abutment 6914159

North Coordinate: East Coordinate:

Azimuth:

Dip:

Date:

Static W.L. from stick-up:

Stick-up A.G.L. along dip:

Static W.L. below G.L.:

Height of guage A.G.L.:

Bottom of Interval:

Top of Interval:

Length of Interval L:

Middle of Interval to D.F.:

Open Hole Radius R:

Deloitte & Touche Inc.

Plug Dam

584896

deg

90 deg Sept 9/04

5.75 m

0.00 m

5.75 m (vertical)

1.30 m (vertical)

21.99 m

18.24 m


3.75 m 20.12 m (vertical)

0.0375 m

Total Gauge Time Volume Q Pressure Q Head Κ (m³/sec) (mH<sub>2</sub>O)(min) (Litres) (Lpm) (psi) (m/sec) 1.51E-05 26.0 1.1E-07 7 6.36 0.91 27.0

Q ave: 1.51E-05 (m<sup>3</sup>/sec)

Comments: Static WL measured at 5.75 m below ground. Flow rate measured in Igal and converted to L.



#### **Graphical Analysis**

Q ave:

1.51E-05 (m<sup>3</sup>/sec)

Head H from Plot:

26.03 (m)

Qln(L/R) 2(pi)LH

K= 1.1E-07 m/s

Diamond Drillhole: BGC04-04

Water Test Interval: 21.90m to 25.65m

Project Number:

0257-027-01

Client: Project Site: Plug Dam General Location: Left Abutment 6914159 North Coordinate: 584896 East Coordinate: Azimuth: dea Dip:

Date:

Static W.L. from stick-up: Stick-up A.G.L. along dip:

Static W.L. below G.L.:

Height of gauge A.G.L.:

Bottom of Interval: 25.65 m 21.90 m Top of Interval:

Length of Interval L: Middle of Interval to D.F.:

Open Hole Radius R:

Deloitte & Touche Inc.

	ucg
90	deg
Sept 9/0	4

5.75 m 0.00 m

5.75 m (vertical)


1.30 m (vertical)

3.75 m 23.78 m (vertical) 0.0375 m

Total Gauge Κ Volume Q Pressure Q Head Time (m³/sec) (mH<sub>2</sub>O) (m/sec) (min) (Litres) (Lpm) (psi) 1.21E-05 1.3E-07 5 3.64 0.73 15.0 17.6 2.00E-05 30.3 1.3E-07 5 6.00 33.0 1.20

Q ave: 1.61E-05 (m<sup>3</sup>/sec)

Comments: Static WL measured at 5.75 m below ground. Flow rate measured in Igal and converted to L.



#### **Graphical Analysis**

Q ave:

1.61E-05 (m<sup>3</sup>/sec)

Head H from Plot:

24.03 (m)

Qln(L/R) 2(pi)LH

K = 1.3E-07 m/s

Diamond Drillhole: BGC04-04

Water Test Interval: 25.56m to 29.30m

Project Number: 0257-027-01

Client: Deloitte & Touche Inc. Project Site: Plug Dam General Location: Left Abutment North Coordinate: 6914159 East Coordinate: 584896 Azimuth: deg Dip: 90 deg Sept 9/04 Date:

Static W.L. from stick-up: 5.75 m

Stick-up A.G.L. along dip:

Static W.L. below G.L.: 5.75 m (vertical) Height of gauge A.G.L.: 1.30 m (vertical)

0.00 m

Bottom of Interval: 29.30 m 25.56 m Top of interval: Length of Interval L: 3.74 m


27.43 m (vertical) Middle of Interval to D.F.:

Open Hole Radius R: 0.0375 m

Time (min)	Volume (Litres)	Q (Lpm)	Gauge Pressure (psi)	Q (m³/sec)	Total Head (mH₂O)	K (m/sec)
5	0.04	0.01	16.0	1.33E-07	18.3	1.4E-09
5	0.04	0.01	26.0	1.33E-07	25.3	1.0E-09
5	0.04	0.01	47.0	1.33E-07	40.1	6.5E-10

Q ave: 1.33E-07 (m<sup>3</sup>/sec)

Comments: Static WL measured at 5.75 m below ground. Flow rate measured in Igal and converted to L.



#### **Graphical Analysis**

1.33E-07 (m<sup>3</sup>/sec) Q ave:

Head H from Plot: 27.91 (m)

Qin(L/R) 2(pi)LH

9.4E-10 m/s

Diamond Drillhole: BGC04-04

Water Test Interval: 29.78m to 33.53m

**Project Number:** 

**General Location:** 

North Coordinate:

East Coordinate:

0257-027-01

Client:

Project Site:

Plug Dam Left Abutment 6914159 584896

Azimuth:

Dip: Date:

Static W.L. from stick-up:

Stick-up A.G.L. along dip:

Static W.L. below G.L.:

Height of gauge A.G.L.:

Bottom of Interval:

Top of Interval:

Length of Interval L:

Middle of Interval to D.F.:

Open Hole Radius R:

Deloitte & Touche Inc.

deg 90 deg

Sept 9/04 5.75 m

0.00 m

5.75 m (vertical)

1.30 m (vertical)

33.53 m

29.78 m 3.75 m


31.66 m (vertical)

0.0375 m

Gauge Total Q Q Head Κ Time Volume Pressure (m³/sec) (mH<sub>2</sub>O) (min) (Litres) (Lpm) (psi) (m/sec) 1.4E-09 5 0.04 0.01 16.0 1.33E-07 18.3 1.33E-07 7.4E-10 5 0.01 40.0 35.2 0.04 47.1 1.33E-07 5.5E-10 5 0.04 0.01 57.0

Q ave: 1.33E-07 (m<sup>3</sup>/sec)

Comments: Static WL measured at 5.75 m below ground. Flow rate measured in Igal and converted to L.



#### **Graphical Analysis**

Q ave:

1.33E-07 (m<sup>3</sup>/sec)

Head H from Plot:

33.53 (m)

Qln(L/R) 2(pi)LH

K = 7.8E-10 m/s

Diamond Drillhole: BGC04-04

Water Test Interval: 32.57m to 36.32m

Project Number:

**General Location:** 

North Coordinate:

0257-027-01

Client: Project Site:

Plug Dam Left Abutment 6914159

**East Coordinate:** 

Azimuth: Dip:

Date:

Static W.L. from stick-up:

Stick-up A.G.L. along dip:

Static W.L. below G.L.:

Height of gauge A.G.L.: Bottom of Interval:

Top of Interval:

Length of Interval L:

Middle of Interval to D.F.:

Open Hole Radius R:

Deloitte & Touche Inc.

584896

deg 90 deg Sept 9/04

5.75 m

0.00 m

5.75 m (vertical)

1.30 m (vertical)

36.32 m 32.57 m 3.75 m


34.45 m (vertical)

0.0375 m

Gauge Total Volume Q Q Head Κ Time Pressure (m³/sec) (mH<sub>2</sub>O)(min) (Litres) (Lpm) (psi) (m/sec) 1.33E-07 1.2E-09 5 0.04 0.01 20.0 21.1 1.33E-07 7.4E-10 5 0.04 0.01 40.0 35.2 8.50E-06 3.1E-08 5 2.55 0.51 67.0 54.2 5 0.04 37.0 1.33E-07 33.1 7.9E-10 0.01

Q ave: 2.23E-06 (m<sup>3</sup>/sec)

Comments: Static WL measured at 5.75 m below ground. Flow rate measured in Igal and converted to L.



#### **Graphical Analysis**

2.23E-06 (m<sup>3</sup>/sec) Q ave:

Head H from Plot: 14.53 (m)

Qln(L/R) 2(pi)LH


K = 3.0E-08 m/s



Laboratory Testing Summary BGC - Anvil Range Mine September 2004 Project # 1200091.015

	Standard Proctor	Optimum Water Content													707	8/ -															
100000	Standar	Maximum Dry Density														Z,U65 Kg/m															
7/0/ 77:	mrs (%)	Plasticity Index			6	7	6	13	10	14		11			13			4													
1 1 1 1 1 1 1 1	Atterberg Limits (%)	Plastic Limit			13	15	10	ω	15	7		7			10			13													
		Liquid Limit			22	22	19	21	25	21		18			23			17													
1,00	@	Gravel			19.8	35.8	32.5	20.6	58.4	19.7		15.6						11.4	18.5	25.1									40.8	29.1	423
10.40	ISTRIBUTION 	Sand			41.4	43.3	43.3	52.1	28.4	41.2		55.9						57.0	54.6	51.0									43.6	53.7	44.3
	Grain Size Distribution (%)	Silt			38.8	20.9	24.2	27.3	13.2	39.1		28.5						31.6	26.9	23.9									15.6	17.2	13.4
	و	Clay			6,		N	N	_	(,)	:	· ·						6,		· ·									Υ-		_
Moisture	Content (%)		10.7	11.1	8.9	8.5	10.1	8.2	5.3	10.0	10.1	8.8	8.6	6.7	9.5	8.0	6.8	8.0	9.0	8.4	8.9	10.0	8.1	8.0	6.5	7.2	7.6	8.7	9.0	8.8	5.5
Sample	Number		GWF - 1	S- JWD	GWF - 4	GWF - 5	9 - JMD	GWF - 7	GWF - 8	GWF - 9	GWF - 10	GWF - 11	GWF - 12	GWF - 13	GWF - 14	GWF - 15	GWF - 16	GWF - 17	GWF - 18	GWF - 19	GWF - 20	GWF - 21	GWF - 22	GWF - 23	GWF - 24	GWF - 25	GWF - 26	GWF - 27	GWF - 28	GWF - 29	GWF - 30
Borehole	Number		BGCTP04-01	BGCTP04-02	BGCTP04-03	BGCTP04-03	BGCTP04-03	BGCTP04-03	BGCTP04-03	BGCTP04-03	BGCTP04-04	BGCTP04-04	BGCTP04-04	BGCTP04-05	BGCTP04-05	BGCTP04-05	BGCTP04-05	BGCTP04-06	BGCTP04-06	BGCTP04-06	BGCTP04-08										






lota presented hereon is for the sole use of the stipulated client. EBA is not responsible, nor can be held lidble, for use made of this report by any other party, with or without the knowledge of EBA

Tested in accordance with ASTM D422 unless otherwise noted.

The testing services reported herein have been performed by an EBA technicion to recognized industry standards, unless otherwise noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.






Data presented hereon is for the sale use of the stipulated client. EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of EBA

Tested in accordance with ASTM D422 unless otherwise noted.

The testing services reported berein have been performed by an EBA technician to recognized industry standards, unless otherwise noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.






Data presented hereon is for the sole use of the atipulated client. EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of EBA

Tested in accordance with ASTM D422 unless otherwise noted.

The testing services reported herein have been performed by an EBA technician to recognized industry standards, unless otherwise noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.






Doto presented hereon is for the sole use of the stipulated client. EBA is not responsible, nor can be held lidble, for use made of this report by any other party, with or without the knowledge of EBA

Tested in accordance with ASTM D422 unless otherwise noted.

The testing services reported herein have been performed by an EBA technician to recognized industry standards, unless atherwise noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.






Data presented hereon is for the sole use of the stipulated client, EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of EBA Tested in accordance with ASTM 0422 unless otherwise noted.

The testing services reported herein have been performed by an EBA technician to recognized industry standards, unless otherwise noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.






Data presented hereon is for the sole use of the stipulated client. EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of EBA

Tested in accordance with ASTM D422 unless otherwise noted.

The tasting services reported herein hove been performed by an EBA technician to recognized industry standards, unless otherwise noted. No other worranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.






Data presented hereon is for the sole use of the stipulated offent. EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of EBA

Tested in accordance with ASTM D422 unless otherwise noted.

The testing services reported herein have been performed by an EBA technician to recognized industry standards, unless otherwise noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.






bota presented hereon is for the sole use of the stipulated client. EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of EBA

Tested in accordance with ASTM D422 unless otherwise noted.

The testing services reported herein have been performed by an EBA technician to recognized industry standards, unless otherwise noted. No other worranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.






Data presented hereon is for the sole use of the atipulated client. EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of EBA

Tested in accordance with ASTM D422 unless otherwise noted.

The testing services reported herein have been performed by an EBA technician to recognized industry standards, unless otherwise noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.






Dota presented hereon is for the sale use of the stipulated client. EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of EBA

Tested in accordance with ASTM 0422 unless otherwise noted.

The testing services reported herein have been performed by an EBA technician to recognized industry standards, unless otherwise noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.






Data presented hereon is for the sale use of the stipulated client. EBA is not responsible, nor can be held liable, for use made of this report by any other party, with ar without the knowledge of EBA

Tested in accordance with ASTM D422 unless otherwise noted.

The testing services reported herein have been performed by an EBA technician to recognized industry standards, unless otherwise noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.





Data presented hereon is for the sole use of the stipulated client. EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of EBA

Tested in accordance with ASTM D422 unless otherwise noted.

The testing services reported herein have been performed by an EBA technician to recognized industry standards, unless otherwise noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material sultability. Should engineering interpretation be required, EBA will provide it upon written request.



## EBA Engineering Consultants Ltd.

#### MOISTURE-DENSITY RELATIONSHIP Project: Anvil Range Mine Sample No.: GSF 13-16 Address: Faro, YT Date Sampled: Sample Location: Project No.: 0201-1200091.015 7-Oct-04 Date Tested: By: MS Sample Description: SAND & GRAVEL - silty Client: BGC Attention: Gerry Ferris Maximum Dry Density: 2065 kg/m<sup>3</sup> 2500 Optimum Water Content: 2400 Natural Water Content: 6.7 Standard Proctor (ASTM D 698) 2300 Hammer Weight: 2.5 Hammer Drop: 305 mm No. of Layers: 3 2200 No. of Blows / Layer: 25 Diameter of Mould: 102 mm Dry Density (kg/m³) Height of Mould: 116 mm 2100 9.44 x 10<sup>-4</sup> m<sup>3</sup> Volume Mould Compactive Effort 600 kJ/m<sup>3</sup> 2000 Reviewed B√: 1900 1800 1700 1500 10.00 0.00 20,00 Water Content (%)

Data presented hereon are for the sole use of the ..stipulated client. EBA is not responsible, nor can be held liable, for use made of this report by any other party, with or without the knowledge of EBA. The testing services reported herein have been performed by an EBA technician to recognized industry standards., unless otherwise noted. No other warranty is made. These data do not include or represent any interpretation or opinion of specification compliance or material suitability. Should engineering interpretation be required, EBA will provide it upon written request.

