

**DELOITTE & TOUCHE INC.**

**TASK 22F**  
**ROSE CREEK DIVERSION CANAL**  
**PRELIMINARY GEOTECHNICAL EVALUATION**  
**FARO MINE, YT**

**REVISION B: DRAFT FOR CLIENT REVIEW**

PROJECT NO.: 0257-037-02  
DATE: DECEMBER 23, 2005

DISTRIBUTION LIST:	
DELOITTE & TOUCHE INC.	0 COPIES
ANVIL RANGE	0 COPIES
NHC - VANCOUVER	1 COPY
BGC – CALGARY	1 COPY
BGC - VANCOUVER	0 COPIES

## EXECUTIVE SUMMARY

This report presents the results of a geotechnical investigation undertaken to support the evaluation of options for increasing the capacity of the Rose Creek Diversion Canal at the Faro Mine, Yukon Territory.

The investigation included a review of existing data and reports, an engineering terrain analysis, shallow geophysical surveys, drilling of 23 boreholes at selected locations along the north and south sides of the existing canal, as well as along a proposed emergency overflow canal alignment located west of Station 46+00.

The area is underlain by metamorphic rocks, primarily a moderately strong calcareous phyllite, with igneous intrusive rocks (primarily strong gabbro) present in some locations below the existing canal. The bedrock is overlain by silty sand till and colluvial (slopewash) materials. The silty sand till contains 20 to 35 percent silt and clay size particles and is generally non-plastic. The colluvial materials vary widely in grain size distribution but in some locations contain 50 to 90 percent silt and clay size particles.

The depth to bedrock on the south (upslope) side of the existing canal ranged from 0 to a maximum of 8.7 meters in the boreholes. On the north (downslope) side of the canal, the depth to bedrock was generally greater than on the south side, and its presence could not be confirmed in some of the holes due to drilling refusal on cobbles and boulders. The maximum confirmed depth to bedrock on the north side of the canal was 12.2 metres.

Discontinuous permafrost was encountered in some of the holes drilled on the south side of the canal, between the diversion dam (Station 11+00) and the left abutment of the Cross Valley Dam (Station 50+00). The permafrost in this area contains some excess ice, primarily within the upper 2 metres below ground surface. The underlying silty sand till contained very little excess ice and is expected to be thaw stable.

Permafrost which contained significant excess ice was encountered in the area west of Station 50+00, and particularly in the colluvial fan west of Station 54+00 of the existing canal. These materials would be very unstable when thawed.

The required design capacity of the diversion canal under the Probable Maximum Flood event will depend on whether or not permanent storm water retention ponds are constructed upstream from the canal. Once the required design capacity of the canal has been established, a cost benefit analysis should be undertaken to establish which of the various options for increasing the capacity of the canal will be most cost effective. It is expected that additional field investigations will be required to support the detailed design of the selected option.

## TABLE OF CONTENTS

<b>1.0</b>	<b>Introduction.....</b>	<b>1</b>
1.1	General.....	1
1.2	Project Background .....	1
<b>2.0</b>	<b>Scope Of Work.....</b>	<b>3</b>
2.1	Compile and Review Existing Data .....	3
2.2	Terrain Analysis.....	3
2.3	Shallow Geophysical Survey .....	4
2.4	Field Drilling and Laboratory Testing.....	4
<b>3.0</b>	<b>Site Conditions .....</b>	<b>5</b>
3.1	Topography and Drainage.....	5
3.2	Geological Setting .....	6
3.3	Bedrock .....	6
3.4	Overburden Soils.....	7
3.5	Permafrost.....	7
<b>4.0</b>	<b>Canal Construction and Performance .....</b>	<b>8</b>
4.1	General.....	8
4.2	Thermal Liner .....	8
4.3	Canal Construction .....	9
4.4	As Built Cross-Sections .....	10
4.5	Canal Performance .....	10
<b>5.0</b>	<b>Geotechnical Evaluation .....</b>	<b>12</b>
5.1	General.....	12
5.2	Canal Widening .....	12
5.3	Raise North Dike .....	14
5.4	Emergency Spillway and Drop Structure.....	15
5.5	Pre-Design Studies .....	17
	<b>References.....</b>	<b>19</b>

## FIGURES

Figure 1	Site Location Plan
Figure 2	Mine Plan
Figure 3	Canal Plan and Profile – Station 0+00 to 35+00
Figure 4	Canal Plan and Profile – Station 35+00 to 60+00
Figure 5	Terrain Analysis
Figure 6	Bedrock Geology
Figure 7	Sketch of Geological Cross-Section
Figure 8	Grain Size Envelopes
Figure 9	Simplified Construction Schedule
Figure 10	Typical Cross-Sections of Existing Canal
Figure 11	Surface Erosion of Thermal Blanket (1982)
Figure 12	Instances of Instability in Canal Backslope (1994)
Figure 13	Conceptual Cross-Section – Canal Widening
Figure 14	Conceptual Cross-Section – Dike Raise

## APPENDICES

Appendix A – Canal Cross-Sections
Appendix B – Borehole Logs Drilled in 1979 (Golder Associates, 1980)
Appendix C – Borehole Logs Drilled in 2005

## **LIMITATIONS OF REPORT**

This report was prepared by BGC Engineering Inc. (BGC) for Deloitte & Touche Inc., the interim receiver for Anvil Range Mining Corporation and the Faro Mine Closure Office. The material in it reflects the judgement of BGC staff in light of the information available to BGC at the time of report preparation. Any use which a Third Party makes of this report or any reliance on decisions to be based on it is the responsibility of such Third Parties. BGC accepts no responsibility for damages, if any, suffered by any Third Party as a result of decisions made or actions based on this report.

As a mutual protection to our client, the public, and ourselves, all reports and drawings are submitted for the confidential information of our client for a specific project and authorization for use and / or publication of data, statements, conclusions or abstracts from or regarding our reports and drawings is reserved pending our written approval.

DRAFT

## **1.0 INTRODUCTION**

### **1.1 General**

This report presents the results of a geotechnical investigation undertaken to support the evaluation of options for increasing the capacity of the Rose Creek Diversion Canal at the Faro Mine, Yukon Territory.

The investigation was undertaken by BGC Engineering Inc. at the request of Mr. Doug Sedgwick of Deloitte & Touche Inc. who are the interim receivers for Anvil Range Mining Corp.

### **1.2 Project Background**

The Faro Mine is located in the central Yukon, approximately 200 km northeast of Whitehorse. The Mine is accessible by an all weather road from Whitehorse and is about 22 km north of the Town of Faro, as shown on the site location map (Figure 1).

Mine operations began in 1969 and ceased in 1998, when the owner, Anvil Range Mining Corporation declared bankruptcy. Deloitte & Touche Inc. were appointed the interim receivers and are working with various regulatory agencies to develop and implement a mine closure plan.

The general arrangement of the Faro Mine is shown on Figure 2. As indicated, the Rose Creek diversion canal is located along the south side of the tailings area. The diversion canal was constructed to provide room for a tailings facility that was constructed in the Rose Creek valley. The canal diverts clean water from the North and South Forks of Rose Creek, around the south side of the tailings storage facility.

Plans and profiles along the existing diversion canal are presented on Figure 3, which shows the eastern (upstream) half of the canal and Figure 4, which shows the western (downstream) section. Cross-sections along the existing canal are presented in Appendix A.

The diversion canal was constructed in two separate stages. An upstream section of the canal, from near Station 10+00 to 19+00 (Figure 3) was completed in 1974 to carry clean water past the second tailings impoundment. A longer downstream section was completed in 1981, in preparation for construction of the intermediate tailings impoundment downstream (west) of the second tailings impoundment. This second reach extended the canal by about 3800 metres from about Station 19+00 to Station 57+00 (see Figure 4), where it discharges back into Rose Creek, downstream from the Cross Valley Dam. The existing canal is therefore about 4700 metres long.

The diversion canal was designed to carry a 1 in 50 year flood event, with 1 meter of freeboard. The contingency design capacity, with no freeboard, will carry a 1 in 500 year flood event. For mine closure, the canal must be designed to carry the Probable Maximum Flood. The capacity of the existing canal could be increased by either excavating the south cut slope to widen the canal, or by increasing the vertical height of the existing north dike.

The maximum design capacity required under the Probable Maximum Flood event will depend on whether or not permanent storm water retention ponds are constructed on either or both of the North and South Forks of Rose Creek to attenuate flows into the diversion canal.

At the time this report was prepared, a decision had not been made with respect to design of the storm retention ponds and therefore the required capacity of the diversion canal was not known. Therefore, the report only provides preliminary geotechnical recommendations.

As indicated on Figures 3 and 4, the existing gradient along the canal invert between Station 46+00 and 56+00 is relatively steep, with an average slope of about 4 percent. A series of drop weirs were installed along this reach of the canal in 1981 to reduce stream velocities. The weirs were designed on the basis of a 1 in 50 year flood event and would be destroyed under the flow volumes associated with the Probable Maximum Flood event.

Therefore, it will be necessary to provide an overflow spillway and drop structure to carry high flow volumes associated with the Probable Maximum Flood. The overflow spillway will be located near Station 46+00. The emergency drop structure could be located anywhere along the south valley wall, west of Station 46+00, with an overflow canal to direct excess water from the spillway at Station 46+00 to the drop structure. A tentative alignment for the proposed overflow canal is shown on Figure 4.

Subsurface conditions can be expected to have a significant effect on which of the various options will be most cost effective. It was therefore agreed that a preliminary geotechnical investigation should be undertaken to provide a better indication of the subsurface conditions along the canal.

This report presents the results of the field investigation, together with a preliminary geotechnical evaluation of the various options currently being considered. It is expected that the information presented in this report will be used to prepare conceptual designs and preliminary cost estimates of the various options. Once the most cost effective option has been determined, detailed geotechnical design recommendations can be prepared, as appropriate.

## **2.0 SCOPE OF WORK**

The scope of work for the preliminary geotechnical investigation included four major tasks:

- 1) Compile and review existing data,
- 2) Conduct an engineering terrain analysis using available airphotos,
- 3) Conduct shallow geophysical surveys along the proposed alignment of the overflow canal west of Station 46+00.
- 4) Undertake a field drilling and laboratory testing program to characterize subsurface conditions along the existing canal and the proposed alignment of the overflow canal.

### **2.1 Compile and Review Existing Data**

As indicated in the list of references at the end of the text, a considerable amount of information was available with respect to the design and construction of the diversion canal. Selected reports have been reviewed and relevant information has been incorporated into this field investigation report, as appropriate.

No design or construction reports were available for the section of the canal constructed in 1974. Subsurface information was available in a design report prepared by Golder Associates (1980) for the section of the diversion canal completed in 1981. The borehole logs from this investigation are presented in Appendix B for reference.

A report that describes the construction of the 1981 section of the canal was also available (Golder Associates, 1982). The diversion canal was inspected annually following construction, and some of these inspection reports were also available for review.

It should be noted that during the period from 1981 to 2003, all references to stations along the canal were referenced to the construction chainage for which chainage 0+00 was located near the diversion dam constructed in 1981. After 2003, a new chainage benchmark was established about 1900 metres upstream from the 1981 diversion dam, along the North Fork of Rose Creek (Figure 3). The approximate 2003 Stations have been estimated by adding 1900 metres to the construction chainages given in earlier reports and drawings. The accuracy of this conversion has not been determined but is thought to be within plus or minus 50 metres.

### **2.2 Terrain Analysis**

A terrain analysis of the area adjacent to the diversion canal was undertaken using 1 to 10,000 scale airphotos taken in 2003 (Orthoshop, 2003). The terrain analysis delineated the surficial geology, existing drainage courses, unstable slopes and other topographic features of interest.

A site inspection was carried out by Mr. Gerry Ferris, P.Eng. of BGC Engineering, during the period from September 10 and 14, 2004 to confirm the results of the airphoto interpretation.



The results of the terrain analysis are summarized on Figure 5. The bedrock geology in the vicinity of the canal is presented on Figure 6. Figure 7 is a sketch illustrating the major geological units in the area of interest.

### **2.3 Shallow Geophysical Survey**

In the summer of 2004, shallow geophysical surveys were undertaken to determine the depth to bedrock below the proposed alignment of the overflow canal, west of Station 46+00. The survey used ground penetrating radar (GPR) and shallow seismic refraction equipment. The results of these geophysical surveys are presented in a report dated December 21, 2004 prepared by Aurora Geosciences Ltd.

Relevant information from the geophysical survey has been used to supplement observations made in the boreholes during the recent field investigation.

### **2.4 Field Drilling and Laboratory Testing**

A site inspection was undertaken during the period from July 31 to August 4, 2005 by Messrs. G. Ferris and J. Severin (G.I.T.) of BGC Engineering Inc., to check site access for the drill rig and finalize borehole locations.

Field drilling was carried out during the period from August 8 to 20, 2005, during which time a total of 23 boreholes were drilled at selected locations as shown on Figures 3 and 4.

All holes were drilled using a CME-75 auger drill rig, owned and operated by Midnight Sun Drilling Limited of Whitehorse. The rig is equipped to drill with either hollow or solid stem augers and can recover soil samples using a Standard Penetration Test (SPT) sampler, shelly tubes or a CRREL core barrel.

All drilling and sampling was carried out under the supervision of Mr. Severin who logged each hole and collected disturbed and undisturbed soil samples at selected intervals.

In boreholes which stood open without sloughing and where fine grained soils were present, the holes were continuously cored with a CRREL barrel. Representative soil samples were taken from the recovered core. The CRREL barrel could not be used if the soil contained gravel or rocks, because the cutting teeth on the barrel would break off. At these locations, the holes were advanced using solid stem augers and disturbed samples were collected off of the auger flights.

In locations where the borehole was unstable due to sloughing soils, the holes were drilled with hollow stem augers and samples were collected with the SPT, provided the ground was not frozen. When used, SPT samples were collected every 2.5 feet to a depth of 10 feet. Below 10 feet, SPT samples were collected at 5 foot intervals to the end of the hole.

On completion of drilling, all boreholes were backfilled with drill cuttings and the borehole locations were staked. The locations and elevations of the ground surface at each hole location were determined in the field by a survey crew from Yukon Engineering Services of Whitehorse.

The water contents of the soil samples were determined. Grain size analyses and Atterberg limits tests were carried out on selected representative samples to confirm visual soil classifications.

Laboratory testing on selected frozen core samples recovered with the CRREL barrel included bulk density, water content determinations, Atterberg limits and grain size analyses. Grain size envelopes for selected overburden materials are presented on Figure 8.

The borehole logs, which include the laboratory test results, are presented in Appendix C.

### **3.0 SITE CONDITIONS**

#### **3.1 Topography and Drainage**

As indicated on Figure 1, the Rose Creek Diversion Canal is located near the toe of the south wall of the Rose Creek Valley. The south valley wall slopes range from 8 to 15 degrees to the horizontal, with short sections ranging up to about 20 degrees. The elevation difference between the valley bottom and the crest is about 500 metres, and the distance from the toe of the slope to the valley crest is about 3 km.

The valley slopes south of the canal are treed with a moderately dense black spruce forest with tree heights ranging to a maximum of about 10 metres. The surface vegetation in most locations consists of mosses and organic material which is generally about 0.3 metres thick in well drained areas of the slope and 1 or more metres thick in poorly drained areas.

The valley slopes south of the canal are generally well drained and trafficable to bulldozers during the thaw season. The area at the east end of the canal in the vicinity of Boreholes BGC05-14 and 15 is poorly drained and has poor trafficability. Surface drainage and trafficability were also poor on the lower valley slopes in the area between Boreholes BGC05-19 and 23.

Four well defined drainage courses are present on the south valley wall, at the locations shown on Figure 8. For convenience, each drainage course has been assigned a name, as follows:

- 1) Gilchrist Creek which intersects the existing canal near Station 11+00,
- 2) Goodall Creek, which intersects the existing canal near Station 26+00,
- 3) Cornish Creek, which intersects the existing canal near Station 51+00, and
- 4) Severin Creek, which intersects the proposed overflow canal near Station 55+00.

Both Goodall Creek and Cornish Creek are known to flow throughout the winter and caused significant icing problems during construction of the diversion canal in 1981. There is no record of similar difficulties in the vicinity of Gilchrist Creek near Station 11+00. There is no information on flows in Severin Creek.

In addition to these drainage courses, significant seepage was also observed during construction of the canal in 1981 in the vicinity of Stations 19+360, 21+010, 21+670, 21+900 and 22+760.

### **3.2 Geological Setting**

The main geological units in the vicinity of the canal are illustrated on Figure 7. The area was subjected to glaciation, which left silty sand till deposits in the lower portion of the Rose Creek valley as indicated. During de-glaciation, the Rose Creek valley was an outwash channel, which left thick deposits of fluvial sands and gravels along the bottom of the valley, which are underlain by silty sand till.

As indicated on Figure 7, during the post-glacial period, the south slopes of the Rose Creek valley were overlain by more recent deposits including colluvium (slopewash) material which directly overlies the bedrock at higher elevations and the silty sand till at lower elevations.

The following sections provide a more detailed description of the soils and rocks along the existing canal alignment.

### **3.3 Bedrock**

As shown on Figure 6, the area below the canal is underlain by metamorphic and igneous rocks of Ordovician age (400 million years before present). Between Stations 19+00 to 40+00 the bedrock consists primarily of calcareous phyllite which is a metamorphic rock similar to slate. Gabbro (an igneous rock) is present along the canal centreline between Stations 26+00 to 30+00 and along the entire existing canal section west (downstream) from Station 40+00.

The unconfined compressive strength of these rocks has not been determined, however they are medium strong to strong and during construction in 1981, it was necessary to drill and blast the rocks before they could be excavated.

The surface of the bedrock is highly variable along the length of the canal, but is generally higher on the left (south) side of the canal and deeper on the right (north) side. The depths to bedrock, as encountered in the test holes drilled in August, 2005 are shown on Drawings 3 and 4.

The near surface rocks are known to be highly fractured and at least within the upper few metres have a relatively high hydraulic conductivity (Golder Associates, 1982).

### **3.4 Overburden Soils**

As indicated on the borehole logs and on Figure 5, the overburden soils consist primarily of colluvium and silty sand till. Grain size envelopes for both materials are presented on Figure 8.

The silty sand till in the vicinity of the canal consists of a well graded mixture of gravel, sand and silt. The fine grained fraction (silt and clay sized particles) generally ranged from 20 to 35 percent. The material is generally low to non-plastic, indicating it contains almost no clay minerals.

A hydraulic conductivity test (Golder Associates, 1980) on a remoulded, compacted sample of the silty sand till measured a hydraulic conductivity of  $3 \times 10^{-7}$  cm/sec. However the conductivity of the material increased by a factor of about 15 when it was subjected of several freeze-thaw cycles. The hydraulic conductivity could increase even more under field conditions over a period of several decades.

The colluvial material is much more variable as compared to the underlying till. As shown on Figure 8, the fine grained fraction of samples taken from Borehole BGC05-21, which is located in a colluvial fan downslope from Station 58+00 on proposed overflow canal (Figure 4), ranged from 50 to 90 percent, which is significantly higher than the fine grained fraction in the silty sand till.

### **3.5 Permafrost**

The site is located in the discontinuous permafrost zone and average annual ground temperatures range between -0.5°C and +0.5°C. The permafrost in the vicinity of the canal is relatively warm and in most cases will degrade if the surface organic layer is disturbed or removed.

#### **North Side of Canal**

Permafrost was not encountered in any of the boreholes drilled at 7 locations in August 2005 on the north (downslope) side of the diversion canal (Boreholes BGC05-to 13).

#### **South Side of Canal**

Permafrost was not encountered in Boreholes BGC05-17 and 18 on the upslope side of the canal, which are located near Stations 33+00 and 38+00, respectively. However permafrost was encountered in the other 8 holes drilled on the upslope side of the canal between Stations 10+00 and 50+00.

In the holes in which permafrost was encountered, excess ice was found mainly in the near surface 1 or 2 metres. Surface trafficability was found to be poor on the upslope side of the canal between Stations 11+00 and 16+00, but was good in all other borehole locations between Stations 16+00 and 50+00.

The silty sand till located immediately upslope from the diversion canal does not appear to contain significant excess ice, between Stations 10+00 to 50+00. The silty sand till is relatively coarse grained and it is expected to be thaw stable.

#### **West of Station 51+00**

Permafrost which contains significant excess ice appears to be widespread west of Station 50+00. Trafficability in this area was found to be very poor in August, 2005. The soils in the colluvial fan contain significant excess ice and have a relatively high silt and clay content. They are expected to be unstable when thawed.

### **4.0 CANAL CONSTRUCTION AND PERFORMANCE**

#### **4.1 General**

This section provides a brief summary of pertinent information extracted from the design, construction and post-construction monitoring reports. For more detailed information, the reader should refer to the original reports.

#### **4.2 Thermal Liner**

During design of the diversion canal, there was concern with respect to the short and long term stability of the permafrost in the cut slope along the south side of the canal. It was recognized that if the permafrost thawed faster than the melt water could drain out of the soil, the slope would become unstable. Therefore, in order to reduce the rate of thaw of the cut slope, it was planned to over-excavate the cut slope during the winter and place a layer of granular fill over the exposed slope.

Determining the thickness of thermal liner required to prevent thaw instability is largely a matter of judgement. In the winter of 1980, a short trial section of the canal was constructed near Station 40+00 to determine the effectiveness of using 1.7 metres of gravel over the exposed permafrost. The trial section was monitored over the following thaw season to confirm the performance of the slope. It has not been possible to locate the report which describes the configuration and results of this trial. It is understood, however that the trial only used one thickness of gravel over the permafrost. Therefore, it is not known if the cut slope would have remained stable if a thinner (or no) thermal lining had been placed over it (G. Gilchrist, 2005).

### 4.3 Canal Construction

A simplified schedule which highlights the major construction tasks is presented in Figure 9. As indicated, construction began in early October, 1980 and was completed 12 months later.

The volumes of common and rock excavation required to construct the diversion canal in 1981, are given in Table 1 below:

**Table 1 – Common and Rock Excavation Volumes  
Rose Creek Diversion Canal in 1981 (Golder Associates, 1982)**

Item	Description	Volume (cubic metres)
1	Common Excavation	465,000
2	Rock Excavation for Canal	55,000
3	Excavation of Rock Cutoff Trench	12,000
4	Thermal Liner	119,000

Item 1, common excavation, included all materials (including frozen and unfrozen soil and fractured rock) that could be excavated without having to be blasted. Rock excavation was any material that had to be blasted before it could be excavated.

From the point of view of interpreting the post construction performance of the canal, a number of items are worth noting.

Common excavation took place primarily during the period from November to April, when temperature records show that average daily temperatures were below freezing. As mentioned, this timing was deliberate to prevent thawing of any ice rich material in the cut slope along the south side of the canal. The gravel thermal liner was placed over the exposed cut slope before spring breakup to minimize the risk of thaw induced instability.

However, winter construction presents a number of disadvantages with respect to earthworks construction. First of all, as noted in the construction report, it was not possible to determine the extent of permafrost (including ice rich permafrost) in the native material, because even though significant volumes of unfrozen material were encountered at depth, the face of the excavation usually froze within 24 hours.

Secondly, as indicated on Figure 9, a significant portion of the fill for the north dike was placed during March and April, when average air temperatures were below freezing. It is very difficult to achieve satisfactory placement and compaction of fill materials for the dike because the material is frozen and it cannot be adequately compacted. In addition, even if great care is taken by the inspectors and earthworks contractor, ice, snow and large rocks (which appear to be frozen lumps of soil) will be incorporated into the fills.

Finally, it is worth noting that the contract incorporated a bonus / liquidated damages clause to ensure canal construction was substantially completed by October 1, 1981. The contractor would be paid \$10,000 per day for each day in advance of October 1 that construction of the canal was substantially completed and \$10,000 per day penalty for each day after October 1 until the canal was substantially completed. Such incentives are not uncommon; however, if the contractor believes that he cannot meet the target date, construction quality will suffer, despite the efforts of the most conscientious inspectors.

#### **4.4 As Built Cross-Sections**

Typical as built cross-sections of the diversion canal are presented on Figure 10. As shown, in locations where bedrock was not present, the south cut slope was over-excavated and trimmed to a slope of 2 horizontal to 1 vertical. About 1.7 metres of granular fill (thermal liner) was placed over the exposed permafrost to prevent it from becoming unstable during the following thaw season. The excavated material was used to construct the north dike. Silty clay till was placed on the inside slope of the north dike to reduce seepage through the dike. Riprap erosion protection was then placed over the slopes and invert of the canal to prevent erosion.

In locations where bedrock was encountered, the rock slope was trimmed to 0.5 to 1 vertical, and the overlying soil was trimmed to 2 horizontal to 1 (Figure 10). A thermal liner or riprap erosion protection was not required over the exposed rock; however it was required on top of the overlying soil as shown. The excavated material was used to construct the north dike and silty clay till was placed on the inside of the dike to reduce seepage. In locations where the north dike was constructed on bedrock, there was concern that there would be a significant amount of seepage through the near surface fractured bedrock below the dike. Therefore, a cutoff trench was excavated into the rock below the inside toe of the north dike. The trench was backfilled with compacted silty clay till to reduce seepage through the bedrock.

#### **4.5 Canal Performance**

The construction report (Golder Associates, 1982) provides an excellent summary of the performance of the canal earthworks during the period from May to September, 1981, the first thaw season after construction. Annual inspection reports since that time indicate that the canal has performed satisfactorily, requiring only minimal maintenance.

##### **South Cut Slope**

The construction report found virtually no thaw settlements or instability on the south cut slope of the canal during the first summer after construction.

During the summer of 1981, surface runoff flowed over the top of the cut slope and eroded the gravel thermal blanket in some locations, as shown on Figure 11. Drainage swales were therefore installed along the crest of the cut slope to direct surface water to rock filled drainage channels placed at strategic intervals along the cut slope.

An inspection carried out in June, 1994, identified three locations on the south side of the canal where instability was observed (Geo-Engineering MST, 1995):

- 1) An active slump, about 30 metres long, near Station 32+00 on Figure 3. A photo of the slump is presented on Figure 12. The slump is located near one of the till borrow sources used during canal construction. The slump is localized and may be the result of progressive melting of an ice lens within the till, or it may be a groundwater discharge area.
- 2) A minor slump in the vicinity of Station 35+50 (Figure 4) which appears to be associated with surface erosion at that location.
- 3) A fresh landslide, about 100 metres long near Station 39+00. A photo of this instability is also presented on Figure 12. The cause of this slide, which was first observed in the spring of 1994, is uncertain. The immediate cause is believed to have been water that ponded on the upslope (south) side of a construction access road at this location.

The bedrock slopes on the south slope of the diversion canal have remained stable since construction; however there are one or two locations where fractures in the rock are opening up and small scale rock falls may occur in the future.

### **North Dike**

Cracking and settlements of the north dike were noted in a few localized areas and some minor seepage along the north toe of the dike was observed during the first thaw season after construction. None of these defects were of significant concern and continued monitoring and minor regrading of the dikes was recommended. Dike settlements were either the result of inadequate compaction of the fill materials during the previous winter or thaw settlement of ice rich permafrost within the foundation soils.

A report prepared by Golder Associates (1990) indicated that minor thaw settlements and dike slope movements were occurring in the vicinity of Stations 38+00 and 40+00. Some mitigative measures were constructed near Station 40+00 in 1989, however movements at that location were continuing at the time of the 1990 report.

In the decades since construction, the crest of the north dike between stations 31+00 and 41+00 settled a total of about 1 metre. In the summer of 2004, additional fill was placed along this section of the north dike to raise it back to its initial design elevation.



## Drop Weirs

The drop weirs in the canal between stations 49+00 and 56+00 have performed satisfactorily. Some of the rock in the weirs was shifted when flows from a 1 in 40 year flood event occurred. This observation indicates that while the drop weirs conform to the design requirement of a 1 in 50 year flood event, they would most likely be damaged if higher flows were to occur.

## 5.0 GEOTECHNICAL EVALUATION

### 5.1 General

Conceptually, two basic approaches for increasing the capacity of the existing Rose Creek diversion canal can be considered:

- 1) Increasing the width of the canal by excavating material from the south side of the canal, or
- 2) Raising the height of the north dike, so that the water level in the canal can be increased.

The geotechnical aspects of the two options are discussed separately in the following sections, although it is recognized that the most cost effective approach may be to excavate material from the south side of the existing canal and use it to raise the height of the north dike.

### 5.2 Canal Widening

The capacity of the canal can be increased by widening the canal along the south side, as shown schematically on Figure 13.

Care should be taken during canal widening not to disturb or damage the compacted soil lining on the existing canal invert or on the slopes of the north dike. In addition, in those locations where bedrock is encountered on the invert of the widened portion of the canal, it may be necessary to extend the existing cutoff trench into the fresh bedrock excavation. This requirement would have to be confirmed by observations during construction.

It will be necessary to maintain water flow in the canal throughout construction, and in addition, it would be desirable not to damage the lining on the invert of the existing canal. Therefore, it is recommended that the invert elevation of the widened section of the canal remain about 1 metre above the normal water level in the canal during the construction season. This geometry will also cause flows to remain concentrated within the existing canal channel or, at low flows, in the pilot channel. This is particularly important during the early fall and winter to minimize icing in the canal.

For preliminary design, it is recommended that cut slopes in rock should not exceed 0.5 horizontal to 1 vertical. Slopes in bedrock should be scaled to remove loose boulders. It is expected that the rock slopes will remain stable in most locations; however the exposed rock cuts should be inspected by an experienced engineer to determine whether there are any local areas which will require slope flattening or rock reinforcement such as rock bolts or shotcrete.

For preliminary design, it is recommended that cut slopes in silty clay till be trimmed to 2 horizontal to 1 vertical. The silty clay on the cut slope and along the base of the canal section will be susceptible to erosion during periods of high flows in the canal. The requirement and class of riprap erosion protection on the cut slope and on the canal invert should be determined by a hydraulics engineer.

Observations over the past few decades, together with the information obtained from the recent geotechnical investigation, indicate that the frozen silty sand till will remain stable in most locations during the thaw season. It is expected however, that occasional pockets of ice rich soil will be encountered within the till which may result in localized sloughing in the short term. In addition, the overlying ice rich colluvial materials may have to be cut back and covered with gravel to control sloughing. It is not expected that it will be necessary to overexcavate the silty clay till and place a thick granular thermal blanket over the entire cut slope.

It is recommended that widening of the canal be undertaken during the thaw season, so that any ice rich zones can be readily identified and allowed to drain and stabilize as construction proceeds. If unstable areas are encountered in the excavation, a thermal liner can be added to those sections as necessary. Silty sand till excavated from the south side of the canal may be used in the construction of the north dike, provided it has thawed and drained before it is placed and compacted. Alternatively, the till could be used to provide a soil cover over the existing tailings.

It is expected that some fine grained, ice rich zones will be encountered on the south side of the canal, particularly in the near surface 1 to 2 metres below the natural ground surface. Those materials which contain a significant proportion of fine grained or organic material will have to be wasted. This is particularly a concern between Stations 11+00 and Station 16+00, where trafficability of the near surface soils is known to be poor.

If widening the canal proves to be the most cost effective option, It is recommended that at least one full size test excavation be constructed during the thaw season, at a suitable location in the vicinity of Station 14+00, to confirm the expected behaviour of the cut slopes as they thaw during construction. The observations made during the test excavation should be documented and the results should be made available to contractors who are considering bidding for the canal upgrading project.

As mentioned, the primary cause of erosion of the south cut slope following construction in 1981 was uncontrolled flow of surface runoff over the face of the slope (Figure 11). It is recommended that a shallow swale be constructed at the top of the slope to direct surface runoff into rock filled channels placed at strategic locations along the length of the canal. The locations of the drainage swales and rock filled channels will have to be established based on field observations made during the first few thaw seasons after construction.

It is expected that the thickness of the overburden materials over the bedrock will decrease towards the south (upslope) from the canal. However, it is not possible to provide a reliable estimate of the volumes of colluvium, silty sand till and rock that will be encountered in the excavation based on the information currently available. The volume of rock, in particular, should be determined more accurately, since it will have a significant effect on construction costs. In addition, if the most cost effective option is to both widen the canal and use the excavated material to increase the height of the north dike, it would be important to determine the volume of silty sand till as accurately as possible.

It is understood that there is concern that shallow skin flows could occur on the slopes south of the diversion canal, which could block the canal. Skin flows can be initiated by events such as forest fires or unusually heavy rainfall. It is recommended that the slopes be inspected during the late summer months by an experienced geotechnical engineer to confirm surface drainage conditions and the properties of the near surface soils. This information is required to evaluate the risk of skin flows occurring on these slopes in the future.

### **5.3 Raise North Dike**

The second basic approach for increasing the capacity of the canal is to raise the height of the north dike of the canal, as illustrated conceptually on Figure 14. The dike could be raised by using material excavated from the south side of the canal or by importing material from designated borrow sources.

As indicated on the figure, the outside shell of the north dike can be constructed of waste rock hauled from the existing rock dumps or from rock liberated by widening the canal to the south. In any case, it will be necessary to place silty sand till on the south side of the dike to prevent seepage losses through the dike. The silty sand till could be excavated from sources located on the south side of the canal or from any other designed borrow source in the area. It may be necessary to place filter cloth or filter gravel between the silty clay liner and the outside shell of the north dike, depending on the gradation of the material used to construct the shell.

Riprap erosion protection will be required over the silty clay liner placed on the north dike to control erosion from surface precipitation as well as water flowing in the canal during design flood events. The class of riprap should be determined by a hydraulics engineer.

Care will be required during construction not to disturb the compacted silty clay liner that is present on the south slope of the existing dike.

As indicated on Figure 14, a significant portion of the enlarged north dike will extend into the area where tailings were deposited during mine operations. A comparison of the topography prior to placement of the tailings, with that which currently exists, indicates that from Stations 19+00 to 38+00, the foundation soils along the north side of the existing dike should provide adequate support for an enlarged dike.

However, in the section from Stations 38+00 to 44+00, soft, compressible tailings, which range up to 20 metres in thickness, are present close to the toe of the existing dike. These materials will not provide a stable foundation for an enlarged dike. There are three options that can be considered for overcoming this difficulty.

- 1) Subexcavate or densify the tailings to provide a stable foundation for the dike. This option may not be practical depending on the properties of the tailings,
- 2) Limit the maximum height of the dike, to a height that can be accommodated in this section, without having to extend the dike onto the tailings, and
- 3) Realign the section of the dike between Stations 38+00 to 44+00, as necessary, so that the dike can be enlarged without placing fill on the tailings.

It is recommended that a cost benefit analysis be undertaken during the next stage of design to determine which of these options is most cost effective.

The availability of silty clay till on the south side of the canal may limit the maximum height to which the north dike can be raised. As mentioned in the previous section, once the optimum design for increasing the capacity of the diversion canal has been established, a series of probe holes should be drilled along the south side of the canal so that a more reliable estimate of the available volume of silty clay till can be established.

#### **5.4 Emergency Spillway and Drop Structure**

As mentioned, the drop weirs in the existing canal west of Station 46+00 (Figure 4) could be eroded away under extreme flow events in the canal.

The existing drop weirs could be replaced with a single reinforced concrete drop structure in the vicinity of Station 46+00. As indicated on Figure 4, the structure would be relatively large, since the vertical drop is about 30 metres and it would have to incorporate a fish ladder to allow fish passage upstream under normal flow conditions. A reinforced concrete drop structure would be relatively expensive and in addition, would require ongoing maintenance to prevent the concrete from deteriorating. Ultimately, after many decades, it might become necessary to construct a replacement structure.

A better option would be to maintain the existing canal alignment, including the drop weirs, which are designed to allow fish passage up this section of the canal. The existing canal would carry normal stream flows up to about a 1 in 50 year event. An emergency spillway and drop structure would be provided which would be designed to carry excess flows above the 1 in 50 year event. Under this scheme, the emergency spillway and drop structure would only be rarely used.

Since bedrock occurs relatively close to the surface below the south valley wall, it should be possible to construct at least the upper portion of the drop structure in rock. Conceptually the structure could be located anywhere along the proposed alignment of the overflow canal between Station 44+00 and Borehole BGC05-23 (Figure 4).

From a geotechnical point of view it would be preferable to locate the drop structure close to the emergency spillway, somewhere between Stations 44+00 and 46+00, for the following reasons:

- 1) The bedrock between Stations 44+00 and 46+00 is expected to consist of gabbro, a hard igneous rock which is more durable than the calcareous phyllite that underlies the area below the south valley wall west of Station 50+00 (Figure 6).
- 2) Examination of the airphotos indicates that debris flows have occurred periodically in Severin Creek, which crosses near Station 55+00 of the proposed overflow canal. The data obtained in the bore hole drilled in this area indicates that at least three debris flows have occurred at this location in the past. The frequency of occurrence of the debris flows is not known, but could be in the order of every few decades or centuries, depending on climate changes.
- 3) Consideration was given to placing the drop structure east of Severin Creek, between Stations 49+00 and 54+00 of the proposed overflow canal. However, this option would require that a relatively large embankment be constructed between the existing canal and the bottom of the drop structure to direct storm water away from the existing canal, downstream from Station 52+00. The embankment would have to be constructed on the colluvial fan, which, as indicated on Borehole Log BGC05-23 consists of ice rich, thaw unstable soils which extend to depths of about 4 metres.

Ideally, an emergency drop structure between Stations 44+00 and 46+00, should be excavated in bedrock over its entire height. The bedrock is visible at ground surface near the existing canal in this area and was encountered at a depth of 8.6 metres in Borehole BGC05-10.

If a decision is made to locate the emergency spillway and drop structure in this area, it will be necessary to determine the surface topography of the bedrock more accurately so that the design of the emergency spillway, drop structure and outlet structures can be optimized. It is expected that this work can be accomplished by drilling probe holes in combination with geophysical methods. In addition, it is recommended that core samples be obtained of the rock below the proposed location for the drop structure, to establish the rock lithology, depth of weathering, durability, unconfined compressive strength and other properties.

A significant advantage of locating the drop structure between Stations 44+00 and 46+00 is that the outflow would be directed upstream from the Cross Valley Dam. It is understood that this dam may be breached as part of mine closure; however a final decision has not been made.

If the dam is breached, the breach should be located near the north abutment, so that remnants of the dam embankment would outflow from the emergency drop structure away from the downstream section of the existing canal. If the dam is not breached, then it would be necessary to increase the size of the existing emergency spillway located near the north abutment of the dam. If the capacity of the emergency spillway of the dam increased, the topography of the bedrock surface in the vicinity of the spillway should be determined using a combination of probe holes and geophysical methods. In addition, core samples of the rock should be obtained to confirm the properties of the rock below this area.

## **5.5 Pre-Design Studies**

Once the required design capacity of the canal under the Probable Maximum Precipitation event has been established, it is recommended that conceptual designs for increasing the capacity of the canal and for the emergency spillway and drop structure be prepared. The conceptual designs should be based on the geotechnical recommendations presented in this report and should include cross-sections spaced at 100 to 200 metres along the canal, so that material volumes can be estimated to an acceptable level of accuracy.

Preliminary cost estimates for the various options should be prepared so that the most cost effective combination of options can be determined.

It is expected that once the most cost effective approach for increasing the capacity of the diversion canal has been determined, it will be necessary to undertake additional field drilling to support detailed design. Detailed geotechnical design and construction recommendations can be prepared once the subsurface information from these investigations is available.

**BGC Engineering Inc.**

**Per:**

Bruce Smith, M.Sc., P.Eng.  
Project Engineer

DRAFT

Gerry Ferris, M.Sc., P.Eng.  
Review Engineer


## REFERENCES


- Aurora Geosciences Ltd, 2004. *Ground Penetrating Radar and Seismic Refraction Surveys at the Faro Mine, Yukon Territory*. Report prepared for BGC Engineering Inc, dated December 21, 2004.
- BGC Engineering Inc. 2004a. *Hydraulic Capacity Assessment, Rose Creek Diversion Canal*. Report prepared for Deloitte & Touche Inc. June 30, 2004
- BGC Engineering Inc. 2004b. *Evaluation of the North Fork Rock Drain*. Draft report prepared for Deloitte & Touche Inc.
- Golder Associates, 1980. *Final Design Recommendations for the Down Valley Tailings Disposal Project, Faro, Yukon Territory*. Report prepared for Cyprus Anvil Mining Corporation, June 1980.
- Golder Associates, 1982. *Down Valley Tailings Containment Project, 1980-81 Construction, Faro, Yukon*. Report prepared for Cyprus Anvil Mining Corporation.
- Golder Associates, 1990. *1989 Performance Monitoring of the Down Valley Tailings Project, Faro Mine, Volume 1*. Report to Curragh Resources Inc., March, 1990.
- Golder Associates, 2004. *Rose Creek Tailings Impoundment, Site Characterization and Seismic Stability Assessment Report, Anvil Range Mining Complex, Yukon*. Report submitted to SRK Consulting Inc.
- Geo-Engineering (M.S.T.) Ltd., 1989. *Faro Mine, Report on 1988 Inspection*. Report prepared for Northern Affairs Program, Whitehorse, Y.T., dated January, 1989.
- Geo-Engineering (M.S.T.) Ltd., 1991. *Faro Mine, Report on 1990 Inspection*. Report prepared for Northern Affairs Program, Whitehorse, Y.T, dated January, 1991.
- Geo-Engineering (M.S.T.) Ltd., 1995. *Faro Mine, Report on 1994 Inspection*. Report prepared for Northern Affairs Program, Whitehorse, YT, dated January, 1995.
- Gilchrist, G., 2005. Personnel communication.
- Hydrocon Engineering (Continental) Ltd. 1980. *Hydrologic and Hydraulic Design of Down Valley Tailings Disposal Project, Cyprus Anvil Mining Corporation, Faro Mine, YT*. Report Prepared for Golder Associates, May 1980.
- Hydrocon Engineering (Continental) Ltd. 1982. *Rose Creek Diversion, Down Valley Tailings Disposal Project, Cyprus Anvil Mining Corporation, Review of Licensing Requirements and As-Built Conditions*. Report prepared for Golder Associates. May 1980.



- Pigage, L.C., 2001. *Geological map of Mount Mye (NTS 105K/6W), Central Yukon (1:25,000 scale)*. Exploration and Geological Services Division, Yukon Region, Indian and Northern Affairs Canada, Open File 20010-28.
- Northwest Hydraulic Consultants 2001. *Hydrotechnical Assessment for Faro Mine Site*. Report prepared for BGC Engineering Inc.
- Northwest Hydraulic Consultants 2003. *Rose Creek Diversion Channel at Faro Mine, Yukon, Hydrotechnical Investigation*. Submitted to BGC Engineering Inc.
- Northwest Hydraulic Consultants 2004. *Hydrotechnical Study for Closure Planning, Faro Mine Site Area, Yukon*. Report submitted to SRK Consulting Inc.
- Sigma Resource Consultants Ltd. 1975. *Rose Creek Diversion Works, Observations and Measurements Made During Spring Runoff – 1975*. Report prepared for Cyprus Anvil Mining Corporation, June 1975.
- SRK Consulting Inc. 2003. *Scoping Studies for Final Closure and Reclamation Plan, Faro Mine, Faro, Yukon*. Report prepared for Deloitte & Touche Inc. January 2003.
- The Orthoshop 2003. *1:20,000 and 1:10,000 scale airphotos of the Faro Mine*. Prepared for SRK Consulting Inc.

**FIGURES**

A large, 3D, light gray watermark of the word "DRAFT" is oriented diagonally across the center of the page, from the bottom-left towards the top-right. The word is rendered in a bold, sans-serif font with a beveled, three-dimensional effect.



**Note: Base map figure provided by Gartner Lee Limited.**

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

SCALE:	As Shown	DESIGNED:	LBS
DATE:	JANUARY 2005	CHECKED:	GWf
DRAWN:	SLF	APPROVED:	

CLIENT:

**Deloitte  
& Touche**

**BGC**

**BGC Engineering Inc.**  
AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta.

Phone: (403) 250-5185

PROJECT  
**TASK 22F**  
**RCDC - PRELIMINARY GEOTECH EVALUATION**

TITLE

**SITE LOCATION PLAN**

PROJECT No.

0257-037-01

FIGURE No.


1

REV.

A



0257-023-03 001 Fig 2.dwg



CLIENT:

**Deloitte  
& Touche**

**LEGEND:**

- ROADS
- EXISTING DRAINAGE
- ORIGINAL DRAINAGE
- EFFLUENT PIPELINE
- PIPELINE
- WATER MONITORING SITE

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

REV.	DATE	REVISION NOTES	DRAWN	CHECKED	APPROVED

SCALE:	AS SHOWN
DATE:	JAN 2006
DRAWN:	JMS
DESIGNED:	LBS
CHECKED:	GWF
APPROVED:	



PROJECT	TASK 22F RCDC - PRELIMINARY GEOTECHNICAL EVALUATION	
TITLE	MINE PLAN	
PROJECT No.	0257-037-02	FIGURE No. 2
REV.	A	

**NOTES:**

1. BASE MAP SUPPLIED BY THE ORTHOSHOP, JANUARY 1991
2. NORTH AMERICAN DATUM 1927
3. CONTOUR INTERVAL 100m
4. UNIVERSAL TRANSVERSE MERCATOR PROJECTION
5. MAP IS A COMPOSITE OF 9 BASEMAPS

**BGC ENGINEERING INC.**  
AN APPLIED EARTH SCIENCES COMPANY

**BGC** Calgary, AB Phone: (403) 250 5185



PROJECTION: UTM NAD27 ZONE 8

**NOTES:**


1. TOPOGRAPHIC BASE INFORMATION FROM RECTIFIED AIRPHOTOS, THE ORTHOSHOP 2003.
2. ELEVATIONS OF BOREHOLES FROM DIRECT SURVEY, YUKON ENGINEERING SERVICES 2005.

Legend:	
R	Bedrock
Mb/R	Morrainal Blanket over Bedrock
Mb	Morrainal Blanket
Cv	Colluvium
Ff	Fluvial Fan
⊙	Boreholes

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

REV.	DATE	REVISION NOTES	DRAWN	CHECK	APPR.

SCALE	1:10,000
DATE	DEC 6, 2005
DRAWN	EBN/GCB
DESIGNED	LBS
CHECKED	GWF
APPROVED	—



**BGC**


**BGC ENGINEERING INC.**  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, AB Phone: (403) 250 5185

CLIENT


**Deloitte & Touche**

PROJECT		
TASK 22F RCDC - PRELIMINARY GEOTECHNICAL EVALUATION		
TITLE		
CHANNEL PLAN AND PROFILE STATION 0+00 TO 35+00		
PROJECT No.	FIGURE	REV.
0257-037-01	3	A







200m 0 200m 400m 600m  
SCALE = 1:10,000



DETAIL B



DETAIL A



Legend:  
R Bedrock  
Mb/R Morrainal Blanket over Bedrock  
Mb Morrainal Blanket  
Cv Colluvium  
Ff Fluvial Fan  
Boreholes

PROJECTION: UTM NAD27 ZONE 8


NOTES:

1. TOPOGRAPHIC BASE INFORMATION FROM RECTIFIED AIRPHOTOS, THE ORTHOSHOP 2003.
2. ELEVATIONS OF BOREHOLES FROM DIRECT SURVEY, YUKON ENGINEERING SERVICES 2005.

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

REV.	DATE	REVISION NOTES	DRAWN	CHECK	APPR.

SCALE	1:10,000
DATE	DEC. 6, 2005
DRAWN	REM/GCB
DESIGNED	LBS
CHECKED	GWF
APPROVED	



**BGC ENGINEERING INC.**  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, AB Phone: (403) 250 5185

CLIENT


**Deloitte  
& Touche**

PROJECT TASK 22  
RCDC - PRELIMINARY GEOTECHNICAL EVALUATION

TITLE CANAL PLAN AND PROFILE  
STATION 35+00 TO 60+00

PROJECT No.	FIGURE	REV.
0257-037-01	4	A





Source: Airphotos G0307052-2-(070,072,074)  
Scale 1:10,000 taken 07-25-03  
The Orthoshop, Calgary, AB

- Legend:
- Ff- Fluvial Fan
  - Cv - Colluvium
  - R - Rock
  - Cv/R - Thin Colluvium Overlying Rock
  - Mb - Moraine
  - Mb/R - Thin Moraine overlying Rock
  - Cv/Mb - Thin Colluvium Overlying Moraine



AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

	-	-	-	-	-
-	-	-	-	-	-
-	-	-	-	-	-
REV.	DATE	REVISION NOTES	DRAWN	CHECKED	APPROVED


SCALE:	N/A	
DATE:	JANUARY 2005	
DRAWN:	SLF	
DESIGNED:	LBS	
CHECKED:	GWF	
APPROVED:		

PROJECT TASK 22F RCDC - PRELIMINARY GEOTECH EVALUATION		
TITLE TERRAIN ANALYSIS		
PROJECT No. 0257-037-01	FIGURE No. 5	REV. A

**BGC Engineering Inc.**  
AN APPLIED EARTH SCIENCES COMPANY

Calgary Alberta      Phone: (403) 250-5185





Source: Pigage, L.C. 2001

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

SCALE:	N/A	DESIGNED:	LBS
DATE:	JANUARY 2006	CHECKED:	GWf
DRAWN:	JMS	APPROVED:	

CLIENT:

**Deloitte  
& Touche**

**BGC**

**BGC Engineering Inc.**  
AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta.

Phone: (403) 250-5185


PROJECT  
TASK 22F  
RCDC - PRELIMINARY GEOTECH EVALUATION

TITLE  
BEDROCK GEOLOGY


PROJECT No.	DWG. No.	REV.
0257-037-01	6	0



Overall Slope Angle Ranges from 8 to 15 with short sections up to 20 .



DATE: JAN. 2006	DRAWN SLF	 <b>BGC ENGINEERING INC.</b> AN APPLIED EARTH SCIENCES COMPANY Calgary, Alberta Phone: (403) 250-5185	PROJECT TASK 22F RCDC - PRELIMINARY GEOTECH EVALUATION		
<b>REFERENCED DRAWING DESCRIPTION</b> AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.		<b>TITLE</b> <b>SKETCH OF GEOLOGICAL CROSS-SECTION</b>			
CLIENT 		PROJECT No. 0257-037-01		FIGURE No. 7	REV. A



**Legend:**

- |   |         |   |         |
|---|---------|---|---------|
| ○ | JMS 96  | ○ | JMS 123 |
| □ | JMS 60  | □ | JMS 95B |
| △ | JMS 88  | △ | JMS 101 |
| ◇ | JMS 108 |   |         |

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

**BGC ENGINEERING INC.**  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, Alberta Phone: (403) 250-5185

Client: **Deloitte & Touche**

Project: **TASK 22F RCDC – PRELIMINARY GEOTECHNIAL EVALUATION**

Title: **GRAIN SIZE ANALYSIS ENVELOPES**

Project #: **0257-037-01**


Date: **JAN 2006**

Scale: **NA**

Drawn: **JMS**

Approved: **GWf**

Figure: **8**



AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.



**BGC ENGINEERING INC.**  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, Alberta Phone: (403) 250-5185


Client: **Deloitte & Touche**

Project: **TASK 22F RCDC – PRELIMINARY GEOTECHNIAL EVALUATION**


Title: **SIMPLIFIED CONSTRUCTION SCHEDULE**

Project #: 0257-037-01	Date: JAN 2006	Scale: NA	Drawn: JMS	Approved: GWF	Figure: 9
---------------------------	-------------------	--------------	---------------	------------------	--------------

## Common Excavation - Seepage Liner



## Rock Excavation - Seepage Liner




CLIENT:

**Deloitte  
& Touche**

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

	-	-	-	-	-
-	-	-	-	-	-
-	-	-	-	-	-
REV.	DATE	REVISION NOTES	DRAWN	CHECKED	APPROVED

SCALE:	N/A
DATE:	DECEMBER 2005
DRAWN:	SLF
DESIGNED:	GWF
CHECKED:	GWF
APPROVED:	GWF



PROJECT		
RCDC - SITE INVESTIGATION		
TITLE		
PROJECT No.	FIGURE No.	REV.
0257-037-01	10	0



**BGC Engineering Inc.**  
AN APPLIED EARTH SCIENCES COMPANY

Calgary Alberta

Phone: (403) 250-5185



Source: 1982 Hydrocon Report

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

SCALE:	N/A	DESIGNED:	JBS
DATE:	JANUARY 2006	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	GWF

CLIENT: **Deloitte & Touche**

PROJECT **TASK 22F**  
**RCDC - PRELIMINARY GEOTECH EVALUATION**

TITLE **SURFACE EROSION OF THERMAL BLANKET 1982**

PROJECT No.	FIGURE No.	REV.
0257-037-01	11	A

**BGC Engineering Inc.**  
AN APPLIED EARTH SCIENCES COMPANY  
**BGC** Calgary, Alberta. Phone: (403) 250-5185





Source: Geo-Engineering 1994

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA STATEMENTS CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

SCALE:	N/A	DESIGNED:	JBS
DATE:	JANUARY 2006	CHECKED:	GWF
DRAWN:	SLF	APPROVED:	

CLIENT:

**Deloitte  
& Touche**


**BGC**

**BGC Engineering Inc.**  
AN APPLIED EARTH SCIENCES COMPANY

Calgary, Alberta.

Phone: (403) 250-5185

PROJECT TASK 22F RCDC - PRELIMINARY GEOTECH EVALUATION		
TITLE INSTANCES OF INSTABILITY IN CANAL BACKSLOPE (1994)		
PROJECT No. 0257-037-01	FIGURE No. 12	REV. A



AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

**BGC** ENGINEERING INC.  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, Alberta Phone: (403) 250-5185

Client: **Deloitte & Touche**

Project: **TASK 22F RCDC – PRELIMINARY GEOTECHNIAL EVALUATION**

Title: **CONCEPTUAL CROSS-SECTION – CANAL WIDENING**

Project #: **0257-037-01**


Date: **JAN 2006**

Scale: **NA**

Drawn: **JMS**

Approved: **GWF**

Figure: **13**



AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

**BGC** ENGINEERING INC.  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, Alberta Phone: (403) 250-5185

Client: **Deloitte & Touche**

Project: **TASK 22F RCDC PRELIMINARY GEOTECHNICAL EVALUATION**

Title: **CONCEPTUAL CROSS-SECTION- DIKE RAISE**

Project #: 0257-037-01	Date: JAN 2006	Scale: NA	Drawn: JMS	Approved: GWF	Figure: 14
---------------------------	-------------------	--------------	---------------	------------------	---------------




## APPENDIX A - CANAL CROSS-SECTIONS

DRAFT


# STATION 13+00

LEGEND	
	CURRENT TOPO
	PRE-MINE TOPO
	BEDROCK
Mb	MORAINAL BLANKET
R	BEDROCK
Cv	COLLUVIUM
Ⓢ	CENTERLINE OF EXISTING CANAL



# STATION 15+00

LEGEND	
	CURRENT TOPO
	PRE-MINE TOPO
	BEDROCK
Mb	MORAINAL BLANKET
R	BEDROCK
Cv	COLLUVIUM
Ⓢ	CENTERLINE OF EXISTING CANAL




0257-037-02 - RCDC Canal Sections.dwg

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

REV.	DATE	REVISION NOTES	DRAWN	CHECK	APPR.

SCALE	1:1500
DATE	DEC. 9, 2005
DRAWN	EBN
DESIGNED	EBN
CHECKED	GWF
APPROVED	GWF



**BGC ENGINEERING INC.**  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, AB Phone: (403) 250 5185

CLIENT


**Deloitte & Touche**

PROJECT FARO MINE - ROSE CREEK DIVERSION CANAL		
TITLE SECTION AT 13+00 AND SECTION AT 15+00		
PROJECT No. 0257-037-02	FIGURE A.1	REV. A

STATION 20+00

LEGEND


—	CURRENT TOPO
- - -	PRE-MINE TOPO
XXXX	BEDROCK
Mb	MORAINAL BLANKET
R	BEDROCK
Cv	COLLUVIUM
⊕	CENTERLINE OF EXISTING CANAL



STATION 25+00

LEGEND

—	CURRENT TOPO
- - -	PRE-MINE TOPO
XXXX	BEDROCK
Mb	MORAINAL BLANKET
R	BEDROCK
Cv	COLLUVIUM
⊕	CENTERLINE OF EXISTING CANAL




0257-037-02 - RDCD Canal Sections.dwg

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

REV.	DATE	REVISION NOTES	DRAWN	CHECK	APPR.

SCALE	1:1500
DATE	DEC. 9, 2005
DRAWN	EBN
DESIGNED	EBN
CHECKED	GWF
APPROVED	GWF




**BGC ENGINEERING INC.**  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, AB Phone: (403) 250 5185

CLIENT **Deloitte & Touche**

PROJECT	FARO MINE - ROSE CREEK DIVERSION CANAL
TITLE	SECTION AT 20+00 AND SECTION AT 25+00
PROJECT No.	0257-037-02
FIGURE	A.2
REV.	A


# STATION 30+00

LEGEND	
—	CURRENT TOPO
- - -	PRE-MINE TOPO
▨	BEDROCK
Mb	MORAINAL BLANKET
R	BEDROCK
Cv	COLLUVIUM
⊕	CENTERLINE OF EXISTING CANAL



# STATION 35+00

LEGEND	
—	CURRENT TOPO
- - -	PRE-MINE TOPO
▨	BEDROCK
Mb	MORAINAL BLANKET
R	BEDROCK
Cv	COLLUVIUM
⊕	CENTERLINE OF EXISTING CANAL




0257-037-02 - RCDC Canal Sections.dwg

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

REV.	DATE	REVISION NOTES	DRAWN	CHECK	APPR.

SCALE	1:1500
DATE	DEC. 13, 2005
DRAWN	EBN
DESIGNED	EBN
CHECKED	GWF
APPROVED	GWF




**BGC ENGINEERING INC.**  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, AB Phone: (403) 250 5185


CLIENT **Deloitte & Touche**

PROJECT FARO MINE — ROSE CREEK DIVERSION CANAL		
TITLE SECTION AT 30+00 AND SECTION AT 35+00		
PROJECT No. 0257-037-02	FIGURE A.3	REV. A

# STATION 40+00



# STATION 45+00




0257-037-02 - RDC Canal Sections.dwg

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

REV.	DATE	REVISION NOTES	DRAWN	CHECK	APPR.

SCALE	1:1500
DATE	DEC. 13, 2005
DRAWN	EBN
DESIGNED	EBN
CHECKED	GWF
APPROVED	GWF



**BGC ENGINEERING INC.**  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, AB Phone: (403) 250 5185


CLIENT

**Deloitte & Touche**

PROJECT FARO MINE - ROSE CREEK DIVERSION CANAL		
TITLE SECTION AT 40+00 AND SECTION AT 45+00		
PROJECT No. 0257-037-02	FIGURE A.4	REV. A


# STATION 50+00

LEGEND	
—	CURRENT TOPO
- - -	PRE-MINE TOPO
XXXX	BEDROCK
Mb	MORAINAL BLANKET
R	BEDROCK
Cv	COLLUVIUM
⊕	CENTERLINE OF EXISTING CANAL



# STATION 55+00

LEGEND	
—	CURRENT TOPO
- - -	PRE-MINE TOPO
XXXX	BEDROCK
Mb	MORAINAL BLANKET
R	BEDROCK
Cv	COLLUVIUM
⊕	CENTERLINE OF EXISTING CANAL




0257-037-02 - RCDC Canal Sections.dwg

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

REV.	DATE	REVISION NOTES	DRAWN	CHECK	APPR.

SCALE	1:1500
DATE	DEC. 13, 2005
DRAWN	EBN
DESIGNED	EBN
CHECKED	GWF
APPROVED	GWF




**BGC ENGINEERING INC.**  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, AB Phone: (403) 250 5185

CLIENT


**Deloitte & Touche**

PROJECT FARO MINE -- ROSE CREEK DIVERSION CANAL		
TITLE SECTION AT 50+00 AND SECTION AT 55+00		
PROJECT No. 0257-037-02	FIGURE A.5	REV. A

# STATION 60+00



# STATION 65+00




0257-037-02 - RDC Canal Sections.dwg

AS A MUTUAL PROTECTION TO OUR CLIENT, THE PUBLIC AND OURSELVES, ALL REPORTS AND DRAWINGS ARE SUBMITTED FOR THE CONFIDENTIAL INFORMATION OF OUR CLIENT FOR A SPECIFIC PROJECT AND AUTHORIZATION FOR USE AND/OR PUBLICATION OF DATA, STATEMENTS, CONCLUSIONS OR ABSTRACTS FROM OR REGARDING OUR REPORTS AND DRAWINGS IS RESERVED PENDING OUR WRITTEN APPROVAL.

REV.	DATE	REVISION NOTES	DRAWN	CHECK	APPR.

SCALE	1:1500
DATE	DEC. 13, 2005
DRAWN	EBN
DESIGNED	EBN
CHECKED	GWF
APPROVED	GWF



**BGC ENGINEERING INC.**  
AN APPLIED EARTH SCIENCES COMPANY  
Calgary, AB Phone: (403) 250 5185

**Deloitte & Touche**

PROJECT	FARO MINE - ROSE CREEK DIVERSION CANAL
TITLE	SECTION AT 60+00 AND SECTION AT 65+00
PROJECT No.	0257-037-02
FIGURE	A.6
REV.	A

**APPENDIX B - BOREHOLE LOGS DRILLED IN 1979  
(Golder Associates, 1980)**



A drawing showing the location  
of these borehole logs is currently  
under preparation.

# RECORD OF BOREHOLE 79-8

1806-18N ; -92-71 E  
LOCATION (See Figure 3 )

BORING DATE Aug. 2, 1979

BOREHOLE TYPE Rotary with air

BOREHOLE DIAMETER 120 mm

SAMPLER HAMMER WEIGHT 635 kg. DROP 76.2 cm DATUM Ground Surface

Project No. 192-2025

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	BLOWS / FOOT	ELEVATION SCALE	WATER CONTENT PERCENT W <sub>p</sub> W      W <sub>L</sub> 10      20      30      40				PIEZOMETER OR STANDPIPE INSTALLATION	ADDITIONAL LAB. TESTING
ELEV. DEPTH (m)	DESCRIPTION											
1078.80 0.0	Cleared Surface Some boulders											Cleared surface
	Frozen greenish gray sandy silt TILL, no visible ice		1	5mm D.O.	48							G-20 S-34 M-36 C-10
			2	"	62							G-20 S-30 M-34 C-16
			3	"	86							G-12 S-33 M-35 C-20
			4	"	700							G-37 S-34 M-24 C-5
	] boulder [											
	] ice [		5	"	7100							G-15 S-40 M+C-45
1068.43 10.37	Drills more easily - may not be frozen		6	"	7100							
	Brown to red-brown medium to coarse sand (alluvium) probably frozen											
1066.0 12.8	] cobble / boulder [											
	] cobble [											
	shist bedrock											
1062.65 16.15	End of Borehole											

VERTICAL SCALE  
1:125

Golder Associates B.H. 79-8

DRAWN R.D.  
CHECKED JG

# RECORD OF BOREHOLE 79-22

1869.83 N; -198.86 E

LOCATION (See Figure 3 )


BORING DATE 19 Aug 1979

BOREHOLE TYPE Rotary with mud

BOREHOLE DIAMETER 114 mm

SAMPLER HAMMER WEIGHT 63.5 kg DROP 76.2 cm DATUM Cleared ground surface

Project No. 79Z-2025

SOIL PROFILE									PIEZOMETER OR STANDPIPE INSTALLATION	
ELEV. DEPTH (m)	DESCRIPTION	STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	BLOWS / 300 mm	ELEVATION SCALE	WATER CONTENT PERCENT			ADDITIONAL LAB. TESTING
							W <sub>P</sub>	W	W <sub>L</sub>	
1079.20	Cleared ground surface									
0.00	Frozen olive brown to grey fine sandy SILT TILL, occ. coarse sand and gravel pockets		1	76 mm DO	>100					G-59 S-26 M+C -15
			2	"	>100					
1070.06	End of Borehole									No installations
NOTE: Borehole abandoned due to loss of pit seal. Four boreholes were attempted with mud in this area, but all had to be abandoned. Borehole 79-22A was drilled with air										

G-59  
S-26  
M+C  
-15

No installations

VERTICAL SCALE 1:125

Golder Associates BH.79-22

DRAWN RK  
CHECKED DG

# RECORD OF BOREHOLE 79-22A

1840-84 N; -185-90 E

LOCATION (See Figure 3)

BORING DATE 21 Aug 1979

BOREHOLE TYPE Rotary with air

BOREHOLE DIAMETER 114 mm

SAMPLER HAMMER WEIGHT 63.5 kg DROP 76.2 cm DATUM Cleared ground surface

Project No. 792-2025

SOIL PROFILE			STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	BLOWS / 300 mm	ELEVATION SCALE	TEMPERATURE, °C				PIEZOMETER OR STANDPIPE INSTALLATION	ADDITIONAL LAB. TESTING	
ELEV. DEPTH (m)	DESCRIPTION	-0.5 0 +0.5 +1.0												
		WATER CONTENT PERCENT W <sub>P</sub> W W <sub>L</sub>												
1081.90	Cleared ground surface											Cleared surface?		
0.00	Frozen alternating brown & grey fine sandy SILT TILL, non-plastic to low plasticity, occ. organic layers											19mm dia. PVC pipe		
1079.46												Thermistor #1		
2.44	Frozen grey to greenish grey sandy SILT TILL											#2		
	easier drilling											#3		
												#4		
1066.66												Sandpack?		
15.24	= organic											#5		
	Dark grey SILT, non-plastic, occ. cobble or pebble											Cave-in material?		
1063.61														
18.29	End of Borehole													

VERTICAL SCALE 1:125

Golder Associates BH.79-22A

DRAWN RK  
CHECKED DE

# RECORD OF BOREHOLE 79-23

1910.41N; -387.72E

LOCATION (See Figure 3)

BORING DATE 22 Aug 1979

BOREHOLE TYPE Rotary with mud to 2.2m;  
air to 18.29m

BOREHOLE DIAMETER 114 mm

SAMPLER HAMMER WEIGHT 63.5 kg DROP 76.2 cm

DATUM Cut ground surface

Project No. 792-2025

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	BLOWS / 300 mm	ELEVATION SCALE	WATER CONTENT PERCENT				PIEZOMETER OR STANDPIPE INSTALLATION	ADDITIONAL LAB. TESTING
ELEV. DEPTH (m)	DESCRIPTION						W <sub>p</sub>	W	W <sub>L</sub>			
1083.17 0.00	Cut ground surface										Ground surface ↗	
	Ice seams to 12 mm thickness		1	76 mm D.O. >100							19 mm dia. PVC pipe ↗	
	Frozen brown to grey fine sandy SILT TILL, some visible ice near surface		2	" >100							Peltonite seal ↗	
	organic											
1074.03 9.14	Organic black fine to coarse SAND & GRAVEL (appears to be unfrozen)		3	" 90								
	cobble											
1070.06 13.11	SAND & GRAVEL											
	Grey fine sandy SILT TILL											
	Boulder											
1064.88 18.29	End of Borehole											
NOTE: Borehole abandoned due to rotting of permafrost & caving. Hole size at surface ≈ 0.7m dia.												

NOTE:

Piezometer installed in auxilliary borehole drilled with air, about 4m East of BH. 79-23

VERTICAL SCALE  
1:125

Golder Associates BH. 79-23

DRAWN *RK*  
CHECKED *DE*

RECORD OF BOREHOLE 79-24

1161.40 N ; 1222.52 E  
LOCATION (See Figure 3 )

BORING DATE 22 Aug 1979

DATUM Cleared ground surface

BOREHOLE TYPE Rotary with mud

BOREHOLE DIAMETER 114 mm

SAMPLER HAMMER WEIGHT 63.5 kg DROP 76.2 cm

PEN. TEST HAMMER WEIGHT DROP

SOIL PROFILE			SAMPLES		ELEVATION SCALE	DYNAMIC PENETRATION RESISTANCE BLOWS/FT. -----					TEMPERATURE, °C -0.5    0    +0.5    +1.0 Δ				ADDITIONAL LAB. TESTING	PIEZOMETER OR STANDPIPE INSTALLATION	
ELEV. DEPTH (m)	DESCRIPTION	STRAT. PLOT	NUMBER	TYPE		BLOWS/300mm	SHEAR STRENGTH C <sub>u</sub> , LB./SQ.FT.					WATER CONTENT, PERCENT W <sub>p</sub> W                  W <sub>L</sub> 10                  20                  30                  40					
1084.64 0.00	Ground surface														Ground surface ↘		
	Olive brown fine sandy SILT TILL, compact to dense		1		76mm D.O.	29											
1082.35 2.29	Grey fine sandy SILT TILL, low plasticity, fissured, compact to dense (cold but not frozen)		2	"		18											
			3	"		25											
			4	"		31											
	sample seems frozen		5	"		>100											
1075.80 8.84	Grey clayey SILT to sandy SILT TILL, hard																
1070.01 14.63	Blue sandy to clayey SILT TILL, hard																
1067.88 16.76																	
	Light grey clayey SILT TILL, low to medium plasticity, hard																
1061.78 22.86	End of Borehole																
							Composite sample formed from samples 2, 3, and 5 for strength testing. $\phi' = 33^\circ$										
							Percent axial strain at failure										

VERTICAL SCALE  
1:100

Golder Associates BH. 79-24

DRAWN RK  
CHECKED DG

# RECORD OF BOREHOLE 79-25

1050.57N; 1432.59E  
LOCATION (See Figure 3)

BORING DATE 27 Aug 1979

BOREHOLE TYPE Rotary with air

BOREHOLE DIAMETER 114 mm

SAMPLER HAMMER WEIGHT 63.5kg DROP 76.2cm DATUM Cleared ground surface

Project No. 792-2025

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	BLOWS / 300 mm	ELEVATION SCALE	TEMPERATURE, °C		PIEZOMETER OR STANDPIPE INSTALLATION
ELEV. DEPTH (m)	DESCRIPTION						-0.5 0 +0.5 +1.0	WATER CONTENT PERCENT W <sub>p</sub> W W <sub>L</sub>	
1087.00	Cleared ground surface								Ground surface
0.00	Organic SILT & debris								Thermistor #1
1086.09									
0.91	Sandy SILT TILL								#2
1085.48									
1.52	Frozen SILT TILL and schisty TILL								
1082.73									
4.27	SCHIST BOULDER								27 Sept 79 W.L. #3
1080.90									
6.10	Sandy SILT TILL								#4
6.55	SCHIST BEDROCK								Peltonite seal
1079.68									#5
7.32	Relatively hard SCHIST BEDROCK								#6
1076.64									#7
10.36	Relatively soft SCHIST BEDROCK								#8
1074.81									#9
12.19	End of Borehole								Petur pneumatic piezometer

VERTICAL SCALE  
1:100

Golder Associates BH. 79-25

DRAWN RK  
CHECKED DG

DROP

DRAWN R.W.  
CHECKED DG



Project No. 192-2025

## RECORD OF BOREHOLE 80-47

Canal Sta. 2+370  
1600.2 N 164.8 E

LOCATION (See Figure 3)

BORING DATE Feb. 23, 1980

BOREHOLE TYPE Rotary with air

BOREHOLE DIAMETER 100 mm

SAMPLER HAMMER WEIGHT 140 LB. DROP 30 IN.

DATUM Cleared ground surface

SOIL PROFILE						PIEZOMETER OR STANDPIPE INSTALLATION	
ELEV. DEPTH	DESCRIPTION	STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	BLOWS / FOOT	ELEVATION SCALE	ADDITIONAL LAB. TESTING
(m.)							

Backfilled with cuttings

No testing

Bentonite seal

Sand & gravel pack  
Slotted 20mm PVC pipe

Dry at 10.0 m March 8/80

VERTICAL SCALE  
1:100

Golder Associates B.H. 80-47

DRAWN RW  
CHECKED DE

Project No. 7922025

DATUM *Cleared ground surface*

DRAWN R.W.  
CHECKED DG

Project No. 792 2025

Canal Sta. 2+220  
1528.8 N 299.2 E

## RECORD OF BOREHOLE B.H. 80-49

LOCATION (See Figure 3)

BORING DATE Feb 23, 1980

BOREHOLE TYPE Rotary with air

BOREHOLE DIAMETER 100 mm

SAMPLER HAMMER WEIGHT 140 LB. DROP 30 IN.

DATUM Cleared ground surface

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	BLOWS / FOOT	ELEVATION SCALE	PIEZOMETER OR STANDPIPE INSTALLATION			
ELEV.	DESCRIPTION						WATER CONTENT PERCENT			
DEPTH (metres)							W <sub>p</sub>	W	W <sub>L</sub>	ADDITIONAL LAB. TESTING
							10	20	30	40
1088.83	Cleared ground surface									
0.0 1088.23	Frozen organic SILT									Cuttings backfill
0.6	boulder [ boulder Greenish-brown to brown SAND and GRAVEL TILL frozen to about 4m. depth very dry (possibly disturbed bedrock)									Bentonite seal
1079.73										Sand & gravel backfill
9.1 1078.13	Grey schisty BEDROCK									Slotted 20mm PVC pipe
10.7	End of Borehole									Dry at 10.0 m March 8/80

VERTICAL SCALE  
1:100

Golder Associates B.H. 80-49

DRAWN RW.  
CHECKED DG

Project No. 192-2025

## RECORD OF BOREHOLE B.H. 80-50

Canal Sta. 2+100  
1475.8 N 404.4 E  
LOCATION (See Figure 3)

BORING DATE February 23, 1980

BOREHOLE TYPE Rotary with air

BOREHOLE DIAMETER 100 mm.

SAMPLER HAMMER WEIGHT 140 LB. DROP 30 IN.

DATUM Cleared ground surface

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	BLOWS / FOOT	ELEVATION SCALE	WATER CONTENT PERCENT				PIEZOMETER OR STANDPIPE INSTALLATION	ADDITIONAL LAB. TESTING
ELEV. DEPTH (metres)	DESCRIPTION						W <sub>p</sub>	W	W <sub>L</sub>			
1085.66	Cleared ground surface											
0.0 1084.46	Frozen brown organic SILT											
1.2 1083.26	Greenish brown SAND and GRAVEL TILL (unfrozen)											
2.4 1080.76	BROWN SAND and GRAVEL, unfrozen											
4.9 1077.76	Grey silt and sand cuttings, probably disturbed BEDROCK, very dry, probably friable											
7.9 1076.56	Schisty BEDROCK											
9.1	End of Borehole											

No testing

Cuttings backfill 2

Bentonite seal 2

Sand &amp; gravel backfill 2

Slotted 20 mm PVC pipe 2

Dry at 8.0 m March 8/80

VERTICAL SCALE  
1:100

Golder Associates B.H. 80-50

DRAWN R.W.  
CHECKED DG

Project No. 792-2025

## RECORD OF BOREHOLE B.H. 80-51

CONCL. Sta. 2+000  
1438.0 N 482.5 E  
LOCATION (See Figure 3)


BORING DATE Feb. 23, 1980

BOREHOLE TYPE Rotary with air

BOREHOLE DIAMETER 100 mm

SAMPLER HAMMER WEIGHT 140 LB. DROP 30 IN.

DATUM Cleared ground surface



VERTICAL SCALE  
1:100

Golder Associates BH 80-51

DRAWN RW  
CHECKED DG

Project No. 192-2025

## RECORD OF BOREHOLE B.H. 80-52

Corral Sta. 1+890

1369.5 N 618.5 E

LOCATION (See Figure 3)

BORING DATE Feb. 23, 1980

BOREHOLE TYPE Rotary with air

BOREHOLE DIAMETER 100mm

SAMPLER HAMMER WEIGHT 140 LB. DROP 30 IN.

DATUM Cleared Ground Surface

SOIL PROFILE							PIEZOMETER OR STANDPIPE INSTALLATION				
ELEV. DEPTH (metres)	DESCRIPTION	STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	BLOWS / FOOT	ELEVATION SCALE	WATER CONTENT PERCENT				ADDITIONAL LAB. TESTING
							W <sub>p</sub>	W	W <sub>L</sub>		
							10	20	30	40	
1089.41	Cleared ground surface										
1088.81	Frozen, bwn, organic SILT										
0.6	Frozen, greenish-grey, SAND and GRAVEL TILL										Sand & gravel pack 2
											Bentonite seal 2
1083.31											Sand & gravel pack 2
6.1	SAND and GRAVEL TILL with sandy silt pockets (unfrozen)										Slotted 20 mm PVC pipe 2
1080.31											
9.1	End of Borehole										Dry at 7.8 m March 8/80
	Note: Log based on driller's observations										

VERTICAL SCALE  
1:100

Golder Associates B.H. 80-52

DRAWN R.W.  
CHECKED DE

RECORD OF TEST PIT SHEETS

Other Than Along Diversion Canal

Test Pit No. 1 to 20 incl.  
23 to 25 incl.



Project No. 792-2025

2503.4 N -589.3 E

## RECORD OF TEST PIT T.P. 7.9-5

LOCATION (See Figure)

DATE 6 Aug 1979

DATUM Ground surface

METHOD OF EXCAVATION DB Cat &amp; ripper PROJECT

DOWN VALLEY

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT				ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV. N. DEPTH	DESCRIPTION					W <sub>p</sub>	W	W <sub>L</sub>			
(m)						10	20	30	40		
1055.83	Ground surface										
0-00	Organic silt & debris										
0-25	White volcanic ash										
0-46	Brown to brown grey dense coarse sandy GRAVEL										
			1	C.S.							
1053.33											
2-50	Frozen, oxidized med. to coarse SAND, some gravel (to .1m. dia.), dense, thaws quickly									G-49 S-49 M+C-2	
			2	C.S.							
1051.83											
4-0	Olive brown fine to coarse SAND, little med. gravel									G-48 S-50 M+C-2	
			3	C.S.							
1049.83											
6-00	Bottom of Test Pit										

VERTICAL SCALE

1:50

Golder Associates T.P. 79-5

DRAWN RK  
CHECKED DG

Project No. 792-2025

## RECORD OF TEST PIT T.P. 79-6

2300.2N 467.9E  
LOCATION (See Figure)

DATE 7 Aug 1979

DATUM Ground surface

METHOD OF EXCAVATION DB Cat &amp; ripper PROJECT

DOWN VALLEY

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT				ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV.N. DEPTH (m)	DESCRIPTION					W <sub>p</sub>	W	W <sub>L</sub>			
1055.69	Ground surface										
0.00	Organic silt & debris, moss										
1055.39											
0.30	White volcanic ash										
0.51											
	Brown coarse sandy GRAVEL, (max. size 0.5 m)										
1052.49											
3.20											
	Brown grey med. to coarse SAND, some frozen, some gravel to .3 m dia., becoming sandier with depth										
1050.09											
5.60	Bottom of Test Pit										

VERTICAL SCALE  
1:50

Golder Associates T.P. 79-6

DRAWN RK  
CHECKED JG

Project No. 79Z-2025

2041.7N 380.7E

## RECORD OF TEST PIT T.P. 79-7

LOCATION (See Figure)

DATE 8 Aug 1978

DATUM Ground surface

METHOD OF EXCAVATION DB Cat &amp; ripper PROJECT

DOWN VALLEY

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT W <sub>p</sub> W      W <sub>L</sub>			ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV. N. DEPTH (m)	DESCRIPTION									
1057.55	Ground surface									
0.00 1057.28	Moss & organic debris									
0.30 1056.36	Black frozen organic SILT w>>wp, material flows when Thawed									
1.22	Brown gravelly SAND becoming finer with depth		1	C.S.					G-78 SM, C-22	
1054.23	Bottom of Test Pit									
3.35	Depth varies along length of pit									

VERTICAL SCALE

1:50

Golder Associates T.P. 79-7

DRAWN RK  
CHECKED DG

Project No. 792-2025

2131.4N - 441.5E RECORD OF TEST PIT T.P. 79-11

LOCATION (See Figure)

DATE 25 Aug 1979

DATUM Ground surface

METHOD OF EXCAVATION DBCat &amp; ripper PROJECT

DOWN VALLEY

SOIL PROFILE			STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT				ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV.N. DEPTH (m)	DESCRIPTION											
1060.82	Ground surface											
0.00	Frozen organic SILTS & debris with moss at top of stratum, some fine & medium to coarse sand pockets											
1059.30												
1.52	Frozen gravelly SAND (no cobbles or coarse gravel)											
1057.16												
3.66	Bottom of Test Pit											

VERTICAL SCALE  
1:50

Golder Associates T.P. 79-11

DRAWN RK  
CHECKED DG



## RECORD OF TEST PIT T.P. 79-21

LOCATION (See Figure 3)

DATE *Dec. 12. 1979*

DATUM *Ground Surface*

METHOD OF EXCAVATION *D-8 Caterpillar PROJECT Down Valley Tailings*

Project No. 792 2025

[illegible]

VERTICAL SCALE  
1:50

Golder Associates TP 79-21

DRAWN R.W.  
CHECKED DG

# RECORD OF TEST PIT T.P. 0+045

LOCATION (See Figure)

DATE 26 Aug 1979

DATUM Ground surface

METHOD OF EXCAVATION DB Cat & ripper PROJECT Down valley

Project No. 792-2025

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT				ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV. DEPTH	DESCRIPTION					W <sub>P</sub>	W	W <sub>L</sub>			
(m)						10	20	30	40		
1091.3	Ground surface										
0.00	Moss & organic debris										
0.30	Frozen organic SILT, volcanic ash, some boulders										
1090.2											
1.07	Frozen brown sandy GRAVEL (ALLUVIUM), some silty pockets										
1087.6											
3.66	Bottom of Test Pit										
	Surveyed pit bottom elevation 1088.0										

CB1-5  
G-47  
S-39  
M+C-9

VERTICAL SCALE  
1:50

Golder Associates T.P. 0+045

DRAWN RK  
CHECKED DG



# RECORD OF TEST PIT T.P. 0+195

LOCATION (See Figure)

DATE 26 August 1979

DATUM Ground surface

METHOD OF EXCAVATION DB Cat & ripper PROJECT Down valley

Project No. 792-2025

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT				ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV. N. DEPTH (m)	DESCRIPTION					W <sub>p</sub>	W	W <sub>L</sub>			
1092.3	Ground surface										
0.00	Organic debris & moss										
0.28	Brown silty GRAVEL TILL, high proportion of schist rock boulder lag at approx. 1:83 m										
1089.9											
2.44	Bottom of Test Pit										
	Surveyed pit bottom elevation 1090.2										

1-C.S.

○

G-75  
S-18 non-plastic  
M-9

VERTICAL SCALE  
1:50

Golder Associates T.P. 0+195

DRAWN RK  
CHECKED DG

Project No. 792-2025

## RECORD OF TEST PIT T.P. 0+760


LOCATION (See Figure)

DATE 26 Aug 1979

DATUM Ground surface

METHOD OF EXCAVATION DB Cat &amp; ripper PROJECT

Down Valley

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT				ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV.N. DEPTH (m)	DESCRIPTION					W <sub>p</sub>	W	W <sub>L</sub>			
1091.9	Ground surface										
0-15	Organic debris & moss White volcanic ash										
1090.22	Greenish brown silty fine SAND TILL										
1-68	Greenish grey massive metavolcanic rock dipping into slope										
1087.94	396 Bottom of Test Pit										
	surveyed pit bottom elevation 1088.6										

G-51  
S-28 non-plastic  
M-20  
C-1

VERTICAL SCALE

1:50

Golder Associates T.P. 0+760

DRAWN RK  
CHECKED DG

Project No. 702-2025

## RECORD OF TEST PIT T.P. 1+095

LOCATION (See Figure)

DATE 26 Aug 1979

DATUM Ground surface

METHOD OF EXCAVATION DB Cat &amp; ripper PROJECT

Down Valley

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT				ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV. N. DEPTH (m)	DESCRIPTION					W <sub>p</sub>	W	W <sub>L</sub>			
1029.5	Ground surface										
0.00 1029.2	Moss & organic debris										
0.30	Olive brown fine sandy SILT TILL (frozen below 1.22 m)										
1.92 1027.1	Frozen black organic SILT Frozen SAND & GRAVEL										
2.44	Frozen greenish brown fine sandy SILT TILL										
1084.6 4.88	Bottom of Test Pit  Surveyed pit bottom elevation 1085.4										

1-C.5.      0

G-51  
S-35  
M-13  
C-1

VERTICAL SCALE  
1:50

Golder Associates T.P. 1+095

DRAWN RK  
CHECKED JG

# RECORD OF TEST PIT T.P. 1+680

LOCATION (See Figure)

DATE 26 Aug 1979

DATUM Ground surface

METHOD OF EXCAVATION DB Cat & ripper PROJECT

Down valley

Project No. 792-2025

SOIL PROFILE			STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT				ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV. N. DEPTH (m)	DESCRIPTION						W <sub>P</sub>	W	W <sub>L</sub>			
1086.5	Ground surface											
0.00	Organic debris & moss											
1086.1												
0.43	Frozen organic SILT & Brown sandy SILT COLLUVIUM											
1085.3												
1.22	Brown sandy SILT to silty fine SAND COLLUVIUM with several organic seams				1-C.S.						G-39 S-32 M-28 C-1	
1084.7												
1.83												
	Greenish brown fine sandy SILT TILL											
1082.2					2-C.S.						G-53 S-30 M-15 C-2	
4.27	Bottom of Test Pit											
	Surveyed pit bottom elevation 1082.6											

VERTICAL SCALE  
1:50

Golder Associates T.P. 1+680

DRAWN RK  
CHECKED DG

Project No. 792-2025

## RECORD OF TEST PIT T.P. 2+155

LOCATION (See Figure)

DATE 25 Aug 1979

DATUM Ground surface

METHOD OF EXCAVATION DB Cat &amp; ripper PROJECT

DOWN Valley

SOIL PROFILE			SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT				ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV. N. DEPTH (m)	DESCRIPTION	STRATIGRAPHY PLOT									
1084.0	Ground surface										
0.00	Moss & organic debris										
1083.7											
0.30											
	Frozen, mixed brown sandy SILT (TILL) COLLUVIUM & organic SILT, some visible ice									G-25 S-34 M-32 C-9	
1080.65											
3.05											
	Brown silty SAND									G-35 S-38 M-24 C-3	
1076.69											
3.96	Blue green massive BEDROCK										
1072.42											
4.27	Bottom of Test Pit										
	NOTE: Test pit elevation estimated from diversion canal baseline profile.										

VERTICAL SCALE

1:50

Golder Associates T.P. 2+155

DRAWN RK

CHECKED DG

Project No. 792-2025

DATE 25 Aug 1979

DATUM *Ground surface*

METHOD OF EXCAVATION *D8 Cat & ripper* PROJECT

Down Valley

SOIL PROFILE						ELEVATION SCALE	WATER CONTENT, PERCENT W <sub>P</sub> W      W <sub>L</sub> 	ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV N. DEPTH	DESCRIPTION	STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE					
(m)									
1083.5	Ground surface								
0.00	Moss &								
1083.1	organic SILT								
0.41									

VERTICAL SCALE  
1:50

Golder Associates T.P. 2+515

DRAWN *RK*  
CHECKED *DG*

Project No. 792-2025

## RECORD OF TEST PIT T.P. 2+910

LOCATION (See Figure)

DATE 25 Aug 1979

DATUM Ground surface

METHOD OF EXCAVATION DB Cat &amp; ripper PROJECT

Down Valley

SOIL PROFILE		STRATIGRAPHY PLOT	SAMPLE NUMBER	SAMPLE TYPE	ELEVATION SCALE	WATER CONTENT, PERCENT				ADDITIONAL LAB. TESTING	GROUNDWATER CONDITIONS
ELEV. DEPTH (m)	DESCRIPTION					W <sub>p</sub>	W	W <sub>L</sub>			
1086.0	Ground surface										
0.00	Organic debris & moss										
1085.7											
0.30	Frozen olive brown fine sandy SILT										
1085.09											
0.61	COLLUVIUM										
	Frozen brown sandy SILT COLLUVIUM, contains visible ice crystals, organic layer & cobbles at 1.2 m										
1083.57											
1.52											
	Frozen brown sandy SILT TILL, ice rich, non plastic to low plasticity										
1079.91											
3.66	Frozen grey & brown fine sandy SILT TILL, organic seam at 4.6 m										
1074.73											
5.18	Bottom of Test Pit										
	NOTE: Test pit elevation estimated from diversion canal base-line profile.										

1-C.S.

0

G-19  
S-36  
M-39  
C-6

NOTE:  
Surticial mud flows occurring thawing progresses

VERTICAL SCALE

1:50

Golder Associates T.P. 2+910

DRAWN RK  
CHECKED DG





**APPENDIX C - BOREHOLE LOGS DRILLED IN 2005**

DRAFT

# BOREHOLE # BGC05-01

Page 1 of 1

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580888.50E, 6913408.70N

Co-ordinates in NAD 27

Ground Elevation (m) : 1054.1 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 02 Aug 05

Finish Date : 02 Aug 05

Final Depth of Hole (m) : 2.4

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa										
									40	80	120	160							
									VANE	FIELD	LAB	UC/2							
									PEAK	◆	■	▲							
									REMOLD	◇	□	△							
★ % Fines				● SPT (blows/300mm)		Moisture Content & SPT N		W <sub>p</sub> %	W <sub>p</sub> %	W <sub>p</sub> %									
X	20	40	60	80	X														
0					SAND (FILL) Some Gravel, trace Silt. Dense, non-plastic, moist, reddish brown.														
1		JMS 01		UF	SILT (FILL) Some Gravel, some Sand. Dense, non-plastic to low plasticity, grey. at 1.3 m, some oxidation, white powdery crystals.	Cuttings		33	○										
2		JMS 02						30	○										
		JMS 03						100	○										
3					End of Hole: 2.4 m, auger refusal on cobble/boulder..  At 2.3 m, SPT gives 50 blows for 2 inches. Abandoned hole. No water observed. No sloughing observed.														
4																			

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

BGC

Calgary, AB

Phone (403) 250 5185

Client:

Deloitte  
& Touche

## BOREHOLE # BGC05-02

Page 1 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580881.10E, 6913412.60N

Co-ordinates in NAD 27

Ground Elevation (m) : 1054.1 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm


Start Date : 02 Aug 05

Finish Date : 02 Aug 05

Final Depth of Hole (m) : 9.8

Logged by : J. Severin

Reviewed by : G. Ferris



(Continued on next page)

BGC

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

Deloitte  
& Touche

# BOREHOLE # BGC05-02

Page 2 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580881.10E, 6913412.60N

Co-ordinates in NAD 27

Ground Elevation (m) : 1054.1 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm


Start Date : 02 Aug 05

Finish Date : 02 Aug 05

Final Depth of Hole (m) : 9.8

Logged by : J. Severin

Reviewed by : G. Ferris



(Continued on next page)



**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

**Deloitte  
& Touche**

# BOREHOLE # BGC05-02

Page 3 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580881.10E, 6913412.60N

Co-ordinates in NAD 27

Ground Elevation (m) : 1054.1 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 02 Aug 05

Finish Date : 02 Aug 05

Final Depth of Hole (m) : 9.8

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa							
									40	80	120	160				
									VANE	FIELD	LAB	UC/2				
									PEAK	◆	■	▲				
									REMOLD	◇	□	△				
★ % Fines				● SPT (blows/300mm)												
Moisture Content & SPT N								W <sub>p</sub> %	W <sub>L</sub> %							
X	20	40	60	80	X											
10					End of Hole: 9.75 m, drill refusal, likely on cobbles/boulders.  SPT at 9.75 m: 10 blows for 0 inches. Hole sloughed 10 cm at bottom of hole. No water observed.  at 9.4 m: Piezometer (RST P100 - 030137) installed. Piezometer installed in 25 mm diameter protective PVC. Stick up of PVC is 0.55 m. Protective casing installed at surface. 10-20 Frac Sand.	Slough										
11																
12																
13																
14																
15																



**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

**Deloitte  
& Touche**

# BOREHOLE # BGC05-03

Page 1 of 1

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580868.50E, 6913418.40N

Co-ordinates in NAD 27

Ground Elevation (m) : 1054.1 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 03 Aug 05

Finish Date : 03 Aug 05

Final Depth of Hole (m) : 4.7

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	△ Pocket Pen /2
									REMOLD	◇	□	● SPT (blows/300mm)
									★ % Fines			
									Moisture Content & SPT N			
									W <sub>s</sub> %	X	W <sub>s</sub> %	X
									20	40	60	80
0					Hole drilled for the installation of Piezometer (RST P100 - 030139) at depth 4.0 m. Hole drilled with Hollow Stem Auger to 4.7m. Cuttings appeared consistent with BGC05-01 and BGC05-02, No sampling.	Concrete						
1												
2				UF		Cuttings						
3					End of Hole: 4.7 m at target depth. No sloughing observed. No water observed.	Bentonite						
4					at 4.0 m: Piezometer (RST P100 - 030139) installed. Piezometer installed in 25 mm diameter protective PVC. Stick up of PVC is 0.5 m. Protective casing installed at surface. 10-20 Frac Sand.	Sand						
5												

**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

**BGC**

Calgary, AB

Phone (403) 250 5185

Client:

**Deloitte  
& Touche**



# BOREHOLE # BGC05-04

Page 1 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580864.70E, 6913420.20N

Co-ordinates in NAD 27

Ground Elevation (m) : 1054.1 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 03 Aug 05

Finish Date : 04 Aug 05

Final Depth of Hole (m) : 12.1

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa									
									40	80	120	160						
									VANE	FIELD	LAB	UC/2						
									PEAK	◆	■	▲						
									REMOLD	◇	□	△	Pocket Pen /2					
★ % Fines		● SPT (blows/300mm)																
Moisture Content & SPT N																		
W <sub>p</sub> %	X	20	40	60	80	W <sub>p</sub> %	X											
0					Hole drilled for the installation of Thermistor (BGC05-02). Hole drilled with Hollow Stem Auger to 12.1m. Cuttings appeared consistent with BGC05-01 and BGC05-02, No sampling.	Concrete												
1																		
2				UF		Bentonite and Cement												
3																		
4																		
5																		

(Continued on next page)



**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5165

Client:

**Deloitte  
& Touche**

# BOREHOLE # BGC05-04

Page 2 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580864.70E, 6913420.20N

Co-ordinates in NAD 27

Ground Elevation (m) : 1054.1 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 03 Aug 05

Finish Date : 04 Aug 05

Final Depth of Hole (m) : 12.1

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa				
									40	80	120	160	
									VANE	FIELD	LAB	▲ UC/2	
									PEAK	◆	■	▲ Pocket Pen /2	
									REMOLD	◇	□	△	
★ % Fines			● SPT (blows/300mm)										
Moisture Content & SPT N									W <sub>p</sub> %	W <sub>p</sub> %	W <sub>p</sub> %	W <sub>p</sub> %	
X	20	40	60	80	X								
5													
6													
7													
8				UF		Bentonite and Cement							
9													
10													

(Continued on next page)

BGC

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

Deloitte  
& Touche

# BOREHOLE # BGC05-04

Page 3 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580864.70E, 6913420.20N

Co-ordinates in NAD 27

Ground Elevation (m) : 1054.1 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 03 Aug 05

Finish Date : 04 Aug 05

Final Depth of Hole (m) : 12.1

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	60	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	▲ Pocket Pen /2
									REMOLD	◇	□	● SPT (blows/300mm)
									★ % Fines			
									Moisture Content & SPT N			
									W <sub>p</sub> %	X	W <sub>p</sub> %	X
									20	40	60	80
10												
11												
12				UF								
13					End of Hole: 12.1 m at target depth. No sloughing observed. Protective casing installed at surface.  Thermistor installed at 11.9 m in a 1 inch protective PVC casing. Zero marker on thermistor located 0.09 m above ground surface. Thermistor beads located at 0.41 m, 0.66 m, 0.91 m, 1.91 m, 2.91 m, 3.91 m, 5.91 m, 9.91 m, and 11.91 m below ground surface. Stick-up of PVC protective casing 0.23 m.							
14												
15												



**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5165

Client:

**Deloitte  
& Touche**

# BOREHOLE # BGC05-05

Page 1 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT  
Co-ordinates (m) : 580862.30E, 6913421.70N  
Co-ordinates in NAD 27  
Ground Elevation (m) : 1054.2 AMSL

Drill Designation : CME 75  
Drilling Contractor : Midnight Sun Ltd  
Drill Method : Hollow Stem Auger  
Sampling Method : Standard Penetration Test  
Boring Diameter : 20 cm

Start Date : 04 Aug 05  
Finish Date : 04 Aug 05  
Final Depth of Hole (m) : 10.7  
Logged by : J. Severin  
Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa									
									40	80	120	160						
									VANE	FIELD	LAB	▲ UC/2						
									PEAK	◆	■							
									REMOLD	◇	□	△ Pocket Pen /2						
★ % Fines			● SPT (blows/300mm)															
Moisture Content & SPT N																		
W <sub>p</sub> %	X	20	40	60	80	X												
0					Hole drilled for the installation of 2.75 inch PVC Slope Indicator Casing. Hole drilled with Hollow Stem Auger to a depth of 10.7m. Cuttings appeared consistent with BGC05-01 and BGC05-02, No sampling.	Concrete												
1																		
2																		
3				UF		Bentonite and Cement												
4																		
5																		

(Continued on next page)

# BOREHOLE # BGC05-05

Page 2 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580862.30E, 6913421.70N

Co-ordinates in NAD 27

Ground Elevation (m) : 1054.2 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 04 Aug 05

Finish Date : 04 Aug 05

Final Depth of Hole (m) : 10.7

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	▲ UC/2
									REMOLD	◇	□	△ Pocket Pen /2
★ % Fines		● SPT (blows/300mm)										
Moisture Content & SPT N				W <sub>p</sub> %	W <sub>L</sub> %		W <sub>L</sub> %					
X	20	40	60	80	X							
5												
6												
7												
8				UF								
9												
10												

(Continued on next page)

BGC

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 260 5185

Client:

Deloitte  
& Touche

# BOREHOLE # BGC05-05

Page 3 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580862.30E, 6913421.70N

Co-ordinates in NAD 27

Ground Elevation (m) : 1054.2 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 04 Aug 05

Finish Date : 04 Aug 05

Final Depth of Hole (m) : 10.7

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa				
									40	80	120	160	
									VANE	FIELD	LAB	▲	UC/2
									PEAK	◆	■	△	Pocket Pen /2
									REMOLD	◇	□	●	SPT (blows/300mm)
									★ % Fines				
									Moisture Content & SPT N				
									W <sub>p</sub> %	X	W <sub>p</sub> %	O	W <sub>p</sub> %
									20	40	60	80	X
10													
11					End of Hole: 10.7 m due to drill refusal in sloughing gravel. Hole sloughed at 10.5 m. Water level observed at 9.1 m.  2.75 inch PVC Slope Indicator Casing installed at a depth of 11.1 m, casing sunk into slough with applied weight. A° at 26° (wrt magnetic north). Fall line of slope at 26° (wrt magnetic north). Stick up of 0.73 m.								
12													
13													
14													
15													

# BOREHOLE # BGC05-06

Page 1 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580715.30E, 6913517.50N

Co-ordinates in NAD 27

Ground Elevation (m) : 1050.3 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 05 Aug 05

Finish Date : 05 Aug 05

Final Depth of Hole (m) : 9.8

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa							
									40	80	120	160				
									VANE	FIELD	LAB	▲ UC/2				
									PEAK	◆	■	△ Pocket Pen /2				
									REMOLD	◇	□	● SPT (blows/300mm)				
★ % Fines		Moisture Content & SPT N														
W <sub>p</sub> %	W <sub>p</sub> %		W <sub>L</sub> %													
X	20	40	60	80	X											
0					SAND (FILL) Some Gravel, trace Silt. Medium grained sand, loose, non-plastic, moist, light brown.	Concrete										
1		JMS 13						8	○							
2		JMS 14				Cuttings		9	○							
3		JMS 15		UF	at 2.3 m, gravel up to 15 mm, compact.	Bentonite		14	○							
4		JMS 16				Sand		15	○							
5		JMS 17				Bentonite		22	○							

(Continued on next page)



**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

**Deloitte  
& Touche**

# BOREHOLE # BGC05-06

Page 2 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580715.30E, 6913517.50N

Co-ordinates in NAD 27

Ground Elevation (m) : 1050.3 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 05 Aug 05

Finish Date : 05 Aug 05

Final Depth of Hole (m) : 9.8

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	
									REMOLD	◇	□	△ Pocket Pen /2
★ % Fines		● SPT (blows/300mm)										
Moisture Content & SPT N												
W <sub>p</sub> %	W <sub>L</sub> %		W <sub>U</sub> %									
×	20	40	60	80	×							

5					SILT and SAND (TILL) Some Gravel, trace Clay. Compact, low plasticity to non-plastic, moist, greenish brown.													
6					at 5.5 m, Driller's Note: Easier drilling.													
7																		
8		JMS 18			at 6.1 m, Driller's Note: Material is squeezing and sticking to rods.	Cuttings		10	○									
9																		
10		JMS 19		UF	at 7.7 m, large schist rock fragment in SPT.	Bentonite		22	○									
11																		
12																		
13																		
14		JMS 20			at 9.1 m, some oxidation, dry.	Sand												
15																		
16		JMS 21			Schist Bedrock	Bentonite		15	○									
17								50	○									

(Continued on next page)



**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

**Deloitte  
& Touche**



# BOREHOLE # BGC05-06

Page 3 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580715.30E, 6913517.50N

Co-ordinates in NAD 27

Ground Elevation (m) : 1050.3 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 05 Aug 05

Finish Date : 05 Aug 05

Final Depth of Hole (m) : 9.8

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	
									REMOLD	◇	□	△ Pocket Pen /2
★ % Fines				● SPT (blows/300mm)								
Moisture Content & SPT N												
W <sub>p</sub> %				W <sub>p</sub> %				W <sub>p</sub> %				
X				○				X				
20				40				60	80			

10					End of Hole: 9.8 m, drill refusal in bedrock.									
					No sloughing observed.									
					No water observed.									
					Protective casing installed at surface.									
					at 3.5 m:									
					Piezometer (RST P100 - 030138) installed.									
					Piezometer installed in 25 mm diameter protective PVC.									
					Stick up of PVC is 0.5 m.									
11														
					at 8.8 m:									
					Piezometer (RST P100 - 030136) installed.									
					Piezometer installed in 25 mm diameter protective PVC.									
					Stick up of PVC is 0.5 m.									
12														
13														
14														
15														

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

BGC

Calgary, AB

Phone (403) 250 5185

Client:

Deloitte  
& Touche

# BOREHOLE # BGC05-07

Page 1 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580714.00E, 6913518.10N

Co-ordinates in NAD 27

Ground Elevation (m) : 1050.3 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 06 Aug 05

Finish Date : 06 Aug 05

Final Depth of Hole (m) : 11.1

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	
									REMOLD	◇	□	△ Pocket Pen /2
★ % Fines		● SPT (blows/300mm)										
Moisture Content & SPT N												
W <sub>p</sub> %	X	20	40	60	80	W <sub>p</sub> %	X					

0					Hole drilled for the installation of Thermistor (BGC05-01). Hole drilled with Hollow Stem Auger to 11.4 m. Cuttings appeared consistent with BGC05-06, no sampling.	Concrete									
1															
2															
3				UF											
4															
5															

(Continued on next page)



**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 260 5185

Client:

**Deloitte  
& Touche**

## BOREHOLE # BGC05-07

Page 2 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580714.00E, 6913518.10N

Co-ordinates in NAD 27

Ground Elevation (m) : 1050.3 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 06 Aug 05

Finish Date : 06 Aug 05

Final Depth of Hole (m) : 11.1

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	△ Pocket Pen /2
									REMOLD	◇	□	● SPT (blows/300mm)
★ % Fines												
Moisture Content & SPT N												
W <sub>p</sub> %	W <sub>p</sub> %						W <sub>p</sub> %					
X	20	40	60	80	X							

(Continued on next page)

BGC

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

Deloitte  
& Touche

# BOREHOLE # BGC05-07

Page 3 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580714.00E, 6913518.10N

Co-ordinates in NAD 27

Ground Elevation (m) : 1050.3 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 06 Aug 05

Finish Date : 06 Aug 05

Final Depth of Hole (m) : 11.1

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa				
									40	80	120	160	
									VANE	FIELD	LAB	▲	UC/2
									PEAK	◆	■	△	Pocket Pen /2
									REMOLD	◇	□	△	Pocket Pen /2
★ % Fines			● SPT (blows/300mm)										
Moisture Content & SPT N													
W <sub>p</sub> %	X	20	40	60	80	W <sub>p</sub> %	X						

10																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
----	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Client:

Deloitte  
& Touche

BGC

Calgary, AB

Phone (403) 250 5185

# BOREHOLE # BGC05-08

Page 1 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580712.10E, 6913518.60N

Co-ordinates in NAD 27

Ground Elevation (m) : 1050.4 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 07 Aug 05

Finish Date : 07 Aug 05

Final Depth of Hole (m) : 12.2

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa							
									40	80	120	160				
									VANE	FIELD	LAB	UC/2				
									PEAK	◆	■	▲				
									REMOLD	◇	□	△				
★ % Fines		● SPT (blows/300mm)														
Moisture Content & SPT N																
W <sub>p</sub> %	X	20	40	60	80	W <sub>L</sub> %	X									
0					Hole drilled for the installation of 2.75 inch PVC Slope Indicator Casing. Hole drilled with Hollow Stem Auger to a depth of 12.2 m. Cuttings appeared consistent with BGC05-06 and BGC05-07, no sampling.	Concrete										
1																
2																
3				UF												
4																
5																

(Continued on next page)

Client:

**Deloitte & Touche**

## BOREHOLE # BGC05-08

Page 2 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580712.10E, 6913518.60N

Co-ordinates in NAD 27

Ground Elevation (m) : 1050.4 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 07 Aug 05

Finish Date : 07 Aug 05

Final Depth of Hole (m) : 12.2

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa														
									40	80	120	160											
									VANE	FIELD	LAB	UC/2											
									PEAK	◆	■	△											
									REMOLD	◇	□	Pocket Pen /2											
★ % Fines				● SPT (blows/300mm)																			
Moisture Content & SPT N								W <sub>p</sub> %															
X				20				40				60				80				X			

5																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
---	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

(Continued on next page)

BGC

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

Deloitte  
& Touche

# BOREHOLE # BGC05-08

Page 3 of 3

Project : Instrument Replacement

Project No. : 0257-035-01

Location : Faro, YT

Co-ordinates (m) : 580712.10E, 6913518.60N

Co-ordinates in NAD 27

Ground Elevation (m) : 1050.4 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter : 20 cm

Start Date : 07 Aug 05

Finish Date : 07 Aug 05

Final Depth of Hole (m) : 12.2

Logged by : J. Severin

Reviewed by : G. Ferris

Lithologic Description

Backfill  
Instrument Details

SPT Blows per 300mm

Su - kPa

40 80 120 160

VANE FIELD LAB ▲ UC/2

PEAK ◆ ■

REMOULD ◇ □ △ Pocket Pen /2

★ % Fines ● SPT (blows/300mm)

Moisture Content & SPT N

W<sub>p</sub>% X 20 40 60 80 W<sub>p</sub>% X

Depth (m)

Sample Type

Sample No.

Recovery

Permafrost Condition

Backfill

Instrument Details

10

11

12

13

14

15

UF

Bentonite and Cement

Slough

End of Hole: 12.2 m at target depth.

Hole sloughed at 10.5 m.

Depth to water 9.1 m.

2.75 inch PVC Slope Indicator Casing installed at a depth of 12.2 m as casing sunk into slough with applied weight. A<sub>0</sub> was not measured but is approximately coincident with the fall line of the slope. Stick up 1.52 m.

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

BGC

Calgary, AB

Phone (403) 260 5185

Client:

Deloitte  
& Touche

# BOREHOLE # BGC05-09

Page 1 of 3

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT  
Co-ordinates (m) : 579824.40E, 6914048.60N  
Co-ordinates in NAD 27  
Ground Elevation (m) : 1032.8 AMSL

Drill Designation : CME 75  
Drilling Contractor : Midnight Sun Ltd  
Drill Method : Hollow Stem Auger  
Sampling Method : Standard Penetration Test  
Boring Diameter :

Start Date : 08 Aug 05  
Finish Date : 08 Aug 05  
Final Depth of Hole (m) : 10  
Logged by : J. Severin  
Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa					
									40	80	120	160		
									VANE	FIELD	LAB	UC/2		
									PEAK	◆	■	▲		
									REMOLD	◇	□	△		
★ % Fines		● SPT (blows/300mm)												
Moisture Content & SPT N														
W <sub>p</sub> %	W <sub>L</sub> %				W <sub>L</sub> %									
X	20	40	60	80	X									
0					SAND (FILL) Some Cobbles, some Gravel. Compact, non-plastic, moist, grey brown.									
1		JMS 23			SILT and SAND (FILL) Some Gravel, trace Clay. Dark brown, minor oxidation.			14	○					
2		JMS 24 A&B			SAND and SILT (FILL) Some Gravel, trace Clay. Compact to Loose, low plasticity, reddish brown, minor oxidation.			14	○					
		JMS 25		UF	at 2.9 m, clay content increases slightly. at 3.1 m, organic material present mixed with Sand. Non-plastic, dark brown, musty smell, fibrous. Possible Original Ground Surface			9	○					
3		JMS 26 A&B			SAND and SILT (TILL) Some Gravel, trace Clay. Loose, low plasticity, reddish brown, minor oxidation.			8	○				○	
4														
5		JMS 27			SAND and GRAVEL			10	○					

(Continued on next page)



# BOREHOLE # BGC05-09

Page 2 of 3

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 579824.40E, 6914048.60N

Co-ordinates in NAD 27

Ground Elevation (m) : 1032.8 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter :

Start Date : 08 Aug 05

Finish Date : 08 Aug 05

Final Depth of Hole (m) : 10

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa							
									40		80		120		160	
									VANE	FIELD	LAB	▲	UC/2	▲	UC/2	
									PEAK	◆	■	△	Pocket Pen /2	△	Pocket Pen /2	
									REMOLD	◇	□	●	SPT (blows/300mm)	●	SPT (blows/300mm)	
									Moisture Content & SPT N							
									W <sub>p</sub> %	Moisture Content & SPT N		W <sub>p</sub> %	Moisture Content & SPT N			
									X	20	40	60	80	X		

5					trace Silt. Compact, non-plastic, moist, light brown, well-sorted.														
6																			
7																			
8																			
9																			

(Continued on next page)

**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

**BGC**

Calgary, AB

Phone (403) 250 5185

Client:

**Deloitte  
& Touche**

# BOREHOLE # BGC05-09

Page 3 of 3

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 579824.40E, 6914048.60N

Co-ordinates in NAD 27

Ground Elevation (m) : 1032.8 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter :



Start Date : 08 Aug 05

Finish Date : 08 Aug 05

Final Depth of Hole (m) : 10

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	
									REMOLD	◇	□	△ Pocket Pen /2
★ % Fines				● SPT (blows/300mm)								
Moisture Content & SPT N												
W <sub>p</sub> %	W <sub>L</sub> %				W <sub>L</sub> %							
X	20	40	60	80	X							
10		JMS 31			Biotite Schist  Top 1 inch weathered surface in contact with SAND and SILT.   							

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Client:

Deloitte  
& Touche

BGC

Calgary, AB

Phone (403) 250 5185



7505 - 40 Street SE  
Calgary, Alberta T2C 2H5  
Telephone: (403) 235-8880

## Aggregate Analysis Report

Sieve Size (mm)	% Passing
200	
150	
100	
80	
50	
40	100.0
25	69.7
20	60.5
12.5	58.2
10	58.2
5	51.9
2.5	42.3
1.25	32.1
0.63	20.8
0.315	16.1
0.16	12.1
0.08	9.5

**Client** BGC Engineering Inc.

**Address** Suite 1605, 840 - 7th Avenue S.W.  
Calgary, Alberta T2P 3G2

**Attention** Mr. Jordan Severin

**Project** BGC # 0257-037-01

**Job #** 55-099-02-1

**Date Sampled** Rec'd Oct.3/05


**By** CBL

**Date Tested** Oct.6/05

**By** ML

**Aggregate Type** Sand & Gravel

**Comments** JMS-29  
Moisture Content = 4.9%



# BOREHOLE # BGC05-10

Page 1 of 2

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT  
Co-ordinates (m) : 580245.80E, 6913763.70N  
Co-ordinates in NAD 27  
Ground Elevation (m) : 1049.1 AMSL

Drill Designation : CME 75  
Drilling Contractor : Midnight Sun Ltd  
Drill Method : Hollow Stem Auger  
Sampling Method : Standard Penetration Test  
Boring Diameter :

Start Date : 08 Aug 05  
Finish Date : 08 Aug 05  
Final Depth of Hole (m) : 8.6  
Logged by : J. Severin  
Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	△ Pocket Pen /2
									REMOLD	◇	□	● SPT (blows/300mm)
★ % Fines				Moisture Content & SPT N								
W <sub>p</sub> %	X		20	40	60	80	W <sub>p</sub> %	X				

0					SILT and SAND (FILL/SPOIL) Some Gravel. Gravel is angular, compact, non-plastic, moist, grey brown, slight oxidation.														
1		JMS 32						10	○										
					at 1.2 m, Driller's Notes: Chunky / Bony Drilling. at 1.3 m, sandy cuttings.														
2		JMS 33						13	○										
					at 2.1 m, cuttings become dark brown.														
		JMS 34		UF	SILT (FILL) Some Sand, some Gravel, trace Clay. Compact, non-plastic, moist, dark brown, red and white streaks, some oxidation, musty smell, organic particles throughout sample JMS 34 (mostly 6 inches from base).			15	○										
3		JMS 35			at 3.1 m, sporadic oxidation, few organics present. at 3.4 m, some organics present. Possible Original Ground Surface			21	○										
					SILT (TILL) Some Sand, some Gravel. Compact to dense, low plasticity, moist, green brown, some oxidation, organic material present.														
4		JMS 36						45	○										

(Continued on next page)

# BOREHOLE # BGC05-10

Page 2 of 2

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 580245.80E, 6913763.70N

Co-ordinates in NAD 27

Ground Elevation (m) : 1049.1 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter :

Start Date : 08 Aug 05

Finish Date : 08 Aug 05

Final Depth of Hole (m) : 8.6

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa						
									40	80	120	160			
									VANE	FIELD	LAB	▲	UC/2		
									PEAK	◆	■				
									REMOLD	◇	□	△	Pocket Pen /2		
									★ % Fines	● SPT (blows/300mm)					
									Moisture Content & SPT N						
									W <sub>p</sub> %	W <sub>n</sub> %			W <sub>n</sub> %		
									X	20	40	60	80	X	
5															
6															
										</					

BGC

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 260 5165

Client:

Deloitte  
& Touche

# BOREHOLE # BGC05-11

Page 1 of 3

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 581001.40E, 6913375.90N

Co-ordinates in NAD 27

Ground Elevation (m) : 1051.6 AMSL

Drill Designation : CMĒ 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter :

Start Date : 09 Aug 05

Finish Date : 09 Aug 05

Final Depth of Hole (m) : 9.7

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa							
									40	80	120	160				
									VANE	FIELD	LAB	▲ UC/2				
									PEAK	◆	■	▲ Pocket Pen /2				
									REMOLD	◇	□	△ SPT (blows/300mm)				
★ % Fines				● SPT (blows/300mm)												
Moisture Content & SPT N																
W <sub>p</sub> % X — 20 — 40 — 60 — 80 — W <sub>p</sub> % X																
0					SAND (FILL / SPOIL) Some Silt, some Gravel, some Cobbles. Dense, moist, light brown.											
1		JMS 39						24	○							
2		JMS 40			at 1.5 m, some oxidation and organic materials, compact.			12	○							
3		JMS 41		UF	at 2.3 m, fines content increases, some oxidation.			12	○							
4		JMS 42			SILT and SAND (FILL) Some Gravel. Compact, low plasticity, moist, brown.			10	○							
5		JMS 43						17	○							

(Continued on next page)



**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

**Deloitte  
& Touche**

# BOREHOLE # BGC05-11

Page 2 of 3

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 581001.40E, 6913375.90N

Co-ordinates in NAD 27

Ground Elevation (m) : 1051.6 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter :

Start Date : 09 Aug 05

Finish Date : 09 Aug 05

Final Depth of Hole (m) : 9.7

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	△ Pocket Pen /2
									REMOLD	◇	□	● SPT (blows/300mm)
									★ % Fines			
									Moisture Content & SPT N			
									W <sub>p</sub> %	W <sub>n</sub> %	W <sub>n</sub> %	W <sub>n</sub> %
									20	40	60	80
5												
6					at 5.8 m, organic material in cuttings, dark brown colour, easy drilling. Possible Original Ground Surface SAND and SILT (TILL) Some Gravel. Compact, low plasticity, moist, light brown, some oxidation.			19	○			
7												
8					at 7.4 m, wet. Phyllite / Schist Dark grey, weak, slightly weathered (W 5/6), some oxidation, distinct foliation across SPT sample. at 8.5 m, rock becomes more competent.			20	○			
9												
10					End of Hole: 9.7 m, auger refusal in bedrock.			50	○			

(Continued on next page)



**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

**Deloitte  
& Touche**

# BOREHOLE # BGC05-11

Page 3 of 3

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 581001.40E, 6913375.90N

Co-ordinates in NAD 27

Ground Elevation (m) : 1051.6 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter :

Start Date : 09 Aug 05

Finish Date : 09 Aug 05

Final Depth of Hole (m) : 9.7

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa				
									40	80	120	160	
									VANE	FIELD	LAB	▲	UC/2
									PEAK	◆	■	△	Pocket Pen./2
									REMOLD	◇	□	●	SPT (blows/300mm)
★ % Fines													
Moisture Content & SPT N													
W <sub>p</sub> %					W <sub>p</sub> %								
X	20	40	60	80	X								
10					Depth to water 7.4 m. Sloughing not observed due to Hollow Stem Auger.								
11													
12													
13													
14													
15													

BGC

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

Deloitte  
& Touche



# BOREHOLE # BGC05-12

Page 1 of 2

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 581467.20E, 6913201.00N

Co-ordinates in NAD 27

Ground Elevation (m) : 1053.2 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter :

Start Date : 09 Aug 05

Finish Date : 09 Aug 05

Final Depth of Hole (m) : 5.7

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa							
									40		80		120		160	
									VANE	FIELD	LAB	▲	UC/2			
									PEAK	◆	■	△	Pocket Pen /2			
									REMOLD	◇	□	●	SPT (blows/300mm)			
★ % Fines								Moisture Content & SPT N								
W <sub>p</sub> %				W <sub>u</sub> %				W <sub>u</sub> %								
X				O				X								
20				40				60				80				

0					SAND and SILT (TILL) Some Gravel, trace Clay. Dense, low plasticity, moist to wet, dark brown, well graded to gap graded, well rounded gravel clasts.														
1		JMS 47			at 0.7 m, Gravel, trace Sand.			38											
2		JMS 48			at 1.8 m, silt content increases, not as moist.			20											
3		JMS 49		UF	at 2.5 m, dry to moist.			35											
4		JMS 50			at 3.0 m, faster drilling, wet.			29											
5																			

(Continued on next page)

BGC

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

Deloitte  
& Touche

# BOREHOLE # BGC05-12

Page 2 of 2

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 581467.20E, 6913201.00N

Co-ordinates in NAD 27

Ground Elevation (m) : 1053.2 AMSL

Drill Designation : CMÉ 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter :


Start Date : 09 Aug 05

Finish Date : 09 Aug 05

Final Depth of Hole (m) : 5.7

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa							
									40	80	120	160				
									VANE	FIELD	LAB	▲ UC/2				
									PEAK	◆	■	△ Pocket Pen /2				
									REMOLD	◇	□	● SPT (blows/300mm)				
★ % Fines				Moisture Content & SPT N												
W <sub>p</sub> %	X		20		40		60		80		W <sub>L</sub> %	X				
5				UF												
6					End of Hole: 5.7 m, auger refusal on cobbles/boulders or bedrock.  Depth to water 3.0 m. Sloughing not observed due to Hollow Stem Auger.											
7																
8																
9																
10																

**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Client:

**Deloitte  
& Touche**

**BGC**

Calgary, AB

Phone (403) 250 5185

# BOREHOLE # BGC05-13

Page 1 of 2

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 581627.40E, 6913145.80N

Co-ordinates in NAD 27

Ground Elevation (m) : 1052.4 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter :

Start Date : 09 Aug 05

Finish Date : 09 Aug 05

Final Depth of Hole (m) : 6.5

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	△ Pocket Pen /2
									REMOLD	◇	□	● SPT (blows/300mm)
★ % Fines				Moisture Content & SPT N								
W <sub>p</sub> %	X		20	40	60	80	W <sub>L</sub> %	X				

0					SAND (FILL) Silty, some Gravel, some Cobbles. Dense to compact, non-plastic, moist, light brown.														
1		JMS 51						27	○										
2		JMS 53 JMS 52						11	○○										
		JMS 54		UF	at 2.3 m, some oxidation.			10	○										
3		JMS 55			Possible Original Ground Surface SILT (TILL) Sandy, some Gravel. Loose, low plasticity, moist, dark brown, some oxidation, few organics present.			9	○										
4		JMS 56			at 4.6 m, wet.			8	○										

(Continued on next page)

# BOREHOLE # BGC05-13

Page 2 of 2

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 581627.40E, 6913145.80N

Co-ordinates in NAD 27

Ground Elevation (m) : 1052.4 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : Hollow Stem Auger

Sampling Method : Standard Penetration Test

Boring Diameter :

Start Date : 09 Aug 05

Finish Date : 09 Aug 05

Final Depth of Hole (m) : 6.5

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	△ Pocket Pen /2
									REMOLD	◇	□	● SPT (blows/300mm)
									★ % Fines			
									Moisture Content & SPT N			
									W <sub>p</sub> %	W <sub>p</sub> %	W <sub>p</sub> %	W <sub>p</sub> %
									X	20	40	60
5												
6				UF								
		JMS 57			SAND Some Silt. Loose, non-cohesive, wet, grey brown, massive, well sorted. Phyllite (BEDROCK)			80	○			
					Weak, weathered (W5), no oxidation. End of Hole: 6.48m, auger refusal in bedrock.							
7					Depth to water 4.6 m. Sloughing not observed due to Hollow Stem Auger.							
8												
9												
10												

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Client:

Deloitte  
& Touche

BGC

Calgary, AB

Phone (403) 250 5185

# BOREHOLE # BGC05-14

Page 1 of 1

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 583072.10E, 6912389.00N

Co-ordinates in NAD 27

Ground Elevation (m) : 1063.9 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : CRRL / Solid Stem Auger

Sampling Method : CRRL / Solid Stem Auger

Boring Diameter :


Start Date : 10 Aug 05

Finish Date : 10 Aug 05

Final Depth of Hole (m) : 4.3

Logged by : J. Severin

Reviewed by : G. Ferris



BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Client:

Deloitte  
& Touche

BGC

Calgary, AB

Phone (403) 250 5185




7505 - 40 Street SE  
Calgary, Alberta T2C 2H5  
Telephone: (403) 236-8880

## Grain Size Distribution

Project	BGC # 0257-037-01	Test Hole #	JMS-60	
Client	BGC Engineering Inc.	Depth		
Job #	55-099-02-1	Description	SAND, some silt, some gravel, trace of clay	
Date Sampled	Rec'd Oct.3/05			
Date Tested	Oct.5/05			
Remarks				
ML				
	Gravel	16.7%	Natural Water Content	9.9%
	Sand	55.9%	Liquid Limit	24
	Silt	20.2%	Plastic Limit	23
	Clay	7.2%	Plasticity Index	1
			Specific Gravity	2.68

Gravel		Sand			Silt	Clay
Coarse	Fine	Coarse	Medium	Fine		



## BOREHOLE # BGC05-15

Page 1 of 1

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 582856.10E, 6912526.10N

Co-ordinates in NAD 27

Ground Elevation (m) : 1063.5 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : CRRL / Solid Stem Auger

Sampling Method : CRRL / Solid Stem Auger

Boring Diameter :


Start Date : 11 Aug 05

Finish Date : 11 Aug 05

Final Depth of Hole (m) : 4

Logged by : J. Severin

Reviewed by : G. Ferris



BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

BGC

Calgary, AB

Phone (403) 250 5185

Client:

Deloitte  
& Touche

# BOREHOLE # BGC05-16

Page 1 of 2


Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT  
Co-ordinates (m) : 581714.00E, 6912992.60N  
Co-ordinates in NAD 27  
Ground Elevation (m) : 1064.2 AMSL

Drill Designation : CME 75  
Drilling Contractor : Midnight Sun Ltd  
Drill Method : CRRL / Solid Stem Auger  
Sampling Method : CRRL / Solid Stem Auger  
Boring Diameter :

Start Date : 11 Aug 05  
Finish Date : 11 Aug 05  
Final Depth of Hole (m) : 8.7  
Logged by : J. Severin  
Reviewed by : G. Ferris



(Continued on next page)

**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

**BGC**

Calgary, AB

Phone (403) 250 5185

Client:

**Deloitte  
& Touche**



# BOREHOLE # BGC05-16

Page 2 of 2

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 581714.00E, 6912992.60N

Co-ordinates in NAD 27

Ground Elevation (m) : 1064.2 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : CRRL / Solid Stem Auger

Sampling Method : CRRL / Solid Stem Auger

Boring Diameter :

Start Date : 11 Aug 05

Finish Date : 11 Aug 05

Final Depth of Hole (m) : 8.7

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	UC/2
									PEAK	◆	■	▲
									REMO	◇	□	△
									★ % Fines			● SPT (blows/300mm)
									Moisture Content & SPT N			
									W <sub>L</sub> %	W <sub>P</sub> %	W <sub>L</sub> %	W <sub>P</sub> %
									X	—	—	X
5												
6												
7		JMS 81		UF			Cuttings					
8												
8.5					at 8.5 m, silt-rich, looks like decomposed rock.							
8.69		JMS 82										
9					End of Hole: 8.69 m, auger refusal in possible bedrock.							
					No water observed.							
					No sloughing observed.							
10												

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Client:

Deloitte  
& Touche

BGC

Calgary, AB

Phone (403) 250 5185

# BOREHOLE # BGC05-17

Page 1 of 2


Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT  
Co-ordinates (m) : 581288.30E, 6913174.20N  
Co-ordinates in NAD 27  
Ground Elevation (m) : 1065.2 AMSL

Drill Designation : CME 75  
Drilling Contractor : Midnight Sun Ltd  
Drill Method : CRRL / Solid Stem Auger  
Sampling Method : CRRL / Solid Stem Auger  
Boring Diameter :

Start Date : 12 Aug 05  
Finish Date : 12 Aug 05  
Final Depth of Hole (m) : 5.6  
Logged by : J. Severin  
Reviewed by : G. Ferris



(Continued on next page)

**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Client:

**Deloitte  
& Touche**

**BGC**

Calgary, AB

Phone (403) 250 5185

# BOREHOLE # BGC05-17

Page 2 of 2

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 581288.30E, 6913174.20N

Co-ordinates in NAD 27

Ground Elevation (m) : 1065.2 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : CRRL / Solid Stem Auger

Sampling Method : CRRL / Solid Stem Auger

Boring Diameter :

Start Date : 12 Aug 05

Finish Date : 12 Aug 05

Final Depth of Hole (m) : 5.6

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	△ Pocket Pen /2
									REMOLD	◇	□	● SPT (blows/300mm)
★ % Fines				Moisture Content & SPT N								
W <sub>p</sub> %	X		20	40	60	80	W <sub>p</sub> %	X				

5	<div><div></div><div>JMS 80</div></div>	<div><div></div><div>JMS 81</div></div>	<div><div></div></div>	UF	PHYLLITE (BEDROCK)  Fine-grained, greenish grey colour, weak, slightly weathered (W5), no visible fabric. at 5.4 m, switched to Solid Stem Auger.	<div><div></div></div>		<div><div></div><div></div></div>	<div><div></div><div></div></div>
6					End of Hole: 5.64m, auger refusal in bedrock.  No water observed. Hole sloughes below 3.0 m.				
7									
8									
9									

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Client:

Deloitte  
& Touche

BGC

Calgary, AB

Phone (403) 250 5185




7505 - 40 Street SE  
Calgary, Alberta T2C 2H5  
Telephone: (403) 236-8880

## Grain Size Distribution

Project	BGC # 0257-037-01	Test Hole #	JMS-88
Client	BGC Engineering Inc.	Depth	
Job #	55-099-02-1	Description	SAND, some silt, some gravel, some clay
Date Sampled	Rec'd Oct.2/05		
Date Tested	Oct.5/05		
Remarks		Gravel	13.2%
		Sand	60.8%
		Silt	15.1%
		Clay	11.1%
		Natural Water Content	10.5%
		Liquid Limit	25
		Plastic Limit	20
		Plasticity Index	5
		Specific Gravity	2.68

CL - ML

Gravel		Sand			Silt	Clay
Coarse	Fine	Coarse	Medium	Fine		



# BOREHOLE # BGC05-18

Page 1 of 2

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 580808.00E, 6913361.80N

Co-ordinates in NAD 27

Ground Elevation (m) : 1067.4 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : CRRL / Solid Stem Auger

Sampling Method : CRRL / Solid Stem Auger

Boring Diameter :


Start Date : 12 Aug 05

Finish Date : 12 Aug 05

Final Depth of Hole (m) : 6.3

Logged by : J. Severin

Reviewed by : G. Ferris



(Continued on next page)

BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Client:

Deloitte  
& Touche

BGC

Calgary, AB

Phone (403) 250 5185

# BOREHOLE # BGC05-18

Page 2 of 2

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT  
Co-ordinates (m) : 580808.00E, 6913361.80N  
Co-ordinates in NAD 27  
Ground Elevation (m) : 1067.4 AMSL

Drill Designation : CME 75  
Drilling Contractor : Midnight Sun Ltd  
Drill Method : CRRL / Solid Stem Auger  
Sampling Method : CRRL / Solid Stem Auger  
Boring Diameter :

Start Date : 12 Aug 05  
Finish Date : 12 Aug 05  
Final Depth of Hole (m) : 6.3  
Logged by : J. Severin  
Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa			
									40	80	120	160
									VANE	FIELD	LAB	▲ UC/2
									PEAK	◆	■	
									REMOLD	◇	□	△ Pocket Pen /2
★ % Fines			● SPT (blows/300mm)									
Moisture Content & SPT N									W <sub>p</sub> %			
									X			
									20			
									40			
									60			
									80			
									X			

5																			
6				UF			Cuttings												
7					End of Hole: 6.3 m, auger refusal, possible bedrock surface.  Depth to water 3 m. Hole sloughed below 3.4 m.														
8																			
9																			
10																			

**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

**BGC**

Calgary, AB

Phone (403) 250 5185

Client:

**Deloitte  
& Touche**



7505 - 40 Street SE  
Calgary, Alberta T2C 2H5  
Telephone: (403) 236-8880

## Grain Size Distribution

Project BGC # 0257-037-01  
Client BGC Engineering Inc.  
Job # 55-099-02-1  
Date Sampled Rec'd Oct.3/05  
Date Tested Oct.11/05

Test Hole # JMS-96  
Depth

Description Silty SAND, some gravel, trace of clay


Remarks

ML

Gravel 15.3%  
Sand 51.4%  
Silt 23.7%  
Clay 9.6%

Natural Water Content 28.2%  
Liquid Limit 40  
Plastic Limit 32  
Plasticity Index 8  
Specific Gravity 2.66

Gravel		Sand			Silt	Clay
Coarse	Fine	Coarse	Medium	Fine		



# BOREHOLE # BGC05-19

Page 1 of 1

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 579662.90E, 6913972.00N

Co-ordinates in NAD 27

Ground Elevation (m) : 1049.0 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : CRRL / Solid Stem Auger

Sampling Method : CRRL / Solid Stem Auger

Boring Diameter :


Start Date : 16 Aug 05

Finish Date : 16 Aug 05

Final Depth of Hole (m) : 3

Logged by : J. Severin

Reviewed by : G. Ferris







7505 - 40 Street SE  
Calgary, Alberta T2C 2H5  
Telephone: (403) 236-8880

## Grain Size Distribution

Project BGC # 0257-037-01  
Client BGC Engineering Inc.  
Job # 55-099-02-1  
Date Sampled Rec'd Oct.3/05  
Date Tested Oct.11/05


Test Hole # JMS-95B  
Depth

Description SILT & SAND, some clay, trace of gravel

Remarks	Gravel	0.6%	Natural Water Content	40.6%
	Sand	41.4%	Liquid Limit	49
	Silt	44.8%	Plastic Limit	41
	Clay	13.2%	Plasticity Index	8
			Specific Gravity	2.63

ML

Gravel		Sand			Silt	Clay
Coarse	Fine	Coarse	Medium	Fine		



# BOREHOLE # BGC05-20

Page 1 of 2


Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT  
Co-ordinates (m) : 579300.10E, 6914219.60N  
Co-ordinates in NAD 27  
Ground Elevation (m) : 1047.1 AMSL

Drill Designation : CME 75  
Drilling Contractor : Midnight Sun Ltd  
Drill Method : CRRL / Solid Stem Auger  
Sampling Method : CRRL / Solid Stem Auger  
Boring Diameter :

Start Date : 17 Aug 05  
Finish Date : 17 Aug 05  
Final Depth of Hole (m) : 6.8  
Logged by : J. Severin  
Reviewed by : G. Ferris



(Continued on next page)

# BOREHOLE # BGC05-20

Page 2 of 2

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 579300.10E, 6914219.60N

Co-ordinates in NAD 27

Ground Elevation (m) : 1047.1 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : CRRL / Solid Stem Auger

Sampling Method : CRRL / Solid Stem Auger

Boring Diameter :

Start Date : 17 Aug 05

Finish Date : 17 Aug 05

Final Depth of Hole (m) : 6.8

Logged by : J. Severin

Reviewed by : G. Ferris

Depth (m)	Sample Type	Sample No.	Recovery	Permafrost Condition	Lithologic Description	Backfill	Instrument Details	SPT Blows per 300mm	Su - kPa											
									40	80	120	160								
									VANE	FIELD	LAB	▲	UC/2							
									PEAK	◆	■	△	Pocket Pen /2							
									REMOLD	◇	□	●	SPT (blows/300mm)							
★ % Fines					Moisture Content & SPT N															
W <sub>p</sub> %	W <sub>w</sub> %				W <sub>w</sub> %	W <sub>w</sub> %														
X	20	40	60	80	X															
5	<div><div></div><div></div><div></div></div>	JMS 107 JMS 106	<div><div></div><div></div><div></div></div>		Low plasticity, wet, grey brown.															
	<div><div></div><div></div><div></div></div>	JMS 108	<div><div></div><div></div><div></div></div>	UF	Gravel 12% Sand 56% Silt 20% Clay 12%	Cuttings	<div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div></div>													



**BGC ENGINEERING INC.**

AN APPLIED EARTH SCIENCES COMPANY

Calgary, AB

Phone (403) 250 5185

Client:

**Deloitte  
& Touche**



7505 - 40 Street SE  
Calgary, Alberta T2C 2H5  
Telephone: (403) 236-6880


## Grain Size Distribution

<b>Project</b>	BGC # 0257-037-01	<b>Test Hole #</b>	JMS-101
<b>Client</b>	BGC Engineering Inc.	<b>Depth</b>	
<b>Job #</b>	55-099-02-1	<b>Description</b>	Silty SAND, some clay, trace of gravel
<b>Date Sampled</b>	Rec'd Oct.3/05		
<b>Date Tested</b>	Oct.11/05		
<b>Remarks</b>			
MH - ML			

<b>Gravel</b>	0.4%	<b>Natural Water Content</b>	70.4%
<b>Sand</b>	49.2%	<b>Liquid Limit</b>	51
<b>Silt</b>	39.2%	<b>Plastic Limit</b>	46
<b>Clay</b>	11.2%	<b>Plasticity Index</b>	5
		<b>Specific Gravity</b>	2.63

Gravel		Sand			Silt	Clay
Coarse	Fine	Coarse	Medium	Fine		





7505 - 40 Street SE  
Calgary, Alberta T2C 2H5  
Telephone: (403) 236-8880

## Grain Size Distribution


<b>Project</b>	BGC # 0257-037-01	<b>Test Hole #</b>	JMS-108
<b>Client</b>	BGC Engineering Inc.	<b>Depth</b>	
<b>Job #</b>	55-099-02-1	<b>Description</b>	SAND, some silt, some gravel, some clay
<b>Date Sampled</b>	Rec'd Oct.3/05		
<b>Date Tested</b>	Oct.5/05		

<b>Remarks</b>	<b>Gravel</b>	12.4%	<b>Natural Water Content</b>	10.4%
	<b>Sand</b>	56.1%	<b>Liquid Limit</b>	18
	<b>Silt</b>	19.5%	<b>Plastic Limit</b>	17
	<b>Clay</b>	12.0%	<b>Plasticity Index</b>	1
			<b>Specific Gravity</b>	2.68

ML

Gravel		Sand			Silt	Clay
Coarse	Fine	Coarse	Medium	Fine		



# BOREHOLE # BGC05-21

Page 1 of 2


Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT  
Co-ordinates (m) : 579246.20E, 6914517.30N  
Co-ordinates in NAD 27  
Ground Elevation (m) : 1026.7 AMSL

Drill Designation : CME 75  
Drilling Contractor : Midnight Sun Ltd  
Drill Method : CRRL / Solid Stem Auger  
Sampling Method : CRRL / Solid Stem Auger  
Boring Diameter :

Start Date : 18 Aug 05  
Finish Date : 18 Aug 05  
Final Depth of Hole (m) : 8.9  
Logged by : J. Severin  
Reviewed by : G. Ferris



(Continued on next page)

Client:

**Deloitte  
& Touche**

# BOREHOLE # BGC05-21

Page 2 of 2


Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT  
Co-ordinates (m) : 579246.20E, 6914517.30N  
Co-ordinates in NAD 27  
Ground Elevation (m) : 1026.7 AMSL

Drill Designation : CME 75  
Drilling Contractor : Midnight Sun Ltd  
Drill Method : CRRL / Solid Stem Auger  
Sampling Method : CRRL / Solid Stem Auger  
Boring Diameter :

Start Date : 18 Aug 05  
Finish Date : 18 Aug 05  
Final Depth of Hole (m) : 8.9  
Logged by : J. Severin  
Reviewed by : G. Ferris





7505 - 40 Street SE  
Calgary, Alberta T2C 2H5  
Telephone: (403) 236-8880

## Grain Size Distribution

Project BGC # 0257-037-01  
Client BGC Engineering Inc.  
Job # 55-089-02-1  
Date Sampled Rec'd Oct.3/05  
Date Tested Oct.11/05

Test Hole # JMS-123  
Depth

Description SILT, some clay, some sand


Remarks

ML

Gravel 0.0%  
Sand 15.0%  
Silt 65.3%  
Clay 19.7%

Natural Water Content 29.1%  
Liquid Limit 30  
Plastic Limit 25  
Plasticity Index 5  
Specific Gravity 2.63

Gravel		Sand			Silt	Clay
Coarse	Fine	Coarse	Medium	Fine		







7505 - 40 Street SE  
Calgary, Alberta T2C 2H5  
Telephone: (403) 236-8880

## Aggregate Analysis Report

Sieve Size (mm)	% Passing
200	
150	
100	
80	
50	
40	
25	100.0
20	94.0
12.5	83.0
10	81.4
5	68.2
2.5	56.6
1.25	41.1
0.63	23.5
0.315	16.7
0.16	12.5
0.08	9.4

**Client** BGC Engineering Inc.

**Address** Suite 1605, 840 - 7th Avenue S.W.  
Calgary, Alberta T2P 3G2

**Attention** Mr. Jordan Severin

**Project** BGC # 0257-037-01

**Job #** 55-099-02-1

**Date Sampled** Rec'd Oct.3/05

**By** CBL


**Date Tested** Oct.8/05

**By** ML

**Aggregate Type** Sand & Gravel

**Comments** JMS-127

Moisture Content = 8.4%



# BOREHOLE # BGC05-22

Page 1 of 1

Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT

Co-ordinates (m) : 578921.00E, 6914612.70N

Co-ordinates in NAD 27

Ground Elevation (m) : 1045.6 AMSL

Drill Designation : CME 75

Drilling Contractor : Midnight Sun Ltd

Drill Method : CRRL / Solid Stem Auger

Sampling Method : CRRL / Solid Stem Auger

Boring Diameter :


Start Date : 19 Aug 05

Finish Date : 19 Aug 05

Final Depth of Hole (m) : 3.3

Logged by : J. Severin

Reviewed by : G. Ferris



BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Client:

Deloitte  
& Touche

BGC

Calgary, AB

Phone (403) 260 6186

# BOREHOLE # BGC05-23

Page 1 of 1


Project : Rose Creek Diversion Canal Investigation

Project No. : 0257-037-01

Location : Faro, YT  
Co-ordinates (m) : 578561.90E, 6914958.40N  
Co-ordinates in NAD 27  
Ground Elevation (m) : 1021.5 AMSL

Drill Designation : CME 75  
Drilling Contractor : Midnight Sun Ltd  
Drill Method : CRRL / Solid Stem Auger  
Sampling Method : CRRL / Solid Stem Auger  
Boring Diameter :

Start Date : 19 Aug 05  
Finish Date : 19 Aug 05  
Final Depth of Hole (m) : 4.3  
Logged by : J. Severin  
Reviewed by : G. Ferris



BGC ENGINEERING INC.

AN APPLIED EARTH SCIENCES COMPANY

Client:

Deloitte  
& Touche

BGC

Calgary, AB

Phone (403) 250 5185