

SCHEDULE A, PART I  
MONITORING STATIONS

***Faro Mine Site:***

<u>Station</u>	<u>Location</u>
X2	North Fork of Rose Creek at access road
X3	Pumphouse pond
X4	Intermediate pond at spillway
X5	Cross Valley pond surface outflow
X5P	Cross Valley pond at spillway
X11	Cross Valley Dam North Seep
X12	Cross Valley Dam South Seep
Weir 3	Cross Valley Dam Central Seep
X13	Cross Valley Dam Combined Seepage
X14	Rose Creek after mixing downstream of the diversion canal confluence
X22b	Faro Main Pit at Pumping Barge
X23	Old Faro Creek channel near the toe of the main (southwest) rock dumps.
X26	Faro Zone II Pit Pumped Discharge
R1	South Fork Rose Creek upstream of pumphouse pond
R2	Rose Creek downstream of mixing zone
R3	Rose Creek mid length
R4	Rose Creek just above Anvil Creek
R5	Anvil Creek just below the confluence of Rose Creek
R6	Anvil Creek immediately upstream of Rose Creek
Faro Cr	Outlet of Faro Creek Diversion
R7	North Fork of Rose Creek upstream of the confluence with the Faro Creek Diversion
R8	North Fork of Rose Creek, 100 m downstream of confluence with Faro Creek Diversion
R9	North Fork of Rose Creek, adjacent to Zone 2 Rock Dumps
R10	North Fork of Rose Creek, downstream of Zone 2 Rock Dumps and 100 metres downstream of R9
X16	Downstream of Rose Creek Tailings Facility
X17	Downstream of Rose Creek Tailings Facility
X18	Downstream of Rose Creek Tailings Facility
X21-96	Rose Creek Tailings Facility
X24-96	Rose Creek Tailings Facility
X25-96	Rose Creek Tailings Facility
P01-01 to 11	Rose Creek Tailings Facility
TH86-26	Upstream of Rose Creek Tailings Facility
BH1	Zone 2 Rock Dumps
BH2	Zone 2 Rock Dumps
BH4	Zone 2 Rock Dumps
BH12	Northeast Rock Dumps
BH13	Northeast Rock Dumps
BH14	Northeast Rock Dumps
P96-6	Main/Intermediate Rock Dumps
P96-7	Main/Intermediate Rock Dumps

***Faro Mine Site (continued):***

<u>Station</u>	<u>Location</u>
P96-8	Main/Intermediate Rock Dumps
S1	Main/Intermediate Rock Dumps
S2	Main/Intermediate Rock Dumps
S3	Main/Intermediate Rock Dumps
FDU	Faro Creek Diversion, upstream end
FDL	Faro Creek Diversion
FCO	Old Faro Creek, upstream of Faro Valley Dump
A30	Flow to Main Pit from Faro Valley Dump
A25	Main Pit, northwest wall
SP5/6	Internal Surface Flow on Faro Rock Dump
NE1	North Seep to North Fork from Northeast Dumps
NE1	Central Seep to North Fork from Northeast Dumps
NE1	South Seep to North Fork from Northeast Dumps
NF1	Upstream side of rock drain
NF2	Downstream side of rock drain
W5	East Dump
W8	Upper Guardhouse Creek downstream of Northwest Dump
W10	Upper Guardhouse Creek upstream of Northwest Dump
GDHSECK	Guardhouse Creek at Intermediate Pond
IDSEEP	Intermediate Dam toe seep, south side
X7	Seep downstream of emergency tailings area
K8	Tributary of Rose Creek upstream of the site of the freshwater dam
Grum Corner	Tributary of Rose Creek upstream of the site of the freshwater dam
Anvil Cr	Anvil Creek above the confluence with the Pelly River

***Vangorda Mine Site:***

<u>Station</u>	<u>Location</u>
V1	Vangorda Creek upstream of Vangorda Pit
V2	Grum Creek upstream of confluence with Vangorda Creek
V2A	Grum Creek upstream of confluence with Moose Pond
V4	Shrimp Creek upstream of confluence with Vangorda Creek
V5	West Fork of Vangorda Creek at gravel pit
V6A	AEX Creek
VG Main	Main Stem of Vangorda Creek
V8	Lower Vangorda Creek at the footbridge
V14	Grum Rock Dump at North toe seep
V15	Grum Rock Dump at central toe seep
V16	Grum Rock Dump at South toe seep
V17A	Creek from Grum ore transfer pad
V19	Vangorda Pit northwest diversion ditch
V20	Vangorda Pit, northeast diversion ditch
LCD	Little Creek Dam Pond at old pumphouse
V22	Vangorda Pit at pumping barge

***Vangorda Mine Site (continued):***

<u>Station</u>	<u>Location</u>
V23	Grum Pit at Haul Road
V24	Influent to water treatment plant
V25	Effluent from clarification pond
V25BSP	Grum Interceptor Ditch below Sheep Pad Pond
V27	Main Stem of Vangorda Creek upstream of Shrimp Creek
V29	Vangorda Dump drain #2
V30	Vangorda Dump drain #3
V31	Vangorda Dump drain #4
V32	Vangorda Dump drain #5
V33	Vangorda Dump drain #6
V37	Vangorda Rock Dump, GW94-01
V38	Vangorda Rock Dump, GW94-02
V39	Vangorda Rock Dump, GW94-03
V40	Vangorda Rock Dump, GW94-04
P96-9	Grum Rock Dump
P01-01 to 03	Vangorda Rock Dump

SCHEDULE A, PART II  
MONITORING SCHEDULE LEGEND

Frequency:

C = Continuously  
 WD = Weekly when discharging  
 MD = Monthly when discharging  
 M = Monthly  
 SF = Spring and Fall  
 SSF = Spring, Summer and Fall  
 WS = Winter and Summer  
 Q = Quarterly

Parameters:

ICP-T = ICP Total Metals including all metals listed in the effluent quality standards specified in Part C of this licence.

ICP-D = ICP Dissolved Metals including all metals listed in the effluent quality standards specified in Part C of this licence.

Other = field pH, field temperature, field conductivity, total suspended solids, sulphate (SO<sub>4</sub>), ammonia (as N). For groundwater samples, "Other" also includes purge volume, purge rate, purge time and sampling time.

SCHEDULE A, PART III  
MONITORING SCHEDULE  
(FARO MINE SITE)

Station	Parameter				
	ICP-T	ICP-D	Other	Hardness	Flow/Level
X2	M	M	M	M	M
X3	M	M	M	M	-
X4	M	M	M	-	M
X5	WD	WD	WD	WD	WD
X5P	M	M	M	-	M
X11	WS	WS	WS	-	W
X12	WS	WS	WS	-	W
Weir 3	WS	WS	WS	-	W
X13	M	M	M	M	W
X14	WD/M	WD/M	WD/M	WD/M	C
X22B	M	M	M	-	M
X23	M	M	M	-	M
X26	MD	MD	MD	-	M
R1	WS	WS	WS	WS	WS
R3	WS	WS	WS	WS	WS
R4	WS	WS	WS	WS	WS
R5	WS	WS	WS	WS	WS
R6	WS	WS	WS	WS	WS
Faro Cr	M	M	M	-	-
R7	M	M	M	-	C
R8	M	M	M	-	-
R9	M	M	M	-	-
R10	M	M	M	-	-
X16	-	SF	SF	-	SF
X17	-	SF	SF	-	SF
X18	-	SF	SF	-	SF
X21-96	-	SF	SF	-	SF
X24-96	-	SF	SF	-	SF
X25-96	-	SF	SF	-	SF
P01-01to 11	-	SF	SF	-	SF
TH86-26	-	SF	SF	-	SF
BH1	-	SF	SF	-	SF
BH2	-	SF	SF	-	SF
BH4	-	SF	SF	-	SF
BH12	-	SF	SF	-	SF
BH13	-	SF	SF	-	SF
BH14	-	SF	SF	-	SF

Station	Parameter				
	ICP-T	ICP-D	Other	Hardness	Flow/Level
P96-6	-	SF	SF	-	SF
P96-7	-	SF	SF	-	SF
P96-8	-	SF	SF	-	SF
S1	-	SF	SF	-	SF
S2	-	SF	SF	-	SF
S3	-	SF	SF	-	SF
FDU	SF	SF	SF	-	SF
FDL	SF	SF	SF	-	SF
FCO	SF	SF	SF	-	SF
A30	SF	SF	SF	-	SF
A25	SF	SF	SF	-	SF
SP5/6	SF	SF	SF	-	SF
NE1	SF	SF	SF	-	SF
NE2	SF	SF	SF	-	SF
NE3	SF	SF	SF	-	SF
NF1	SF	SF	SF	-	SF
NF2	SF	SF	SF	-	SF
W5	SF	SF	SF	-	SF
W8	SF	SF	SF	-	SF
W10	SF	SF	SF	-	SF
GDHSECK	SF	SF	SF	-	SF
IDSEEP	SF	SF	SF	-	SF
X7	SF	SF	SF	-	SF
K8	M	M	M	M	-
Grum Corner	M	M	M	M	-
Anvil Cr	WS	WS	WS	-	-

SCHEDULE A, PART IV  
MONITORING SCHEDULE  
(VANGORDA MINE SITE)

Station	Parameter				
	ICP-T	ICP-D	Other	Hardness	Flow/Level
V1	Q	Q	Q	Q	Q
V2	M	M	M	M	M
V2A	M	M	M	-	M
V4	SSF	SSF	SSF	SSF	-
V5	M	M	M	M	Q
V6A	Q	Q	Q	Q	Q
VGMain	M	M	M	M	-
V8	M	M	M	M	C
V14	SF	SF	SF	-	SF
V15	M	M	M	-	M
V16	SF	SF	SF	-	SF
V17A	SF	SF	SF	-	SF
V19	SF	SF	SF	-	SF
V20	SF	SF	SF	-	SF
LCD	SF	SF	SF	-	M
V22	Q	Q	Q	-	M
V23	Q	Q	Q	-	M
V24	WD	WD	WD	-	WD
V25	WD	WD	WD	-	WD
V25BSP	WD/M	WD/M	WD/M	WD/M	WD/M
V27	SSF	SSF	SSF	SSF	-
V29	-	SF	SF	-	SF
V30	-	SF	SF	-	SF
V31	-	SF	SF	-	SF
V32	-	SF	SF	-	SF
V33	-	SF	SF	-	SF
V37	-	SF	SF	-	SF
V38	-	SF	SF	-	SF
V39	-	SF	SF	-	SF
V40	-	SF	SF	-	SF
P96-9	-	SF	SF	-	SF
P01-01 to 03	-	SF	SF	-	SF