

Table of Contents

1 Introduction..... 1-1

1.1 General..... 1-1

1.2 Report Organization..... 1-1

1.3 Project Description Update..... 1-2

2 Climate and Air Quality..... 2-1

2.1 Site Meteorological Station..... 2-3

2.2 Precipitation 2-3

2.2.1 Annual Precipitation Estimate from Precipitation Isoline Maps 2-3

2.2.2 Annual Precipitation Estimate from Regional and Wolverine Climate Stations. 2-3

2.2.3 Annual Precipitation Estimate from Water Balance 2-5

2.2.4 Monthly Precipitation Estimates from Annual Precipitation..... 2-6

2.2.5 Snowpack 2-6

2.3 Evaporation..... 2-8

2.4 Air Quality 2-11

2.4.1 Air Quality Study Area Definition..... 2-11

3 Surficial Geology and Vegetation..... 3-1

3.1 Surficial Geology 3-3

3.1.1 Terrain/Surficial Materials Study Area Definition 3-3

3.1.2 Glaciolacustrine and Borrow Pit Materials..... 3-3

3.1.3 Additional References..... 3-3

3.2 Permafrost..... 3-4

3.3 Vegetation..... 3-4

3.3.1 Vegetation Study Area Definition 3-4

4 Wildlife..... 4-1

4.1 Wildlife Study Area 4-5

4.2 Caribou..... 4-6

4.2.1 Wildlife Movement Corridors..... 4-6

4.2.2 Baseline Data 4-7

4.3 Moose..... 4-8

4.3.1 Habitat Availability..... 4-8

4.3.2 Moose Stratification Study 4-9

4.4 Wildlife and Project Interaction..... 4-9

4.4.1 Tailings Facility 4-10

4.4.1.1 Birds..... 4-10

4.4.2 Site Access..... 4-11

4.4.3 Tourism and Wildlife Experience..... 4-12

4.5 Hunting 4-12

5 Hydrology and Aquatic Resources..... 5-1

5.1 Regional Hydrometric Information..... 5-4

5.1.1 Peak Flow Analysis..... 5-5

5.1.2 Mean Monthly and Mean Annual Flow..... 5-9

5.1.3 Low Flow 5-12

5.2	Fisheries	5-16
5.2.1	Fisheries Study Area	5-16
5.2.2	Stream Crossing Mitigation Measures	5-16
6	Underground Mine	6-1
6.1	Geological Sampling Methodology	6-7
6.2	Mine Plan	6-9
6.2.1	Mining Method	6-9
6.2.2	Drift and Fill with Primary and Secondary Panels (DFPS)	6-11
6.2.3	Drift and Fill with Retreat Panels (DFRP)	6-12
6.2.4	Drift and Fill with Side Slash (DFSS)	6-12
6.3	Underground Water Quality Model	6-13
6.4	Hydrogeology	6-14
6.4.1	Introduction	6-14
6.4.2	Study Objectives	6-15
6.4.3	Field Methodology	6-15
6.4.3.1	Borehole Packer Testing Procedure	6-15
6.4.3.2	Vibrating Wire Piezometer Installation	6-17
6.4.4	Data Interpretation	6-17
6.4.4.1	Geological and Hydrogeological Observations	6-17
6.4.4.2	In-Situ Bedrock Permeability Test Results	6-19
6.4.4.3	Baseline Groundwater Conditions	6-21
6.4.5	Groundwater Quality Sampling	6-22
6.4.6	Conceptual Hydrogeological Model Development	6-25
6.4.7	Flownet Construction	6-27
6.4.8	Mine Inflow Prediction	6-28
6.4.9	Potential Impacts from Dewatering and Groundwater Recharge	6-30
6.4.9.1	Dewatering during Operations	6-30
6.4.9.2	Closure Considerations	6-32
6.4.9.3	Groundwater and Surface Water Quality Following Closure	6-32
6.4.10	Proposed Monitoring during Operation and Closure Periods	6-35
7	Tailings Facility	7-1
7.1	Introduction	7-7
7.2	Site Conditions	7-7
7.2.1	General	7-7
7.2.2	Geology	7-8
7.2.3	Seismicity	7-8
7.2.4	Climate and Hydrology	7-16
7.2.5	Groundwater	7-17
7.2.6	Water Quality	7-18
7.2.6.1	Surface Water	7-18
7.2.6.2	Groundwater	7-21
7.3	Geotechnical Characterization	7-23
7.3.1	Site Investigations	7-23
7.3.2	Laboratory Testing	7-28
7.4	Geochemical Characterization	7-29

7.4.1	Borrow and Construction Materials.....	7-29
7.4.2	Tailings and Supernatant Water Geochemistry	7-31
	7.4.2.1 Sample Preparation, Acid Base Accounting and Mineralogy	7-31
	7.4.2.2 Shake Flask Tests.....	7-36
	7.4.2.3 Tailings Supernatant, Aging and Subaqueous Column Tests.....	7-37
	7.4.2.4 Acute Lethality Testing of Tailings Supernatant	7-42
	7.4.2.5 Humidity Cell Testing.....	7-43
7.4.3	DMS Float and Waste Rock	7-43
7.5	Design Criteria.....	7-47
	7.5.1 General.....	7-47
	7.5.2 Dam Failure Consequence Classification	7-48
	7.5.3 Design Earthquakes	7-50
	7.5.4 Design Floods	7-50
	7.5.5 Design “Allowable” Seepage Assessment.....	7-51
7.6	Tailings Impoundment.....	7-52
	7.6.1 General Layout.....	7-52
	7.6.2 Storage Capacity	7-53
	7.6.3 Deposition Strategy and Staged Development	7-54
	7.6.4 Liner Design.....	7-55
	7.6.5 Water Balance.....	7-56
	7.6.6 Water Quality Management.....	7-59
	7.6.7 Seepage Recovery Facility.....	7-59
7.7	Tailings Dam Design	7-60
	7.7.1 Dam Design Section	7-60
	7.7.2 Geotechnical Parameters.....	7-60
	7.7.3 Slope Stability Analyses	7-61
	7.7.4 Dam Foundation Liquefaction Assessment	7-63
	7.7.5 Monitoring and Environmental Management.....	7-64
7.8	Construction.....	7-65
7.9	Water Management.....	7-67
	7.9.1 General.....	7-67
	7.9.2 Diversion and Seepage Collection Ditches.....	7-67
	7.9.3 Flood Handling and Spillways.....	7-70
7.10	Closure	7-71
	7.10.1 General.....	7-71
	7.10.2 Geochemical Stability and Surface Water Quality	7-71
	7.10.3 Dam Safety at Closure	7-72
	7.10.4 Decommissioning of Water Management Structures	7-72
	7.10.5 Monitoring	7-73
8	Waste Rock Management.....	8-1
8.1	General Site and Structure Description.....	8-3
8.2	Geotechnical Assessments	8-3
8.3	Pad Construction Details.....	8-4
	8.3.1 Surface Preparation.....	8-4
	8.3.2 Liner Installation.....	8-4
	8.3.3 Water Diversion.....	8-6

8.3.4	Collection Sump.....	8-6
8.4	Quality Assurance/Quality Control Plans and Testing Protocols.....	8-7
8.5	Operational Details	8-8
8.6	Closure Plans	8-10
9	Site Water Management and Treatment	9-1
9.1	Surface Water Quality and Related Aquatic Issues	9-6
9.1.1	Revised Compliance Point in Go Creek	9-6
9.1.2	Baseline Water Chemistry at Compliance Point.....	9-7
9.1.3	Additional Aquatic Issues in Wolverine and Go Creeks	9-9
9.1.4	Water Quality Objectives.....	9-11
9.2	Site Water Management.....	9-13
9.3	Site Water Balance.....	9-15
9.3.1	Operations.....	9-15
9.3.2	Closure	9-17
9.4	Water Treatment	9-20
9.4.1	Tailings Supernatant Chemistry.....	9-20
9.4.2	Treatment Requirements and Proposed Discharge Limits.....	9-21
9.4.3	Predictions of Water Quality in Go Creek During Discharge	9-22
9.4.4	Treatment Process.....	9-24
9.5	Potential Effects on Aquatic Communities of Go Creek	9-25
9.6	Monitoring and Mitigation Plans	9-26
9.6.1	Go Creek	9-26
10	Yukon Conservation Society Comments and YZC Responses	10-1
10.1	General Comments.....	10-1
10.2	Project Components	10-1
10.2.1	Overview of Project Components, Design Criteria and General Layout.....	10-1
10.2.2	Humidity Cells.....	10-2
10.2.3	Post-Closure Mine Water Quality Estimate.....	10-2
10.2.4	Conclusions.....	10-3
10.2.5	Dense Media Separation Operations.....	10-3
10.2.6	Waste Rock	10-3
10.2.7	Tailings Storage Facility	10-3
10.2.8	Water Treatment Plant - Selenium.....	10-4
10.2.9	Water Treatment Plant Sludge	10-4
10.3	Biophysical Components	10-5
10.3.1	Climate Project Effects	10-5
10.3.2	Cumulative Climate Effects.....	10-5
10.3.3	Air Quality Project Effects.....	10-6
10.3.4	Operations.....	10-6
10.3.5	Residual Project Effects and Significance	10-6
10.3.6	Terrain, Surficial Geology and Soils	10-7
10.3.7	Surficial Materials Construction	10-7
10.3.8	Permafrost.....	10-7
10.3.9	Soil Erosion.....	10-8
10.3.10	Natural Terrain Hazards.....	10-8

10.3.11	Decommissioning - Permafrost.....	10-8
10.3.12	Surface Water Hydrology - Project Effects - Mine Dewatering Affecting Flows in Wolverine and Go Creeks	10-9
10.3.13	Go Creek.....	10-9
10.3.14	Residual Project Effects.....	10-9
10.3.15	Surface Water and Sediment Quality.....	10-10
10.3.16	Results - Cadmium (Cd)	10-10
10.3.17	Wolverine Lake.....	10-11
10.3.18	Construction-Wolverine Creek	10-11
10.3.19	Mitigation Measures for Effects on Water and Sediment Quality.....	10-11
10.3.20	Closure - Treatment Plant Effluent – Go Creek.....	10-11
10.3.21	Groundwater Discharge – Wolverine Creek at Closure	10-12
10.3.22	Tributaries along the Access Road	10-13
10.3.23	Construction.....	10-13
10.3.24	Mitigation Measures for Effects on the Fish Resources	10-13
10.3.25	Vegetation.....	10-14
10.3.25.1	General Comments.....	10-14
10.3.25.2	Scope of Assessment.....	10-14
10.3.25.3	Mitigation Measures	10-15
10.3.26	Wildlife	10-16
10.3.26.1	Caribou.....	10-17
10.3.26.2	Moose.....	10-19
10.3.26.3	Grizzly Bear.....	10-20
10.3.26.4	Beaver	10-22
10.3.26.5	Lynx and Snowshoe Hare	10-23
10.3.26.6	American Marten	10-24
10.3.26.7	Trumpeter Swan.....	10-24
10.3.26.8	Non-traditional Hunting, Guide Outfitting and Trapping.....	10-25
11	Response to Public Consultation Comments.....	11-1
11.1	Ross River Dena Council Comments (Review of Environmental Assessment Report for Wolverine Project).....	11-1
11.1.1	Cover Letter	11-1
11.1.2	General Concerns with EAR.....	11-1
11.1.3	Environmental Effects of EAR.....	11-2
11.1.3.1	Wildlife in LSA.....	11-2
11.1.3.2	Fish in LSA.....	11-8
11.1.3.3	Water Quality.....	11-9
11.1.4	Section 2.8.2 Tailings Storage Facility, pages 2-75 to 2-76.....	11-10
11.1.5	Trapping Concerns.....	11-12
11.1.6	Archeological.....	11-12
11.1.7	Cumulative Impacts	11-13
11.1.8	Local Employment.....	11-14
11.1.9	Effects on Traffic and Safety (construction and operation).....	11-15
11.1.10	Effects on Traditional Lifestyles.....	11-15
11.2	Community Questions and Concerns Raised during Meetings and Interviews.....	11-16
11.2.1	Ross River.....	11-16

11.2.2	Watson Lake	11-26
11.2.3	Further Questions and Concerns raised during Interviews with Ross River Dena Land Users of the Wolverine Lake Area in January 2006.....	11-29
12	Reference	12-1

List of Tables

Table 2-1	Climate and Air Quality Table of Conformance	2-2
Table 2-2	Comparison of Measured Monthly Precipitation at Wolverine Climate Station and at Watson Lake	2-4
Table 2-3	Mean Monthly Precipitation at Wolverine Estimated from Regional Monthly Proportion of Annual Rainfall.....	2-6
Table 2-4	Mean and Standard Deviation of Observed Lake Evaporation (mm) Northwestern Canada, 1951-1980.....	2-10
Table 3-1	Surficial Geology and Vegetation Table of Conformance	3-2
Table 4-1	Wildlife Table of Conformance.....	4-2
Table 4-2	Wildlife Buffer Distances	4-5
Table 4-3	Linear Disturbances in the Wolverine Regional Study Area.....	4-11
Table 5-1	Hydrology and Aquatic Resources Table of Conformance	5-2
Table 5-2	WSC Gauges used for Revised Flow Analysis.....	5-4
Table 5-3	Estimated 2-Year to 500-Year Instantaneous Peak Flow (m ³ /s) for WSC Gauges	5-5
Table 5-4	Expected Instantaneous Peak Flow (m ³ /s) by Return Period for Specified Watersheds within the Wolverine Project Area	5-8
Table 5-5	Observed Mean Monthly and Mean Annual Flow (m ³ /s) and Mean Annual Yield by Watershed	5-10
Table 5-6	Expected Mean Monthly and Mean Annual Flow (m ³ /s) by Drainage for Wolverine Project Area	5-13
Table 5-7	Expected 7-day Summer Low Flows (m ³ /s) For Wolverine Project Area.....	5-15
Table 5-8	Expected 7-day Winter Low Flows (m ³ /s) for the Wolverine Project Area	5-15
Table 6-1	Underground Mine Table of Conformance	6-2
Table 6.1-1	Major Lithology Types for Wolverine Deposit with Rock Type Numbering	6-8
Table 6.1-2	Original Listing of Major Lithology Types for Wolverine Deposit	6-8
Table 6.2-1	Selection of Mining Method by Ore Thickness.....	6-11
Table 6.3-1	Predicted Mass-Loading and Base Case Concentrations at Closure	6-14
Table 6.4-1	Summary of Borehole Information.....	6-18
Table 6.4-2	Summary of Notable Features from Core Log Descriptions	6-19
Table 6.4-3	Summary of Deep Borehole Permeability Testing.....	6-20
Table 6.4-4	Summary of Piezometer Installations and Initial Groundwater Elevations.....	6-21
Table 6.4-5	Summary of Field Groundwater Quality Measurements.....	6-22
Table 6.4-6	Summary of Select Mine Groundwater Quality Parameters from Boreholes and Underground.....	6-24
Table 6.4-7	Summary of Inferred Hydrostratigraphic Units - Mine Area	6-25

Table 6.4-8	Predicted Water Quality in Wolverine Creek at Closure During Summer and Winter	6-33
Table 6.4-1	Tailings Facility Table of Conformance.....	7-2
Table 7.2-1	Probabilistic Evaluation of Peak Horizontal Ground Acceleration at Project Site.....	7-14
Table 7.2-2	Deterministic Evaluation of Peak Horizontal Ground Acceleration at Project Site	7-16
Table 7.2-3	Ratios of Dry and Wet Year Annual Precipitations and Mean Monthly Runoff Flows ...	7-16
Table 7.2-4	Monthly Precipitation and Runoff Distribution.....	7-16
Table 7.2-5	Expected Mean Monthly and Annual Flows (m ³ /s) for Selected Stations.....	7-17
Table 7.2-6	Summary of Piezometric Elevations in Tailings Impoundment Area	7-17
Table 7.2-7	Summary of Baseline Groundwater Flow for Selected Locations.....	7-18
Table 7.2-8	Background Surface Water Quality in Tailings Impoundment Area.....	7-20
Table 7.2-9	Background Groundwater Quality in Tailings Impoundment Area	7-22
Table 7.3-1	Summary of Large and Standard Penetrometer Test Results	7-25
Table 7.3-2	Summary of Falling-Head Permeability Test Results	7-25
Table 7.3-3	Summary of Packer Permeability Test Results.....	7-27
Table 7.3-4	Summary of Falling-Head Permeability Test Results – Monitoring Wells.....	7-27
Table 7.3-5	Summary of Packer Permeability Test Results – Monitoring Wells	7-28
Table 7.3-6	Summary of Engineering Properties Determined from Laboratory Tests on Dam Fill, Tailings, DMS Float and Waste Rock	7-28
Table 7.4-1	Summary of Metal Leachate Analyses for Borrow Materials	7-29
Table 7.4-2	ABA Results For Dam Borrow Materials	7-30
Table 7.4-3	Number of Tailings Tests by Geochemical Test Method.....	7-31
Table 7.4-4	Mineral Assemblages and Modal Abundances by Optical Microscopy (wt. %)... ..	7-32
Table 7.4-5	Elemental Concentrations Greater than 5X Crustal Abundance.....	7-33
Table 7.4-6	Tailings Acid Base Accounting Results	7-35
Table 7.4-7	Shake Flask Extraction Test Results.....	7-36
Table 7.4-8	Tailings Supernatant Chemistry	7-37
Table 7.4-9	Summary of Tailings Aging Tests at 120 Days.....	7-40
Table 7.4-9	Summary of Tailings Aging Tests at 120 Days (cont'd).....	7-41
Table 7.4-10	Summary of Subaqueous Column Results after 8 Weeks	7-41
Table 7.4-11	Tailings Supernatant Acute Lethality Results for <i>Daphnia Magna</i>	7-42
Table 7.4-12	Tailings Supernatant Acute Lethality Results for Rainbow Trout.....	7-42
Table 7.4-13	Preliminary Humidity Cell Results for Combined OD Composite Tailings	7-43
Table 7.4-14	DMS Whole Rock Analysis (%).	7-44
Table 7.4-15	DMS Float Rock Acid Base Accounting Results	7-44
Table 7.4-16	Summary of Anomalous elements in DMS Float Rock	7-45

Table 7.4-17	Summary of Shake Flask Tests in DMS Float Rock	7-46
Table 7.5-1	Summary of Design Criteria.....	7-47
Table 7.5-2	Estimated Dam Breach Flood Peaks Downstream of Tailings Dam	7-49
Table 7.5-3	Selected Flood Design Criteria for Water Management Facilities	7-51
Table 7.5-4	Summary of Concentrations of Parameters of Potential Concern and “Tolerable” Seepage Rates	7-52
Table 7.6-1	Tailings and Coarse Waste Storage Volumes.....	7-53
Table 7.6-2	Summary of Seepage Analyses for Ultimate Tailings Dam.....	7-55
Table 7.6-3	Tailings Pond Annual Water Balances with Diversion Ditches	7-58
Table 7.6-4	Tailings Pond Annual Water Balances Assuming Diversion Ditches Were Not in Place	7-58
Table 7.7-1	Summary of Material Properties Used in Seepage and Slope Stability Analyses	7-61
Table 7.7-2	Summary of Safety Factors for Tailings Dam.....	7-61
Table 7.7-3	Dam Foundation Liquefaction Assessment Based on LPT and SPT Data	7-63
Table 7.7-4	Summary of Tailings Facility Monitoring Program	7-65
Table 7.8-1	Bill of Quantities for the Dam and Associated Water Management Structures	7-66
Table 7.9-1	Tailings Pond and Seepage Recovery Ponds Free Water Surface Areas.....	7-68
Table 7.9-2	Estimated Catchment Areas, Design Flood Flows and Freeboards.....	7-69
Table 8-1	Waste Rock Table of Conformance.....	8-2
Table 8-2	Temporary Waste Rock and Ore Facility - Catchment Areas and Design Flows	8-6
Table 8-3	2005 Waste Rock Pad Sump Monitoring	8-7
Table 9-1	Site Water Management Table of Conformance	9-2
Table 9-2	Summary of Baseline Water Quality (mg/L) at the Compliance Point in Go Creek.....	9-9
Table 9-3	Summary of Water Quality Objectives (mg/L) for the Compliance Point in Go Creek...	9-13
Table 9-4	Summary of Expected Tailings Supernatant Quality	9-21
Table 9-5	Summary of Proposed Discharge Limits (mg/L) from the Water Treatment Plant/Retention Pond.....	9-22
Table 9-6	Summary of Predicted Concentrations (mg/L) of Key Parameters at the Compliance Point in Go Creek in June as Compared to Water Quality Objectives	9-23
Table 9-7	Summary of Predicted Concentrations (mg/L) of Key Parameters at the Compliance Point in Go Creek in July as Compared to Water Quality Objectives	9-23
Table 9-8	Effluent Quality from Different HDS Plants (mg/L).....	9-24
Table 10-1	Linear Disturbances in the Wolverine Regional Study Area.....	10-21
Table 10-2	Beaver Habitat Overlap with Other Wildlife Species (from L. Foote, 2005).....	10-22
	Proposed Mitigation Practices for Bear Issues	11-7
	Description of Sediment and Erosion Techniques	11-21

List of Figures

Figure 1-1	Overall Project Layout (Figures Section)	1-2
Figure 1-2	Industrial Complex Area Layout (Figures Section).....	1-2
Figure 1-3	Industrial Complex Sections (Figures Section)	1-2
Figure 1-4	Process Plant Water Balance Flowsheet (Figures Section)	1-2
Figure 1-5	Tailings/Reclaim Pipeline Plan, Profile and Section (Figures Section)	1-3
Figure 2-1	Monthly Precipitation at Watson Lake (mm) vs. Monthly Precipitation at Wolverine (mm)	2-4
Figure 2-2	Observed Annual Precipitation at Regional Stations Plotted by Elevation	2-5
Figure 2-3	Hamon Equations	2-8
Figure 3-1	Surficial Materials Distribution in the Wolverine Project Area (Figures Section).....	3-3
Figure 4-1	Finlayson Caribou Herd, Surveys 1982-2004 (Figures Section).....	4-6
Figure 4-2	Calf Recruitment of the Finlayson Caribou Herd.....	4-8
Figure 5-1	Regional Hydrologic Stations (Figures Section)	5-4
Figure 5-2	Peak Instantaneous Discharge (m ³ /s) by Drainage Area for Q2, Q10, Q50 and Q100 Periods	5-7
Figure 5-3	Mean Monthly Flows (m ³ /s) for Stations near the Wolverine Project (Figures Section) ...	5-9
Figure 5-4	Plots of Mean Monthly Discharge (m ³ /s) vs. Drainage Area (km ²) for Selected Months	5-11
Figure 5-5	Summer and Winter 7-Day Low Flow (m ³ /s) for Selected Return Periods.....	5-14
Figure 6.2-1	Revised Mine Material Balance (Mt)	6-9
Figure 6.2-2	Wolverine Mine Development Plan (Figures Section).....	6-10
Figure 6.2-3	Life of Mine, Elevation Looking Northwest (Figures Section).....	6-10
Figure 6.2-4	Status of Mine End of 2010 (Figures Section)	6-10
Figure 6.2-5	Status of Mine End of 2015 (Figures Section)	6-10
Figure 6.2-6	Status of Mine End of 2018 (Figures Section)	6-10
Figure 6.2-7	Status of Mine End of Mining (Figures Section).....	6-10
Figure 6.2-8	Typical Stopping Level Sequence (Figures Section).....	6-11
Figure 6.2-9	Typical Stopping Level Detail (Figures Section)	6-11
Figure 6.4-1	Groundwater Study Plan (Figures Section)	6-15
Figure 6.4-2	Conceptual Hydrogeologic Model Plan (Figures Section)	6-18
Figure 6.4-3	Hydraulic Conductivity versus Depth (Figures Section).....	6-20
Figure 6.4-4	Measured Potentiometric Groundwater Elevations in Mine Area Piezometers – Precipitation (Figures Section)	6-22
Figure 6.4-5	Measured Potentiometric Groundwater Elevations in Mine Area Piezometers – Sump Flow (Figures Section).....	6-22

Figure 6.4-6	Conceptual Hydrogeologic Model Cross-Section A-A (Pre-Mining) (Figures Section)..	6-27
Figure 6.4-7	Conceptual Hydrogeologic Model Cross-Section B-B (Pre-Mining) (Figures Section) ..	6-27
Figure 6.4-8	Conceptual Hydrogeologic Model Cross-Section A-A' (Operating) (Figures Section)...	6-28
Figure 6.4-9	Conceptual Hydrogeologic Model Cross-Section B-B' (Operating) (Figures Section) ...	6-29
Figure 6.4-10	Mine Inflow Estimate versus Drift Length (after Goodman <i>et al.</i> , 1965) (Figures Section).....	6-30
Figure 6.4-11	Days to Drain Pore Water Above Mine versus Inflow Rate (Figures Section).....	6-30
Figure 6.4-12	Potential Groundwater Depression Plan (Figures Section)	6-31
Picture 7.2-1	Photograph of Tailings Facility General Area.....	7-8
Figure 7.2-1	Surficial and Bedrock Geology Plan (Figures Section).....	7-8
Figure 7.2-2	Regional Seismicity	7-10
Figure 7.2-3	Location Map of Recent Regional Epicentres	7-11
Figure 7.2-4	Seismogenic Zonal Map – 2005 NBCC H Seismicity Model	7-12
Figure 7.2-5	Characteristics of Tintina Source Zone	7-13
Figure 7.2-6	Peak Horizontal Ground Acceleration at Various Probability of Annual Exceedance.....	7-14
Figure 7.2-7	Deaggregation of Seismic Hazard for Peak Horizontal Ground Acceleration 10,000 year Return Period.....	7-15
Figure 7.2-8	Location Map of Surface Water Monitoring Stations, Groundwater Monitoring Wells and Catchment Boundary	7-19
Figure 7.2-9	Piper Trilinear Plot of Background Groundwater Chemistry	7-23
Figure 7.3-1	Site Investigation Plan (Figures Section)	7-24
Figure 7.3-2	Geologic Cross Sections (Figures Section)	7-24
Figure 7.4-1	Variation in Thiosalt concentration over time	7-38
Figure 7.4-2	Variation in pH over time.....	7-38
Figure 7.4-3	Variation in Dissolved Zinc Concentration Over Time.....	7-39
Figure 7.4-4	Variation in Selenium Concentration Over Time	7-39
Figure 7.4-5	Variation in Cadmium Concentration Over Time	7-40
Figure 7.6-1	Stage Storage Curve – Tailings Impoundment.....	7-54
Figure 7.6-2	Starter Impoundment – Tailings and DMS Placement Plan (Figures Section)	7-54
Figure 7.6-3	Final Impoundment – Closure Plan (Figures Section).....	7-54
Figure 7.6-4	Starter Impoundment – Typical Section (Figures Section)	7-54
Figure 7.6-5	Ultimate Impoundment – Typical Section (Figures Section)	7-54
Figure 7.6-6	Go Creek and Ditch A Diversion Structures (Figures Section).....	7-55
Figure 7.6-7	Starter Dam Excavation and Fill Plan (Figures Section).....	7-56
Figure 7.6-8	Ultimate Dam Excavation and Fill Plan (Figures Section).....	7-56

Figure 7.6-9	Impoundment – Excavation and Fill – Typical Sections (Figures Section)	7-56
Figure 7.6-10	Water Balance Schematic	7-57
Figure 7.7-1	Tailings Dam Plan and Sections (Figures Section)	7-60
Figure 7.7-2	Tailings Dam – Stability Analyses for Starter Dam and Ultimate Dam Sections.	7-62
Figure 7.9-1	Diversion Ditches and Spillways – Plan and Typical Section (Figures Section)	7-67
Figure 8-1	Waste Rock Pad Plan and Cross-Section (Figures Section)	8-1
Figure 8-2	Plant Site and Waste Rock Pile Site Investigation Plan (Figures Section).....	8-4
Picture 8-1	Grading, Contouring and Proof-Rolling the Till-Like Surface.....	8-4
Picture 8-2	Installation of the Geotextile Layer and Enviro Liner®	8-5
Picture 8-3	Completion of Enviro Liner® Installation.....	8-5
Picture 8-4	Water Collection Sump at the Southeast Corner of the Waste Rock Pad.....	8-7
Picture 8-5	Haulage of Waste Rock on to the Waste Rock Pad.....	8-9
Picture 8-6	Waste Rock Pad, August 19, 2005	8-9
Picture 8-7	Waste Rock Pad, August 19, 2005	8-9
Figure 9-1	Base Map of Wolverine Project in Relation to Go Creek and Wolverine Creek and Depicting Important Water Management Features.....	9-7
Figure 9-2	Schematic of Key Components of Wolverine Project Water Management and Water Balance	9-14
Figure 9-3	Wolverine Project Water Balance Schematic for Operations.....	9-16
Figure 9-4	Monthly Balance of Inflows and Losses (not including water treatment) for Wolverine Project Average Year Conditions	9-17
Figure 9-5	Schematic of Closure Water Balance for Average Year Flows During the First 3 Years Following Cessation of Operations	9-18
Figure 9-6	3-Dimensional Rendering of Post-Closure Tailings Facility.....	9-19
Figure 9-7	Annual Fresh Water Inflows to the Tailings Impoundment for Average Year Post-Closure without Diversions.....	9-19
Figure 9-8	Post-Closure Water Balance for Passive Discharge to Go Creek.....	9-20
Figure 9-9	Key Features of the Water Treatment-Discharge Monitoring System for Go Creek	9-27

Abbreviations

ABA	Acid Base Accounting
AES	Atmospheric Environment Service
ARD	Acid Rock Drainage
CCME	Canadian Council for Ministers of the Environment
Cd	Cadmium
cm	centimeter
CO ₂	Carbon dioxide
COSEWIC	Committee on the Status of Endangered Wildlife in Canada
DFPS	Drift and Fill with Primary and Secondary Panels
DFRP	Drift and Fill with Retreat Panels
DFSS	Drift and Fill with a Side Slash
DMS	Dense Media Separation
EAR	Environmental Assessment Report
EPP	Environmental Protection Plan
EXCP	Calcite Pyrite Exhalite
FCH	Finlayson caribou herd
GIS	Geographic Information System
GPS	Global Positioning System
HDPE	high density polyethylene
HYDAT	hydrometric data
km	kilometre
LFA	Low Flow Frequency Analysis
LSA	local study area
m	meter
m ²	metres squared
mm	millimeter
MMER	Metal Mining Effluent Regulation
NH ₃	Ammonia
NRCan	Natural Resources Canada
NWT	Northwest Territories
QA/QC	Quality Assurance/Quality Control
RCH	Robert Campbell Highway
RMA	Riparian Management Area
RQD	Rock Quality Designation
RRDC	Ross River Dena Council
RSA	regional study area
SARA	Species at Risk Act
Se	Selenium
SWE	snowpack water equivalent
TEM	Terrestrial Ecosystem Mapping
tpd	tonnes per day
TSS	total suspended solids
UFVCI	uniform flow velocity cap intake
UTM	Universal Transverse Mercator
VECC	valued ecosystem and cultural component
VW	vibrating wire

WPP.....	Wildlife Protection Plan
WQC.....	Water Quality Criteria
WSC.....	Water Survey of Canada
YCS.....	Yukon Conservation Society
YTG.....	Yukon Territorial Government
YZC.....	Yukon Zinc Corporation