1987 EXPLORATION PROJECT

YUKON EXPLORATION INCENTIVES PROGRAM

DESIGNATION NUMBER

EIP 87021

November 1987

. Widmann P. Eng.

SPRINGMOUNT OPERATING COMPANY LTD.

1987 EXPLORATION PROJECT

EXPLORATION INCENTIVES PROGRAM DESIGNATION

NUMBER - EIP 87021

Report on the No. 5 X-Trench & No. 6 Trench

A. General

The Thunderbird M.C. which borders the "Greta" Claim on which a high grade Silver Lode was mined in the early fifties and which is also located on Strike (N.E.) of the Bellekeno Vein System, was selected for examination due to its favourable location mentioned above.

The Trench is located on the South Slope of Keno Hill; an area which was never extensively prospected due to the existence of (1) heavy overburden which ranges from 10 ft. to 40 ft., (2) the presence of a 10 ft. to 20 ft. thick band of Schist which underlies a top layer of thin bedded Quartzites and minor Schist Bands, which ranges in thickness from 20 ft. to 50 ft.

It is believed, that it is this thick Band of Schist which prevented the mineralization of the Vein Faults to reach the surface, making it extremely difficult to assess or even to recognize a Vein Fault after removal of the overburden.

Mineralization reached the surface only at places where this Schist Band is comparatively thin (3 ft. to 5 ft.).

B. Veins

The Vein Faults on the South Slope of Keno Hill are mainly of the transverse variety, i.e. striking from just West of North to 40 degrees Northeast, the predominant Dip being Southeast. Some known veins on Keno Hill have a "Reverse Dip" - i.e. Northwest.

The Vein Faults are offset by "Post-Mineral-ization Cross Faults" as well as numerous flat dipping Bedding Plane Faults. The ore deposits in the Vein Faults are localized structurally in the following sites:

- (1) at the junction of Vein Faults
- (2) at the junction of a Vein Fault and subsidiary fractures (splits).
- (3) in massive Quartzites and Greenstones.

C. Trenching

1. No. 5 X-Trench

This Trench was excavated as a "Side-Cut" and was started at elevation 3720. It is located approx. at 1100 North section with an East-West orientation between 950 ERL and 1200 ERL.

At elevation 3640 and 1140 ERL a weak Vein Fault appeared. This Vein Fault which has a North-South orientation showed at this elevation only slight mineralization. At elevation 3630 another weak Vein Fault appeared at 1050 ERL & 900 North section with the same North-South orientation.

The No. 5 X-Trench was excavated to elevation 3600, when it was decided to further investigate the Vein Fault at 1140 ERL, since this Vein Fault appeared to be slightly stronger than the one at 1050 ERL.

To accomplish this, a longitudinal Trench (No. 6 Trench) was started.

2. No. 6 Trench

This Trench was excavated on Strike and was carried down to elevation 3570 when excavation had to be suspended since the Dip of the Vein brought it too close to the West Wall of the Trench.

The Vein which carried initially only vein-gouge and Siderite, started to carry at elevation 3580 minor amounts of Galena. It is hoped, that this Trench can be widened and deepened at a later date in order to investigate this Vein at depth.

In the course of the above excavations, the following quantities of materials were removed from the trenches:

Overburden - 19,016 m³

Bedrock - 29,346 m³

Total Material Excavated - 48,362 m³

Equipment used:

- 1 D8K Caterpillar with Ripper
- 1 966 Caterpillar Loader
- 1 Gardener Denver Air-Track
- 1 Gardener Denver 350 Compressor

 Approximately 15% of the Bedrock had to be broken by
 drilling and blasting prior to removal from the Trenches.

 A total of 425 6 ft. holes were drilled and blasted.

D. Engineering & Supervision

The existing Survey and Geological Grid was extended to cover the Sites of the Trenches, with a precision of 1: 10,000, the Trenches were surveyed and a plan covering the Trench Areas was drawn up. The Project required the presence of a Supervisor on a daily basis for 4 hours per day.

E. Expenditures

All equipment used at the Project is wholly owned by Springmount Operating Company Ltd. and all work was carried out by Company Employees. The Company is a duly registered Yukon Company and all Employees are Yukon residents.

The Company has no "outside" suppliers, i.e. all purchases are either made in Mayo or in Whitehorse.

The expenses incurred for this Project are as follows:

D8K Caterpillar: 935 hrs. @ \$139.05 = \$130,011.75
966 C Caterpillar Loader: 582 hrs @ \$80.70 = 46,967.40
Drilling & Blasting: 2550 L.F.@ \$3.50/ft.= 8,925.00
Survey Crew: 15 days @ \$00/day = 6,000.00
Engineering: 8 days @ \$400/day = 3,200.00
Supervision: 720 hrs @ \$30/hr. = 21,600.00
Total Expenditures = \$216,704.15

Total Volume Excavated = 48,362 m³

Cost per m³ = 216,704.15/48,362 = \$4.48

Start of Project - May 1st 1987

Completion of Project - October 30th 1987

Number of Manhours = 2,813

PROJECT: EIP 87021

BREAKDOWN OF CREW AND HOURS WORKED

NAME	D8-Cat	966 Loader	Drill & Blast	Supervision	Survey & Engineering	TOTAL
B. Rooney	662	114				776
D. Pavlowych		153	80			233
L. Roy	273	315				588
M. Swizinski			150	720		870
N. Kervin					162	162
F. Widmann					184	184
,				1.		
					<u> </u>	
						-
					,	
						<u> </u>
						·
			<u>'</u>			
TOTAL	935	582	230	720	346	2813

BREAKDOWN OF OPERATING COST/HOUR FOR D8-K CATERPILLAR TRACTOR

Ownership	\$	20.80
Labor (Loaded)		25.00
Fuel		25.00
Lube - Filters & Grease		5.00
Welding - Wear Plates & Small repairs		5.00
Consumables - Cutting Edges, Corner Bits,		
Ripper Tips. Bolts, Nuts & Pias etc.		10.00
1500 hr. Undercarriage - Turn Pins		
Segments, Labor & Freight		3.50
3000 hr. Undercarriage Complete		15.00
Freight to Whitehorse & Return for		
Undercarriage Overhaul		1.00
6000 hr. Driveline Overhaul		7.50
12000 hr. Replacement -		
\$250,000. Less \$50,000. Trade In		16.75
Insurance		3.50
Mobilization & Demobilization		1.00
TOTAL COST PER HOUR	\$1	139.05

BREAKDOWN OF OPERATING COST/HOUR FOR 966 C CATERPILLAR LOADER

Ownership	\$12.50
Labor (Loaded)	25.00
Fuel	15.00
Lube, Filters & Grease	2.50
Small Repairs	2.50
Tires	3.20
Consumables (Bucket Teeth. Etc.)	2.00
6000 hr. Drive Train, Pins & Bushings	5.00
Replacement 12000 hr.	10.00
Mobilization & Demobilization	1.00
Insurance	2.00
TOTAL COST PER HOUR	\$80.70



